Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: TBD

Project Title: Montebello Hills Recycled Water Pipeline and Pump Station Project

Lead Agency: Central Basin Municipal Water District (CBMWD)

Contact Name: Roman Gonzalez

Email: romang@centralbasin.org Phone Number: 323-201-5541

Project Location: Montebello, Los Angeles County
City *County*

Project Decription (Proposed actions, location, and/or consequences).

The project would involve construction and operation of approximately 2,600 linear feet of a 16-inch recycled water pipeline and a pump station with a peak demand capacity of 1,825 gallons per minute. The proposed pipeline would connect to CBMWD's existing Southeast Water Reliability Project pipeline at the intersection of Lincoln Avenue and Montebello Boulevard. Beginning at this intersection, the pipeline would extend north along Montebello Boulevard to the intersection of Montebello Boulevard and Jefferson Boulevard. At this intersection, the pipeline would proceed to the east and connect to the proposed pump station. The pump station would consist of a concrete foundation and a pre-fabricated wood building that would enclose steel or cast iron pumps and steel pipeline. The pump station building would be approximately 252 square feet and approximately 14 feet in height. The pump station would include an approximately 15-foot wide, 100-foot long, gated access driveway off Montebello Boulevard and three parking spaces. Recycled water conveyed by the proposed pipeline and pump station would be supplied by the Sanitation Districts of Los Angeles County (LACSD) and delivered to the Montebello Hills Specific Plan area for construction purposes, dust control, and landscaping irrigation. The maximum amount of recycled water delivered temporarily would be approximately 446 acre-feet per year. In the future, the maximum amount of recycled water delivered would be reduced to 240 acre-feet per year. The recycled water supplied by the LACSD is part of the existing recycled water supply and would not cause a decrease in flow in any portion of a watercourse.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The IS-MND identifies potential impacts to biological resources and land use and planning as less than significant with mitigation incorporated to address impacts to coastal California gnatcatcher and nesting birds. The IS-MND identifies potential impacts to cultural resources as less than significant with mitigation incorporated related to the unanticipated discovery of cultural resources. The IS-MND identifies potential impacts to geology/soils as less than significant with mitigation incorporated for paleontological resources; monitoring is required. The IS-MND identifies potential impacts to hazards and hazardous materials as less than significant with mitigation incorporated and requires a Hazardous Materials Management and Spill Control Plan, soil sampling and disposal, a contaminated soil contingency plan, on-site monitoring of areas of suspect contamination, designation of an alternative emergency evacuation route, and fire prevention measures. The IS-MND identifies potential impacts to hydrology/water quality as less than significant with mitigation incorporated and requires a Hazardous Materials Management and Spill Control Plan. The IS-MND identifies potential impacts to transportation as less than significant with mitigation incorporated, and requires designation of an alternative emergency evacuation route. The IS-MND identifies potential impacts to tribal cultural resources as less than significant with mitigation incorporated for Native American monitoring. The IS-MND identifies potential impacts to wildfire as less than significant with mitigation requiring implementation of fire ignition prevention measures. The IS-MND identifies potential impacts related to the mandatory findings of significance as less than significant with mitigation incorporated for a Hazardous Materials Management and Spill Control Plan, soil sampling and disposal, a contaminated soil contingency plan, and on-site monitoring of areas of suspect contamination.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

One Native American tribe requested government-to-government consultation under AB 52 regarding the potential for the project to encounter and/or disturb previously unidentified tribal cultural resources. At the time of preparation of this Draft IS-MND, CBMWD is actively coordinating with the Tribe and has scheduled a meeting with the Tribe on May 14, 2019 to answer questions about the project and to request information on the presence of any known tribal cultural resources at the site.

Provide a list of the responsible or trustee agencies for the project.

City of Montebello
State Water Resources Control Board, Division of Drinking Water