

Appendix J

Interim ACM-LBP Survey



assess
resolve
strengthen

CITADEL ENVIRONMENTAL SERVICES, INC.

October 23, 2017

Ms. Mindy Sheps
WOLF, RIFKIN, SHAPIRO, SCHULMAN & RABKIN, LLP
11400 West Olympic Boulevard, 9th Floor
Los Angeles, California 90064

Re: CITADEL Project No. 1097.1002.0
Environmentally-Regulated Materials Survey Report (Interim Report)
Pre-Demolition Asbestos and Lead Survey
333 South San Vicente Boulevard
Los Angeles, California 90048

Dear Ms. Sheps:

Enclosed please find Citadel Environmental Services, Inc.'s Environmentally-Regulated Materials (ERMs) Survey Report for the above-referenced location.

If after your review you have any questions or require additional information, please do not hesitate to telephone me at the Citadel Office in Costa Mesa at 714.547.4301.

Sincerely,

CITADEL ENVIRONMENTAL SERVICES, INC.

Kier DeLeo

Digitally signed by Kier DeLeo
DN: cn=Kier DeLeo, o=Citadel Environmental
Services, Inc., ou=Director, Building Sciences,
email=KDeLeo@CitadelEnvironmental.com,
c=US
Date: 2017.10.23 16:35:25 -07'00'

Kier DeLeo, CHMM
Director – Building Sciences

Enclosure

Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP
11400 West Olympic Boulevard, 9th Floor
Los Angeles, California 90064

Environmentally-Regulated Materials Survey Report (Interim Report)

October 23, 2017

Citadel Project Number 1097.1002.0

Asbestos and Lead Survey
333 South San Vicente Boulevard
Los Angeles, California 90048

www.citadelenvironmental.com



CITADEL ENVIRONMENTAL SERVICES, INC.

151 Kalmus Drive, Costa Mesa, California 92626 / P 714.547.4301 / F 714.547.4647 www.citadelenvironmental.com

Table of Contents

1.0 INTRODUCTION	1
2.0 SURVEY METHODOLOGIES	1
Field Methodologies – Asbestos.....	1
Field Methodologies – Lead containing materials (lcms).....	2
FIELD METHODOLOGIES – POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP)	2
FIELD METHODOLOGIES – UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES	3
FIELD METHODOLOGIES – OZONE DEPLETING SUBSTANCES (ODS)	3
3.0 RESULTS	3
ASBESTOS.....	3
Lead-Containing materials.....	6
POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP).....	8
UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES	9
OZONE DEPLETING SUBSTANCES (ODS).....	11
4.0 CONCLUSIONS AND RECOMMENDATIONS	12
ASBESTOS.....	12
LEAD-CONTAINING MATERIALS	13
POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP).....	14
UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES	15
OZONE DEPLETING SUBSTANCES.....	15
5.0 SURVEY LIMITATIONS	15
6.0 SIGNATURES.....	16

APPENDICES

A	Project Team Certifications
B	Drawings with Bulk Sample Locations
C	Table 1.0 – Bulk Sample Results
D	Table 2.0 – Summary by Material
E	Asbestos Laboratory Reports
F	Table 3.0 - Lead XRF SA Results
G	Table 3.1 – Lead XRF Results – LBP (Positive)
H	Table 3.2 – Lead XRF Results – LCP – (≥ 0.1 mg/cm ² .and < 0.7 mg/cm ²)

1.0 INTRODUCTION

Citadel Environmental Services, Inc. (Citadel) was contracted by Wolf, Rifkin, Schulman & Rabkin, LLP (Client) to conduct an Environmentally-Regulated Materials (ERMs) survey {i.e., asbestos-containing materials/asbestos-containing construction materials (ACMs/ACCMs), lead-containing materials (LCMs), and miscellaneous ERMS associated with Our Lady of Mt. Lebanon Church}, of four (4) structures located at 333 South San Vicente Boulevard in Los Angeles, California (Project Site). The structures included in this survey are as follows:

1. Church House
2. Church Hall
3. Church Office Building
4. Church Structure (Survey Pending)

The survey of structures 1-3 as identified above was conducted on select dates between August 14th through August 24th, 2017, by Citadel representative Mr. Jeffrey Klein. Mr. Klein is a California Department of Occupational Safety and Health (DOSH) Certified Asbestos Consultant (CAC) (No. 07-4240), and California Department of Public Health Services (CDPH) Lead-Related Construction Inspector/Assessor & Project Manager (LRCIA/PM) (No. 9799). The report was written by, Mr. Klein and reviewed by Mr. Kier DeLeo, CHMM. Project team certifications can be found in Appendix A.

The purpose of the survey was to locate, identify, and quantify ACMs/ACCMs, LCMs and miscellaneous ERMS in the interiors, exteriors, and roofs of the buildings that would be disturbed by a demolition project. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure.

2.0 SURVEY METHODOLOGIES

FIELD METHODOLOGIES – ASBESTOS

Citadel began the field survey by visually inspecting the project area to categorize suspect ACMs/ACCMs to be impacted by the project. Suspect ACMs/ACCMs were categorized by homogeneous areas (HAs). HAs consist of groupings of materials that have uniform appearances, textures, and installation dates. Following the walk through, representative bulk samples of suspect ACMs/ACCMs were then collected. As the samples were collected, the locations of the HAs and samples were marked on field sketches. Locations of visible debris were also noted where observed.

ACMs/ACCMs Condition Assessment

Materials were assessed to be in *good*, *damaged*, or *significantly damaged* condition based on how their condition at the time of the survey related to the following:

- ❖ **Good Condition** - No or very limited visible damage or deterioration was observed.
- ❖ **Damaged Condition** - Crumbling, blistering, water damage, gouges, or other damage was observed over less than 25% of the materials (one-tenth if evenly distributed); or accumulation of suspect powder, dust or debris below the material was observed.
- ❖ **Significantly Damaged Condition** - Crumbling, blistering, water damage, gouges, or other damage was observed over greater than 25% of the material (one-tenth if evenly

distributed); material is delaminating or showing adhesive failure; or accumulation of suspect powder, dust or debris below the material was observed.

Citadel collected bulk samples of suspect materials. Bulk sampling included interior and exterior building materials as necessary, including the roofs. Upon bulk samples collection, Citadel submitted all samples to an accredited laboratory for analysis for asbestos content by polarized light microscopy (PLM).

FIELD METHODOLOGIES – LEAD CONTAINING MATERIALS (LCMS)

X-Ray Fluorescence (XRF SA) (SCREEN)

A lead inspection/screening was conducted to test representative surface paints/coatings on surface area components such as plaster walls, ceramic sinks and tubs, wood doors/frames, etc. for lead-based paints (LBPs) and lead-containing paints (LCPs). Citadel utilized X-Ray Fluorescence Spectrum Analysis (XRF-SA) to test suspect paints and coatings. Assays (tests) were taken from interior and exterior painted/coated surfaces as necessary.

The XRF irradiates the paint on a given surface causing the lead in the paint, if present, to emit a characteristic frequency of x-ray radiation. The intensity of this radiation is measured by the detector and related to the amount of lead in the paint. The type of XRF used in this survey was a Niton XLP-303A X-Ray Fluorescence Spectrum Analyzer, Serial Number 23418. The XRF analyzer provides an in-the-field determination of suspect LBP without the need to collect substantial numbers of paint chip samples for subsequent laboratory analysis.

In order to obtain a reading, the XRF was placed with the face of the instrument flush against the surface to be tested. It was then held in place for the duration of the sample, which was determined by the instrument. At the conclusion of the sample time, the lead concentration was displayed on the device's readout screen. The values, expressed in milligrams per square centimeter (mg/cm²), are stored in the device and can be recalled by the inspector upon downloading into computer software. The Niton is sensitive to 0.01 milligrams per square centimeter (mg/cm²) of lead.

The instrument, equipped with a sealed radioactive source, was operated by certified personnel in accordance with manufacturer requirements and applicable regulations. The operator calibrated the XRF-SA pursuant to the manufacturer's specifications and regularly verified XRF-SA readings against pre-determined lead samples produced by the National Institute of Standards and Testing (NIST). All of these quality control measures produced a 95% confidence level that the XRF-SA readings accurately reflected the actual level of lead in the tested surfaces.

FIELD METHODOLOGIES – POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP)

The inspection for polychlorinated biphenyls (PCBs) and di(2-ethylhexyl) phthalate (DEHP) consisted of a visual inspection of the type(s) of equipment found in the survey areas that commonly use dielectric fluids. Items such as fluorescent lighting ballasts were visually inspected to determine if: (1) they were "wet" ballasts (contain dielectric fluids) as opposed to magnetic, and (2) if the ballasts were labeled "No PCBs" or "Does Not Contain PCBs." Wet ballasts were assumed to contain PCBs or DEHP unless so labeled. As required by Federal and State law, all ballasts manufactured post-1978 are required to be labeled with the aforementioned language. Please note that sampling of energized equipment was not possible during the survey. This portion of the survey was not intended to be comprehensive, but rather sought to identify potential hazards that will be encountered during the project.

FIELD METHODOLOGIES – UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES

The inspection for Universal/Electronic/Radioactive Wastes consisted of visual inspection of the buildings to determine if Universal/Electronic/Radioactive Wastes were present. This portion of the survey was not intended to be comprehensive, but rather sought to identify potential hazards that will be encountered during the project.

FIELD METHODOLOGIES – OZONE DEPLETING SUBSTANCES (ODS)

Under [Title VI](#) of the [Clean Air Act](#) (CAA), US Environmental Protection Agency (USEPA's) [Stratospheric Protection Division](#) is responsible for several programs that protect the stratospheric ozone layer. Several types of refrigerants and propellants have been defined as Ozone Depleting Substances (ODS) by the EPA. These include, but are not limited to, Chlorofluorocarbons (CFCs) and Hydrochlorofluorocarbons (HCFC), as well as Halon, Sulfur Dioxide (SO₂), and Ammonia (NH₃).

Citadel visually inspected the buildings for the following suspect ODS-containing equipment and appliances: refrigerators, freezers, dehumidifiers, window-mounted air cooling units, and forced-air furnaces with cooling units, as well as propellants in fire suppression equipment. This portion of the survey was not intended to be comprehensive, but rather sought to identify potential hazards that will be encountered during the project.

3.0 RESULTS

ASBESTOS

Asbestos Definitions

Asbestos-Containing Materials (ACM): The EPA's Asbestos NESHAPs and the South Coast Air Quality Management District (SCAQMD), the local air pollution control district, define an asbestos-containing material as any material that contains a concentration of asbestos of greater than one percent (>1.0%) by area as determined by PLM (Federal Register, Volume 59, No. 146, August 1, 1994, P. 38970-38971). NESHAPs and SCAQMD Rule 1403 further segregate asbestos-containing materials into *Regulated Asbestos-Containing Materials (RACM)*, *Category I Non-Friable Materials*, and *Category II Non-Friable Materials*, which are defined as follows:

- ❖ **Regulated Asbestos-Containing Materials (RACM)/Asbestos-Containing Materials (ACM):** Includes all friable asbestos materials, Category I/Class I Non-friable ACM that have become friable or will become friable, and Category II/Class II Non-friable ACM that have a high probability of being crumbled, pulverized, or reduced to powder by the forces expected to act on the materials in the course of renovation or demolition.
- ❖ **Category I Nonfriable ACM/Class I Nonfriable ACM:** Includes asbestos-containing packings, gaskets, resilient floor covering, and asphalt roofing products that when dry can be crumbled, pulverized, or reduced to powder by hand pressure in the course of renovation and demolition activities.
- ❖ **Category II Nonfriable ACM/Class II Nonfriable ACM:** Includes all non-friable materials, excluding *Category I/Class I Nonfriable ACM* that when dry cannot be crumbled, pulverized, or reduced to powder by hand pressure.

Asbestos-Containing Construction Materials (ACCM): The California Department of Occupational Safety and Health (Cal/OSHA) further defines an asbestos-containing construction material (ACCM) as a material that contains greater than one-tenth of one percent (>0.1%) asbestos.

Presumed Asbestos-Containing Material (PACM) means thermal system insulation and surfacing material found in buildings, vessels, and vessel sections constructed no later than 1980 that are assumed to contain greater than one percent asbestos but have not been sampled or analyzed to verify or negate the presence of asbestos. PACM is also used in this report to denote suspect asbestos containing materials that were not sampled, but should be assumed to be ACMs.

Asbestos Results

During the survey, a total of 136 asbestos bulk samples were collected and submitted for analysis. The bulk samples were submitted to LA Testing in South Pasadena, California, for analysis by polarized light microscopy (PLM) for asbestos content using EPA 600/R-93/116 Method. The EPA method is a semi-quantitative procedure with a detection limit of one-tenth to one percent (0.10 – 1.0%) by area, dependent upon the material being analyzed. If indicated, select samples were submitted for more objective analysis following EPA 600/R-93/116 Method Point Count procedures (1,000 points). The Point Count procedure is used to increase the amount of sample viewed under PLM so that the results are statistically enhanced, resulting in a generally more accurate analysis.

Table A.1 below summarizes the materials identified and sampled to be **Asbestos Containing Materials (ACM)** (>1.0% asbestos) in the survey area, along with the locations of each material:

TABLE A.1

MATERIAL TYPE	HA NO.	SAMPLE LOCATION(S)	APPROX. QUANTITY ¹	RECOMMENDED MANAGEMENT ACTION
CHURCH STRUCTURE (SURVEY PENDING)				
N/A	N/A	N/A	N/A	N/A
CHURCH HOUSE				
Cement Flue, Gray, 6" Flue Pipe (Hard)	CF1	Room 109, East End	30 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Pipe Jacket/Covering, Gray, Flue Pipe Cover (Soft) a/w CF1	PJ/C1	Room 109, East End	5 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
CHURCH HALL				
Roof Penetration Mastic, Gray	RPM1	Roof, West Wall Vent	50 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Window Putty, Gray, Smooth	WP1	Exterior, Outside Kitchen Room 5	5 Windows	Remove – Utilize: DOSH-Registered Abatement Contractor
CHURCH OFFICE BUILDING				
Roof Penetration Mastic, Gray	RPM1	Roof, HVAC Duct Base; West Wall Vent Pipe & Wall Vent	60 SF	Remove – Utilize: DOSH-Registered Abatement Contractor

¹ All quantities (SF/LF/EA) provided by Citadel are estimates. Contractors are responsible for field verifying actual quantities of materials.

Table A.2 below summarizes the materials identified and sampled to be **Asbestos Containing Construction Materials (ACCM)** (> 0.1%, but ≤1.0% asbestos) in the survey area, along with the locations of each material:

TABLE A.2

MATERIAL TYPE	HA NO.	SAMPLE LOCATION(S)	APPROX. QUANTITY ²	RECOMMENDED MANAGEMENT ACTION
CHURCH STRUCTURE (SURVEY PENDING)				
N/A	N/A	N/A	N/A	N/A
CHURCH HOUSE				
None Identified	N/A	N/A	N/A	N/A
CHURCH HALL				
Exterior Stucco, Green/Brown, Rough	ES1*	North Wall at Grills	80 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Exterior Stucco, Gray, Ceiling Stucco	ES3*	Exterior	500 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Exterior Stucco, Gray, Rough	ES7*	Exterior Walls	1,950 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Exterior Stucco, Gray	ES8*	Upper Roof Walls	240 SF	Remove – Utilize: DOSH-Registered Abatement Contractor
Wall Plaster Finish Coat, White, a/w WPB1	WPF1*	Interior Plaster Walls and Ceilings Throughout	6,000 SF (2,000 SF Walls and 4,000 SF Ceilings)	Remove – Utilize: DOSH-Registered Abatement Contractor
CHURCH OFFICE BUILDING				
N/A Identified	N/A	N/A	N/A	N/A

Note: Samples with an Asterisk (*) were submitted for 1,000 Point Count Analysis and reported to be Asbestos Containing Construction Materials (ACCM).

Table A.3 below summarizes the materials that were inaccessible and possibly present or were not sampled and are categorized as **Presumed Asbestos Containing Construction Materials (PACM)**:

TABLE A.3

MATERIAL TYPE	HA NO.	LOCATION(S)	APPROX. QUANTITY ³	RECOMMENDED MANAGEMENT ACTION
None Identified	N/A	N/A	N/A	N/A

² All quantities (SF/LF/EA) provided by Citadel are estimates. Contractors are responsible for field verifying actual quantities of materials.

³ All quantities (SF/LF/EA) provided by Citadel are estimates. Contractors are responsible for field verifying actual quantities of materials.

Table A.4 below summarizes the materials that were reported by the laboratory to not contain detectable quantities of asbestos **None Detected or ND** or contained less than 0.1% asbestos by the Point Count procedure:

MATERIAL TYPE
Please refer to 2.0 (Appendix D) to view a complete list of asbestos None-Detected Samples.

Table A.5 below summarizes the materials that were **Not Analyzed**:

TABLE A.5

MATERIAL TYPE	HA NO.
None Identified	N/A

The drawings with bulk sample locations can be found in Appendix **B**. A detailed summary of bulk samples collected may be found in Appendix **C**, Table 1.0 – *Bulk Sample Results*. Detailed information pertaining to the location of homogeneous asbestos-containing materials is presented in Appendix **D**, Table 2.0 – *Summary by Material*. LA Testing's bulk sample laboratory results may be found in Appendix **E**.

LEAD-CONTAINING MATERIALS

Lead Definitions

- ❖ **Lead Containing Paint (LCP)** - A lead-containing paint is a paint or coating that contains any detectable concentration of lead.
- ❖ **Lead Based Paint (LBP)** - The California Department of Public Health (CDPH) and the US Department of Housing and Urban Development (HUD) define Lead-Based Paint (LBP) as paint containing lead greater than or equal to 1.0 milligram per square centimeter (\geq mg/cm²) or greater than or equal to 0.5% by weight also expressed as 5,000 parts per million (\geq 5,000 ppm). Furthermore, the California Department of Health and Human Services, Health & Safety Code, Chapter 11 defines lead-bearing substances as any paint, varnish, lacquer or similar coating containing lead >0.7 mg/cm². For the purposes of this report, XRF-SA readings ≥ 0.7 mg/cm² are considered LBP.
- ❖ **Lead Containing Material (LCM)** - A lead-containing material may consist of identified lead-containing paint (LCP), lead-based paint (LBP), or other materials such as lead sheeting, ceramic tile glazing, etc., or presumed LCMS.
- ❖ **Presumed Lead-Based Paint (PLBP)** - Title 17, California Code of Regulations, Division 1, Chapter 8 defines as paint or surface coating affixed to a component in or on a structure constructed prior to January 1, 1978 as a presumed lead-based paint unless it has been tested and found to contain an amount of lead less than one milligram per square centimeter 1.0 mg/cm² (<1.0 mg/cm²) or less than 0.5% ($< 0.5\%$) by weight.

A total of 196 assays (tests) (excluding "Null" and "Calibration Readings"), using the XRF-SA, were conducted during the survey. Of the 196 assays collected, 23 were found to contain LBP (i.e., ≥ 0.7 mg/cm²).

XRF-SA results may be found in Appendix **F**, Table 3.0 – XRF-SA Results; Appendix **G**, Table 3.1 – Lead-Based Paint (LBP) XRF-SA results; and Appendix **H**, Table 3.2 – Lead-Containing Paint (LCP) results (i.e., ≥ 0.01 mg/cm² and < 0.7 mg/cm²).

Table B.1 below summarizes the materials identified and sampled to be **Lead-Based Paints (LBP)** (detectable quantities of lead in concentrations of $\geq 5,000$ ppm or ≥ 1.0 mg/cm²) in the survey area:

TABLE B.1

COMPONENT	SUBSTRATE	COLOR(S)	SAMPLE LOCATION(S)
CHURCH STRUCTURE			
None Identified	N/A	N/A	N/A
CHURCH HOUSE			
Down Spout	Metal	Tan	1 st Floor: Outside, East
Window	Metal	Blue	1 st Floor: Outside, East
Window Frame	Wood	Blue	1 st Floor: Outside, East
Square Down Spout	Wood	Tan	1 st Floor: Outside, SE
Back Door	Wood	Blue	1 st Floor: Outside, South
Back Door Jam	Wood	Blue	1 st Floor: Outside, South
West Door Jam	Wood	Blue	1 st Floor: Room 109, West Side to Garage; Outside, West Side to Garage
Door	Wood	Blue	1 st Floor: Outside, North Door
Door Jam	Wood	Blue	1 st Floor: Outside, North Door
Tub	Ceramic	White	2 nd Floor: Rooms 202, 206, & 213
Sink	Ceramic	White	2 nd Floor: Room 213
Trim	Wood	Beige	1 st Floor: Office
CHURCH HALL			
Baseboard	Ceramic	Yellow	1 st Floor: Rooms 9 & 10
Wall	Ceramic	Yellow, Beige	1 st Floor: Rooms 7, 9, 10, & Exterior
Sink	Ceramic	White	1 st Floor: Room 4
CHURCH OFFICE BUILDING			
None Identified	N/A	N/A	N/A

Similar materials present elsewhere within each structure should be assumed to be LBP unless specifically tested.

See Appendix **G** – Table 3.1 for complete list of LBP materials.

See Appendix **H** – Table 3.2 for a summary of materials identified and sampled to be **Lead-Containing Paints (LCP)** (detectable quantities of lead in concentrations of $< 5,000$ ppm or < 0.7 mg/cm²).

POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP)

Fluorescent light ballasts with wet (liquid) capacitors utilize dielectric fluids that may contain PCBs or DEHP dielectric fluids.

PCBs are regulated under 40 CFR Part 761 as part of the Toxic Substances Control Act (TSCA). The PCB regulations and requirements apply to both PCB waste materials and PCBs still in use. States and the Federal Government regulate the use, storage, and disposal of equipment containing PCBs, depending upon the concentrations of PCBs present.

DEHP is regulated under the Resource Conservation and Recovery Act (RCRA), "Superfund", Superfund Amendments, Clean Water Act, Safe Drinking Water Act, OSHA, and by the Food and Drug Administration.

PCB and DEHP Definitions

Environmental Protection Agency: 40 CFR Part 761 Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions has established the following threshold limits for liquid and non-liquid materials containing PCBs:

- ❖ **PCB-Contaminated Electrical Equipment** is defined as a liquid material (homogenous flowable material containing no more than 0.5% by weight non-dissolved material) that contains concentrations of PCBs at ≥ 50 ppm and < 500 ppm, or where insufficient liquid is available for analysis, a non-porous surface having a PCB concentration of > 10 $\mu\text{g}/100$ cm^2 but < 100 $\mu\text{g}/100$ cm^2 as measured by a standard wipe test. Electrical Equipment includes, but is not limited to, transformers, capacitors, circuit breakers, re-closers, voltage regulators, switches, electromagnets, and cable.
- ❖ **PCB-Contaminated** is defined as a non-liquid material (does not flow at room temperature of 25 °C or 77 °F) that contains concentrations of PCBs at ≥ 50 PPM but < 500 PPM; a liquid material that contains concentrations of PCBs at ≥ 50 ppm but < 500 ppm, or where insufficient liquid is available for analysis, a non-porous surface having a PCB concentration of > 10 $\mu\text{g}/100$ cm^2 but < 100 $\mu\text{g}/100$ cm^2 as measured by a standard wipe test.
- ❖ **PCB Capacitor** is defined as any capacitor that contains concentrations of PCBs at > 500 ppm.
- ❖ **PCB Transformer** is defined as any transformer that contains concentrations of PCBs < 500 ppm.
- ❖ **PCB Bulk Product Waste** is defined as waste derived from manufactured products containing PCBs in a non-liquid state, at any concentration where at the time of designation for disposal the concentration of PCBs was ≥ 50 ppm. Fluorescent light ballasts with labels that do not contain the words "No PCBs" or "Does Not Contain PCBs" are considered a PCB Bulk Product Waste.
- ❖ **Di(2-ethylhexyl) phalate** is a colorless, odorless, toxic liquid used in dielectric fluids from 1979 to 1991.

State of California-Department of Toxic Substances Control (DTSC): The DTSC enforces Title 22 of the California Code of Regulation, Chapter 11, Article 3, δ 66261.20-24 which has established the following threshold limits for PCBs in solid waste material:

- ❖ Total Threshold Limit Concentration (TTLC) of ≥ 50 ppm.
- ❖ Soluble Threshold Limit Concentration (STLC) of ≥ 5 mg/L.

Table C.1 below summarizes the **PCB** and **DEHP** containing equipment that may exist in the survey area:

TABLE C.1

MATERIAL TYPE	LOCATION
CHURCH STRUCTURE (SURVEY PENDING)	
N/A	N/A
CHURCH HOUSE	
N /A	N/A
CHURCH HALL	
20 Ballasts	Throughout
CHURCH OFFICE BUILDING	
33 Ballasts	Throughout

UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES

Universal Wastes

The *Universal Waste Rule* found in the California Code of Regulations (CCR), Title 22, division 4.5, Chapter 23, regulates the disposal of the following items such as:

- ❖ Mercury thermostats (ampoules);
- ❖ Batteries, including rechargeable nickel-cadmium batteries, silver button batteries, mercury batteries, small sealed lead acid batteries (burglar alarm and emergency light batteries), most alkaline batteries, carbon zinc batteries, and any other batteries that exhibit a characteristic of a hazardous waste (§66261.20 through §66261.24);
- ❖ Lamps, including fluorescent tubes, high intensity discharge lamps, sodium vapor lamps, and any other lamps that exhibit a characteristic of a hazardous waste;
- ❖ Non-empty aerosol cans;
- ❖ Mercury switches, including thermostats and tip switches in portable heaters, washing machine out-of-balance switches, silent wall switches, and other mercury-containing switches and products containing them;
- ❖ Mercury thermometers;
- ❖ Mercury pressure or vacuum gauges, including U tube manometers, barometers, and sphygmomanometers (blood pressure meters.);
- ❖ Medical devices containing mercury including, dilators and weighted tubing;
- ❖ Mercury-containing rubber flooring, including older gymnasium floors that were poured in place to form indoor tracks and gymnastic areas;
- ❖ Mercury gas flow regulators managed exclusively by natural gas utilities;
- ❖ Counterweights and dampers, including devices that use pouches of high density mercury to dampen shaking on hunting bows and snow skis or to absorb recoil on shotguns;
- ❖ Consumer electronic devices, including cell phones, game consoles, and computers; and
- ❖ Mercury gauges, including vacuum and pressure gauges, including blood pressure gauges, barometers, and manometers.

Electronic Wastes

The Department of Toxic Substances Control (DTSC) regulates electronic waste. As part of its implementation of the [Electronic Waste Recycling Act](#), DTSC has tested certain types of electronic devices to determine which would be hazardous waste when discarded. Currently, any of the following devices manufactured before 2006 are considered hazardous wastes:

- ❖ Cathode Ray Tube (CRT) devices (including televisions and computer monitors);
- ❖ LCD Desktop Monitors;
- ❖ Laptop Computers with LCD Displays;
- ❖ LCD Televisions;
- ❖ Plasma Televisions; and
- ❖ Portable DVD Players with LCD Screens ([added December 31, 2006](#)).

Radioactive Wastes

Various fire/life safety devices used in residential, industrial, and commercial buildings utilize low energy radioactive sources such as Americium-241 and Tritium. Common applications are ionization smoke detectors and self-luminous exit signage.

While low-energy radioactive devices pose little or no threat to public health, they are subject to certain reporting, handling, and transfer requirements including proper disposal of unwanted or unused signs as specified by the general licensing agreements of the United States Nuclear Regulatory Commission.

Under the licensing agreement, a general licensee must properly dispose of such products, report to the NRC any lost, stolen, or broken devices, and transfer unwanted devices to a specific licensee such as a manufacturer, distributor, licensed radioactive broker, or a low-level radioactive waste disposal facility. Radioactive sources may not be disposed of as architectural/construction waste.

Table D.1 below summarizes **universal/electronic/radioactive** wastes assumed to be present in the survey area:

TABLE D.1

MATERIAL TYPE	LOCATION
CHURCH STRUCTURE (SURVEY PENDING)	
N/A	N/A
CHURCH HOUSE	
47 Light Bulb Fixtures	Throughout
2 Thermostats	Throughout
CHURCH HALL	
40 Fluorescent Light Tubes	Reception
75 Light Bulb Fixtures	Reception
2 Thermostats	Reception
CHURCH OFFICE BUILDING	
88 Fluorescent Light Tubes	Throughout
3 Thermostats	Throughout

TABLE D.1

MATERIAL TYPE	LOCATION
CHURCH OFFICE BUILDING	
14 Light Bulb Fixtures	Throughout

OZONE DEPLETING SUBSTANCES (ODS)

Ozone Depleting Substances Definitions

A chlorofluorocarbon (CFC) is an [organic compound](#) that contains [carbon](#), [chlorine](#), and [fluorine](#), produced as a [volatile](#) derivative of [methane](#) and [ethane](#). A common subclass is the hydrochlorofluorocarbons (HCFCs), which contain hydrogen, as well. They are also commonly known by the [DuPont trade name](#) Freon. The most common representative is [dichlorodifluoromethane](#) (R-12 or Freon-12). Many CFCs have been widely used as refrigerants, propellants (in aerosol applications), and solvents. The compounds are suspected of contributing to [ozone depletion](#).

Under [Title VI](#) of the [Clean Air Act](#) (CAA), US Environmental Protection Agency (USEPA's) [Stratospheric Protection Division](#) is responsible for several programs that protect the stratospheric ozone layer. Several types of refrigerants and propellants have been defined as Ozone Depleting Substances (ODS) by the EPA. These include, but are not limited to, Chlorofluorocarbons (CFCs) and Hydrochlorofluorocarbons (HCFC), as well as Halon, Sulfur Dioxide (SO₂), and Ammonia (NH₃).

Table E.1 below summarizes the **ozone depleting substances** assumed to be present in the survey area:

TABLE E.1

MATERIAL TYPE	LOCATION
CHURCH STRUCTURE (SURVEY PENDING)	
N/A	N/A
CHURCH HOUSE	
2 Fire Extinguishers	Throughout
1 Refrigerator	Throughout
2 HVAC Units	Roof
9 Smoke Detectors	Throughout
CHURCH HALL	
4 Fire Extinguishers	Reception
2 Exit Signs	Reception
3 Smoke Detectors	Reception
2 Refrigerators/Freezers	Reception
1 Microwave	Reception
1 Ice Machine	Reception

MATERIAL TYPE	LOCATION
CHURCH OFFICE BUILDING	
22 Fire Extinguishers	Throughout
11 Exit Signs	Throughout
11 Smoke Detectors	Throughout

4.0 CONCLUSIONS AND RECOMMENDATIONS

ASBESTOS

The results of the survey indicate that ACMs and ACCMS are present in the area(s) surveyed. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure.

Citadel's scope of work and testing of representative areas was limited to accessible building materials specifically identified as being impacted by the proposed work to be performed. Areas outside of the specific areas identified in this scope of work were not included as part of this investigation.

Additional suspect materials and/or debris may be present in concealed or hidden spaces including, but not limited to, above-ceiling areas, within wall cavities, and beneath floor coverings, but will only be accessible during the course of demolition activities. Care should be exercised when accessing these areas. If suspect ACM's and/or ACCMs are identified in these areas that have not been previously tested, these materials are required to be sampled prior to disturbance.

All asbestos removal operations shall be performed by a Cal/OSHA-DOSH-registered and California-licensed asbestos contractor. All disturbances of asbestos-containing materials, and/or abatement operations, should be performed under the surveillance of a third-party Cal/OSHA Certified Asbestos Consultant retained by the Client.

All disturbances of asbestos-containing materials, and/or abatement operations, must be performed in accordance with the Cal/OSHA requirements set forth in 8 CCR 1529. Given the location of the subject facility, all asbestos abatement must also be performed in accordance with South Coast Air Quality Management District (SCAQMD) requirements set forth in Rule 1403. Finally, notification of the presence and location of asbestos-containing materials shall be made to all employees and vendors who work within the subject structure, in accordance with California Health and Safety Code, Section 25915, et seq. (also known as Connolley Notification Bills).

Citadel recommends that all undamaged ACMs, ACCMs, and PACMs not to be disturbed as part of this project and scheduled to remain be managed in place in accordance with the EPA's guidance document Managing Asbestos In-Place (a.k.a., the Green Book). The Green Book can be obtained by calling the Toxic Substance Control Act Hotline at (202) 554-1404. Citadel also recommends that the materials be managed in place in accordance with the Client's Operations and Maintenance (O & M program) addressing building cleaning, maintenance, renovation, and general operation procedures to minimize exposure to asbestos.

LEAD-CONTAINING MATERIALS

Lead-Containing Materials/Lead-Based Paints (LCM/LBP)

This survey revealed that building components coated with LCM/LBP are present in areas within the survey areas. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure.

At present there is no explicit state or federal regulations requiring mandatory lead removal prior to disturbance or demolition of structures with identified lead materials. However, there are applicable Cal/OSHA worker protection and training requirements, Cal/EPA waste disposal requirements, CDPH requirements for public and residential buildings, and SB 460 lead hazard regulations that apply to lead-related construction activities and their associated wastes.

The following is a brief discussion and summary of applicable regulatory requirements:

- ❖ **Cal/OSHA:** 8 CCR 1532.1 governs occupational exposure to lead. This regulation requires that prior to initiation of certain activities, referred to as "trigger tasks", workers must be trained, medically evaluated, and properly fitted with respiratory protection, and protective clothing until statistically reliable personal eight-hour Time Weighted Average (TWA) results indicate lead exposure levels below the Personal Exposure Limit (PEL) for each unique task which disturbs lead-based and lead-containing coatings. This process is known as a Negative Exposure Assessment (NEA). If the result of the exposure assessment is above the Action Level (AL), additional monitoring is required, and if the result is above the PEL, additional exposure monitoring, worker protection (including respirator protection and PPE), training and medical requirements apply. At a minimum, contractors performing any lead in construction work shall have a hand washing station and HEPA vacuum present on the job site.
- ❖ "Trigger tasks" are tasks that are assumed to exceed the PEL pending an exposure assessment and encompass the majority of construction activities that disturb surface coatings. Examples of "trigger tasks" range from manual paint scraping as a lower expected exposure up to hot work and abrasive blasting as the highest expected exposures, and include any non-listed task that the employer determines may potentially expose employees to lead levels above the AL.

NOTE: "OSHA does not consider any method that relies solely on the analysis of bulk materials or surface content of lead (or other toxic material) to be acceptable for safely predicting employee exposure to airborne contaminants. Without air monitoring results or without the benefit of historical or objective data (including air sampling, which clearly demonstrates that the employee cannot be exposed above the AL during any process, operation, or activity) the analysis of bulk or surface samples cannot be used to determine employee exposure." OSHA Standard Interpretation dated 5/8/2000.

Furthermore, Cal/OSHA states that these rules apply to "any detectable concentration of lead", without a specified detection level. Due to the Consumer Product Safety Commission currently allowing paint to contain up to 600 parts per million (ppm) of lead for residential consumption and no limits for industrial or commercial coatings, the variation of lead content due to aging and weathering, and the variation of detection limits associated with both paint chip and XRF analysis, all coated surfaces should be treated as potentially containing lead, unless bulk sample analysis indicates that no lead was detected. Positive analytical results can be utilized to indicate that detectable lead is present, but negative XRF results cannot be interpreted as conclusively demonstrating the absence of lead.

Analytical data can be helpful in evaluation of lead-related environmental risks in general but cannot be used to calculate worker exposures and are not a substitute for employee exposure

monitoring. As a result of the above, any employee that works around potential lead-based or lead-containing coatings should have hazard communication training (lead awareness) training and personal exposure air monitoring if they will potentially disturb such coatings. Significant additional certification, notification, and work practices are required for materials found to be "lead-based" or where the operation or process involved results in airborne lead exposures exceeding the PEL.

- ❖ Any welding, cutting, or heating of metal surfaces containing surface coatings should be conducted in accordance with 29 CFR 1926.354 and 8 CCR 1537. These regulations require surfaces covered with toxic preservatives, and in enclosed areas, be stripped of all toxic coatings for a distance of at least 4 inches, in all directions, from the area of heat application prior to the initiation of such heat application. There are some provisions for conducting hot work on coated surfaces, but only with required respiratory protection such as properly selected supplied air respirators.
- ❖ **Cal/EPA** through the Division of Toxic Substance Control (DTSC) regulates disposal of lead hazardous waste (22 CCR Division 4.5, Minimum Standards for Management of Hazardous and Extremely Hazardous Wastes). It is the responsibility of the waste generator to evaluate all waste streams produced and ensure that any resulting wastes that may be hazardous under California and Federal RCRA standards for lead be properly handled, packaged and transported under proper manifest to a permitted hazardous waste storage, treatment and disposal facility.
- ❖ **CDPH**: The Department of Public Health (DPH) has specific requirements (Title 17 Sections 35001 thru 36100) for hazard assessment and work involving lead-based paint (LBP) hazards in public or residential structures. These regulations require special certifications, work practices, and notifications for such activities.
- ❖ **Senate Bill 460 (SB 460)**: An act to amend Section 1941.1 of the Civil Code, and to amend Sections 17961, 17980, and 124130 of, and to add Sections 17920.10, 105251, 105252, 105253, 105254, 105255, 105256, and 105257 to, the Health and Safety Code, relating to lead abatement. This bill allows for fines and criminal penalties to be levied on any person who is found to have performed lead abatement without containment or created a measurable lead hazard based upon current CDPH standards. The testing for this determination can be initiated by any local official. A determination of a lead hazard is not solely based upon the lead content of the paint or coating and can be the result of the disturbance of such materials with low concentrations of lead.
- ❖ **EPA Lead Renovation, Repair, and Paint Rule (40 CFR, Part 745)**: Beginning in April 2010, contractors performing renovation, repair and painting projects that disturb lead-based paint in homes, child care facilities, and schools built before 1978 must be certified and must follow specific work practices to prevent lead contamination.

POLYCHLORINATED BIPHENYLS (PCBS)/DI (2-ETHYLHEXL) PHTHALATE (DEHP)

Field observation by Citadel indicated that fluorescent light fixture ballasts are present throughout the buildings. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure.

Typically during demolition, the contractor will dismantle the fluorescent light fixtures by removing the tubes and then the ballasts and package them for recycling and disposal, regardless of the ballast labeling. The recommended disposal method for ballasts is recycle/incineration whereby the PCB and DEHP capacitors and asphalt potting material are removed and incinerated, and the metal carcasses are cleaned and sent to a metal recycler.

UNIVERSAL/ELECTRONIC/RADIOACTIVE WASTES

Citadel visually identified universal/electronic/radioactive wastes present throughout the survey areas. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure.

In accordance with regulatory requirements, Universal/Electronic/Radioactive Wastes should be removed prior to demolition activities and set aside for re-use or disposal/recycling by a licensed recycler or specific licensee.

Citadel recommends either re-using the light tubes, lamps, or monitors, or utilizing a licensed recycler to process the Universal/Electronic Wastes removed from the building. Recycling facilities must be authorized by the California Environmental Protection Agency – Department of Toxic Substances Control (DTSC) or the state in which they are located.

Bill(s) of lading should accompany each load of waste that leaves the site, including the name and address of the Generator, Contractor, pick-up site, disposal site, and quantity of universal waste disposed. The recycler should provide a statement certifying recycling/disposal/destruction of the identified wastes, including the date(s) of recycling/disposal/destruction, and identifying the disposal/destruction process used. In the case of Tritium-containing exit devices, the general licensee must file a report with the NRC.

OZONE DEPLETING SUBSTANCES

Citadel visually identified Ozone Depleting Substances throughout the survey areas. Please note that the Church Structure was not surveyed during Citadel's initial site visits. Citadel is currently waiting for approval from the Client to survey the remaining structure. Chlorofluorocarbons (CFCs), Hydrochlorofluorocarbons (HCFC), as well as Halon, Sulfur Dioxide (SO₂), and/or Ammonia (NH₃) should be extracted from the fire extinguishers, freezers, HVAC units, and other ODS-containing equipment by a trained technician for recovery or recycling prior to demolition.

5.0 SURVEY LIMITATIONS

The survey and bulk sampling was limited to representative locations of the building(s) that were explicitly defined by the Client to be surveyed. Intrusive and destructive sampling was conducted as part of the scope of services performed. Additional suspect materials and/or debris may be present in concealed or hidden spaces including, but not limited to, above-ceiling areas, within wall cavities, and beneath floor coverings, but will only be accessible during the course of demolition activities. Care should be exercised when accessing these areas. Any suspect environmentally-regulated materials (ERMs) encountered during the course of demolition/renovation activities that were not previously sampled, including ERMs not specifically addressed herein, should be *presumed* to be ACMs/ACCMs and LCMs until sampled and proven otherwise. The areas that were accessible should be representative of the types, quantities, and conditions of the materials present at the site.

Quantities presented in this report are for informational purposes only and should not be the sole basis for an estimate for abatement. Contractors should verify and conduct their own takeoffs for their purposes.

This report has been prepared by Citadel Environmental Services, Inc. exclusively for our Client and their Authorized Representatives. The information contained herein pertains only to accessible materials identified at the referenced property at the time of the survey performed in

accordance with a mutually agreed upon scope of work. The findings and recommendations presented are based upon observations of present conditions, and may not necessarily indicate future conditions. Citadel Environmental Services, Inc. implies no warranty to the accuracy of information provided them by outside agents and transmitted herein. The information contained herein may not be used, disclosed, or copied without written permission of the Client.

This survey report is not intended to be a stand-alone design document for the solicitation of bids. This survey report should only be used for developing the scope of work, bid/contract document, and as a reference document.

6.0 SIGNATURES

Services performed by:

[See field documentation for signatures]

Jeffrey Klein
Certified California Asbestos Consultant (No. 07-4240)
CDPH Lead-Related Construction Project Monitor (No. 9799)

Report Prepared by:

Jeffrey Klein

Digitally signed by Jeffrey Klein
DN: cn=Jeffrey Klein, o=Citadel Environmental Services,
Inc., ou=Senior Project Manager, Industrial & Refinery
Programs, email=JKlein@CitadelEnvironmental.com, c=US
Date: 2017.10.23 16:35:58 -07'00'

Jeffrey Klein
Certified California Asbestos Consultant (No. 07-4240)
CDPH Lead-Related Construction Project Monitor (No. 9799)

Report Reviewed by:

Kier DeLeo

Digitally signed by Kier DeLeo
DN: cn=Kier DeLeo, o=Citadel Environmental
Services, Inc., ou=Director, Building Sciences,
email=KDeLeo@CitadelEnvironmental.com,
c=US
Date: 2017.10.23 16:36:14 -07'00'

Kier DeLeo, CHMM
Director, Building Sciences



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix A

Project Team Certifications

DEPARTMENT OF INDUSTRIAL RELATIONS
Division of Occupational Safety and Health
Asbestos Unit
2424 Arden Way, Suite 495
Sacramento, CA 95825-2417
(916) 574-2993 Office (916) 483-0572 Fax
<http://www.dir.ca.gov/dir/databases.html> actu@dir.ca.gov



707034240C

304

Citadel Environmental Service, Inc
Jeffrey D Klein
1725 Victory Blvd.
Glendale CA 91201

June 19, 2017

Dear Certified Asbestos Consultant or Technician:

Enclosed is your certification card. **To maintain your certification, you must abide by the rules printed on the back of the certification card.**

Your certification is valid for a period of one year. If you wish to renew your certification, you must apply for renewal at least 60 days before the expiration date shown on your card. [8 CCR 341.15(h)(1)].

Please hold and do not send copies of your required AHERA refresher renewal certificates to our office until you apply for renewal of your certification.

Certificates must be kept current if you are actively working as a CAC or CSST. The grace period is only for those who are not actively working as an asbestos consultant or site surveillance technician.

Please contact our office at the above address, fax number or email; of any changes in your contact/mailling information within 15 days of the change.


Sincerely,

Jeff Ferrell
Senior Safety Engineer

Attachment: Certification Card

cc: File

Renewal - Card Attached (Revised 10/24/2012)



RECEIVED
JUN 16 2017

BY:.....

Mr. Jeffrey D. Klein
Citadel Environmental Services, Inc.
1725 Victory Boulevard
Glendale, California 91201

State of California Department of Public Health

Lead-Related Construction Certificate	Certificate Type	Expiration Date
	Inspector/Assessor	04/30/2018
	Project Monitor	04/30/2018

Jeffrey D. Klein ID # 9799



Certificate Of Completion

Asbestos Management Planner Refresher Course

DOSH #:CA-015-08

Kier DeLeo

AMPR1213160005N10684

Guillermo Renteria

Principal Instructor



Michael W. Horner

Training Director

12/13/2016

Course Start Date

12/13/2016

Course End Date

12/13/2016

Exam Date

12/13/2017

Expiration Date

This course satisfies the education requirements for Asbestos accreditation under the Toxic Substances Control Act, Title II. This course has been approved by the Department of Industrial Relations, Division of Occupational Safety and Health of the State of California

NATEC International, Inc.

National Association of Training and Environmental Consulting

1100 Technology Circle- Suite A, Anaheim, CA 92805 • www.natecintl.com • 800-969-3228



Important Industry Contacts

CAL-OSHA: Ph# (916) 574-2993
(916) 483-0572 Fax Notification
Web: www.dir.ca.gov or calosha.com

CDPH/CLPPB: Ph# (510) 620-5600
Web: www.cdph.ca.gov/programs/CLPPB

SCAQMD: Ph# (909) 396-3739
Fax#(909) 396-3342

BAAQMD: Ph# (415) 749-4762

NATEC International, Inc.

National Association of Training and Environmental Consulting

Anaheim, CA • Oakland, CA • Fresno, CA • Sacramento, CA

Asbestos • Lead • Mold • HAZWOPER

P.O. Box 25205 Anaheim, CA 92825-5205
(714) 678-2750, (800) 969-3228, Fax (714) 678-2757
www.natecintl.com

NATEC International, Inc.

National Association of Training and Environmental Consulting
*Note: Card is not suitable substitute for certificate and is not accepted by SCAQMD as proof of certification

This Card Acknowledges That
Kier DeLeo

Holds Training Certification For
Asbestos Management Planner Refresher Course

(Valid for 12 months)

Training Date 12/13/2016
Certificate No. AMPR1213160005N10684

Michael W. Horner
Training Director

Certificate Of Completion

Asbestos Contractor/Supervisor Refresher Course

DOSH #:CA-015-04

Kier DeLeo

ASR0116170003N12357

Guillermo Renteria

Principal Instructor



Michael W. Horner
Training Director

1/16/2017

Course Start Date

1/16/2017

Course End Date

1/16/2017

Exam Date

1/16/2018

Expiration Date

This course satisfies the education requirements for Asbestos accreditation under the Toxic Substances Control Act, Title II. This course has been approved by the Department of Industrial Relations, Division of Occupational Safety and Health of the State of California

NATEC International, Inc.

National Association of Training and Environmental Consulting

1100 Technology Circle- Suite A, Anaheim, CA 92805 • www.natecintl.com • 800-969-3228



Important Industry Contacts

CAL-OSHA: Ph# (916) 574-2993
(916) 483-0572 Fax Notification
Web: www.dir.ca.gov or calosha.com

CDPH/CLPPB: Ph# (510) 620-5600
Web: www.cdph.ca.gov/programs/CLPPB

SCAQMD: Ph# (909) 396-3739
Fax#(909) 396-3342

BAAQMD: Ph# (415) 749-4762

NATEC International, Inc.

National Association of Training and Environmental Consulting

Anaheim, CA • Oakland, CA • Fresno, CA • Sacramento, CA

Asbestos • Lead • Mold • HAZWOPER

P.O. Box 25205 Anaheim, CA 92825-5205
(714) 678-2750, (800) 969-3228, Fax (714) 678-2757
www.natecintl.com

NATEC International, Inc.

National Association of Training and Environmental Consulting
*Note: Card is not suitable substitute for certificate and is not accepted by SCAQMD as proof of certification

This Card Acknowledges That
Kier DeLeo

Holds Training Certification For
Asbestos Contractor/Supervisor Refresher Course

(Valid for 12 months)

Training Date 1/16/2017
Certificate No. ASR0116170003N12357

Michael W. Horner
Training Director

Certificate Of Completion

Asbestos Building Inspector Refresher Course

DOSH #:CA-015-06

Kier DeLeo

ABIR1213160009N10682

Guillermo Renteria

Principal Instructor



Michael W. Horner
Training Director

12/13/2016

Course Start Date

12/13/2016

Course End Date

12/13/2016

Exam Date

12/13/2017

Expiration Date

This course satisfies the education requirements for Asbestos accreditation under the Toxic Substances Control Act, Title II. This course has been approved by the Department of Industrial Relations, Division of Occupational Safety and Health of the State of California

NATEC International, Inc.

National Association of Training and Environmental Consulting

1100 Technology Circle- Suite A, Anaheim, CA 92805 • www.natecintl.com • 800-969-3228



Important Industry Contacts

CAL-OSHA: Ph# (916) 574-2993
(916) 483-0572 Fax Notification
Web: www.dir.ca.gov or calosha.com

CDPH/CLPPB: Ph# (510) 620-5600
Web: www.cdph.ca.gov/programs/CLPPB

SCAQMD: Ph# (909) 396-3739
Fax#(909) 396-3342

BAAQMD: Ph# (415) 749-4762

NATEC International, Inc.

National Association of Training and Environmental Consulting

Anaheim, CA • Oakland, CA • Fresno, CA • Sacramento, CA

Asbestos • Lead • Mold • HAZWOPER

P.O. Box 25205 Anaheim, CA 92825-5205
(714) 678-2750, (800) 969-3228, Fax (714) 678-2757

www.natecintl.com

NATEC International, Inc.

National Association of Training and Environmental Consulting
*Note: Card is not suitable substitute for certificate and is not accepted by SCAQMD as proof of certification

This Card Acknowledges That
Kier DeLeo

Holds Training Certification For
Asbestos Building Inspector Refresher Course

(Valid for 12 months)

Training Date 12/13/2016
Certificate No. ABIR1213160009N10682

Michael W. Horner
Training Director



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix B

Drawings with Bulk Sample Locations




CHURCH STRUCTURE (SURVEY PENDING)





CHURCH HOUSE





EXT'G./DEMO FLOOR PLAN
SCALE: 1/8\"/>

- LEGEND**
- () EXISTING
 - () ITEMS TO BE RELOCATED
 - EXT'G WALLS TO BE REMOVED
 - === EXISTING WALLS


GENERAL NOTES

1. THE WORK OF THIS PROJECT INCLUDES ALTERATIONS OF FACILITY TO ACHIEVE THE ARRANGEMENTS INDICATED ON THE GENERAL AND SUB CONTRACTORS SHALL VISIT SITE WITH EXISTING CONDITIONS, LOCATIONS AND RECORD TO SUBMITTING BID AND DETERMINE THE EXTENT AND NEW WORK FOR THESE AREAS SHOW THE CHANGES GENERAL AND SUB CONTRACTORS SHALL REARRANGE, USE EXISTING AS REQUIRED TO ACCOMMODATE THE CHANGES SHOWN AND TO PROVIDE CONTINUING SERVICE FOR THOSE PORTIONS OF THE PROJECT WHICH ARE TO REMAIN IN PLACE.
 2. STRUCTURAL SUB-CONTRACTOR SHALL REMOVE ALL EXISTING WITHIN BOUNDARY OF THIS PROJECT AS SHOWN ON THE FURTHER AS REQUIRED BY JOB CONDITIONS. TERMINATE LINES BACK AT PANEL.
 3. BEFORE STARTING WORK, THE GENERAL AND SUB-CONTRACTORS SHALL VISIT THE SITE AND MAKE A SURVEY CONDITIONS WHICH MAY AFFECT THE WORK, BEFORE BID FOR EXTRAS WILL BE ACCEPTABLE.
 4. THESE NOTES ARE INTENDED TO ACCQUAINTING THE GENERAL CONTRACTORS OF THE GENERAL SCOPE OF THE WORK IN TENTATIVE NEW ROUTING FOR ALL RELOCATED UTILITIES CONTRACTORS SHALL VISIT THE SITE AND MAKE A SURVEY CONDITIONS WHICH MAY AFFECT THE WORK, BEFORE BID FOR EXTRAS WILL BE ACCEPTABLE.
- EXISTING 13 ROWS OF FEWS EACH SIDE AT 10'-0\"/>


17 + 14-3 SEATS EA PEW
13 + 14-7 EACH SIDE OF CHURCH
73 + 14-11 TOTAL SEATS
346 SEATS DOCUMENTED

DEMO NOTES #

- ALL SUB-CONTRACTORS ELECTRICAL MECHANICAL PLUMBING, ETC TO DISCONNECT OR REMOVE ALL EXISTING LINES INCLUDING LANDSCAPE SPRINKLERS SYSTEM OUTDOOR LIGHTING, SEWER LINES, OR POWER SERVICE WIRES, PLUMBING & MECHANICAL LINE VENTS AS REQUIRED TO COMPLETE THE JOB TO USE WITH ALL BUILDING DEPT REQUIREMENTS AND PER THE INTEND OF THESE PLANS
1. REMOVE PORTION OF EXISTING WALLS AS SHOWN
 2. REMOVE EXISTING DOORS & WINDOWS AS SHOWN
 3. REMOVE EXISTING LANDSCAPING AS REQ. EXISTING IRIS TO BE CUT & CAPED AS REQ. FOR NEW ADDITION
 4. REMOVE EXISTING PICTURE AS 8-10\"/>



EXT'G. MEZZANINE FLOOR PLAN
SCALE: 1/8\"/>



217/117
1097.1002.0
Church office


30 Windows 150 sf











CHURCH HALL



25 50



50


-  12x12 VST Beige
-  Window Potty
-  Plaster Wall/Ceiling
-  Mirror Mastic 20 SF
-  Ceramic
-  Wood Floor
-  Painted Concrete
-  SAC



Project No.: 1097.1002 Client: WRSSR Date: 8/14/17
 Project ID: Our Lady of Mt. Lebanon Drawing: Church Hall
 Floor: 1st floor
 Site Address: _____
 Inspector: Jeffrey Klein



ORIGINAL




Project No.: 1097.1002 Client: WRSSR Date: 8/14/17
 Project ID: Our copy of Mt Lebanon Drawing: Church Hall
 Floor: 1st Floor
 Site Address: _____
 Inspector: Jeffrey Klein



2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54

50 SF RPM




Project No.: 1097.1002.0 Client: WRSSR Date: 8/16/17
 Project ID: OUR LADY OF ART LABARON Drawing: ROOF
 Floor: CHURCH HALL
 Site Address: _____
 Inspector: Jeffrey Klein




CHURCH OFFICE BUILDING





Project No.: 1097.1002 Client: WRSSR Date: 5/16/17
 Project ID: Our Lady of Mt Lebanon Drawing: Church office
 Floor: GROUND Level
 Site Address: _____
 Inspector: Jeffrey Klein

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54




 VSF (1) Beige square pattern



CITADEL
ENVIRONMENTAL
SERVICES, INC.

Project No.: 1097.1002 Client: WRSSR Date: 8/16/17
 Project ID: Our Lady of Mt. Lebanon Drawing: 2ND FLOOR
 Floor: church office
 Site Address: _____
 Inspector: Jeffrey Klein


12'



CITADEL
ENVIRONMENTAL
SERVICES, INC.

Project No.: 1097.1002 Client: WRSSR Date: 8/16/17
 Project ID: Dur Lacy on Mt. Lebanon Drawing: Roof
 Floor: church office
 Site Address: _____
 Inspector: Jeffrey Klein

2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54



Project No.: 1097.1202 Client: WRSSR Date: 8/16/17
 Project ID: Our Lady of Mt Lebanon Drawing: 3RD Floor
 Floor: church office
 Site Address: _____
 Inspector: Jeffrey Klein



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix C

Table 1.0 - Bulk Sample Results



**TABLE 1.0
BULK SAMPLE RESULTS**

Project Number: 1097.1002.0

Our Lady of Mt. Lebanon

333 S. San Vicenta Blvd, Los Angeles, CA 90048

Updated 9/5/2017

Consultant Sample No	Material Description	Area/Location	Asbestos Content - Percent:				Non-ACM - Percent:	Not Analyzed	Comments	
001	SAC1 White Spray-Applied Acoustic Ceiling rough texture	Floor 1st Rm Church Hall Room #2, NW	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
002	SAC1 White Spray-Applied Acoustic Ceiling rough texture	Floor 1st Rm Church Hall Room #2, Cen	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
003	SAC1 White Spray-Applied Acoustic Ceiling rough texture	Floor 1st Rm Church Hall Room #2, SE	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
004	WPB1 Gray Wall Plaster Brown Coat	Floor 1st Rm Church Hall Room #4, Jani	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
005	WPF1 White Wall Plaster Finish Coat a/w WPB1	Floor 1st Rm Church Hall Room #4, Jani	Chrysotile	<u>0.2%</u>	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	0.2% Chrysotile
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>99.8%</u>		
006	WPB1 Gray Wall Plaster Brown Coat	Floor 1st Rm Church Hall Room #8, Kitc	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
007	WPF1 White Wall Plaster Finish Coat a/w WPB1	Floor 1st Rm Church Hall Room #8, Kitc	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	0.1% Chrysotile PCV
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>99.9%</u>		
008	WPB1 Gray Wall Plaster Brown Coat	Floor 1st Rm Church Hall Room #1, Wes	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
009	WPF1 White Wall Plaster Finish Coat a/w WPB1	Floor 1st Rm Church Hall Room #1, Wes	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	<0.1% Chrysotile PCV
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
010	WPB1 Gray Wall Plaster Brown Coat	Floor 1st Rm Church Hall Room #1, Wes	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
011	WPF1 White Wall Plaster Finish Coat a/w WPB1	Floor 1st Rm Church Hall Room #1, Wes	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	<0.1% Chrysotile PCV
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
012	WPB1 Gray Wall Plaster Brown Coat	Floor 1st Rm Church Hall Room #10, M	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
013	WPF1 White Wall Plaster Finish Coat a/w WPB1	Floor 1st Rm Church Hall Room #10, M	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	<0.1% Chrysotile PCV
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>		
014	WP1 Gray Window Putty smooth	Floor 1st Rm Church Hall Exterior, N W	Chrysotile	<u>2.0%</u>	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>98.0%</u>		
015	WP1 Gray Window Putty smooth	Floor 1st Rm Church Hall Exterior, West	Chrysotile	<u>3.0%</u>	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>	
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>97.0%</u>		



**TABLE 1.0
BULK SAMPLE RESULTS**

Project Number: 1097.1002.0

Our Lady of Mt. Lebanon

333 S. San Vicenta Blvd, Los Angeles, CA 90048

Updated 9/5/2017

Consultant Sample No	Material Description		Area/Location			Asbestos Content - Percent:					Non-ACM - Percent:	Not Analyzed	Comments	
016	ES1 Gray/Brown	Exterior Stucco rough	Floor	1st	Rm	Church Hall N Wall at Gril	Chrysotile Crocidolite	0.3% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 99.7%	<input type="checkbox"/>	0.29% Chrysotile PCV
017	MISC1 Black	Miscellaneous Material felt barrier paper, smooth	Floor	1st	Rm	Church Hall N Wall at Gril	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
018	ES1 Gray/Brown	Exterior Stucco rough	Floor	1st	Rm	Church Hall N Wall at Gril	Chrysotile Crocidolite	0.3% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 99.7%	<input type="checkbox"/>	0.3% Chrysotile PCV
019	MISC1 Black	Miscellaneous Material felt barrier paper, smooth	Floor	1st	Rm	Church Hall N Wall at Gril	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
020	ES7 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Hall Exterior, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	<0.1% Chrysotile PCV
021	ES7 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Hall Exterior, Nort	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
022	ES7 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Hall Exterior S Wal	Chrysotile Crocidolite	0.2% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 99.8%	<input type="checkbox"/>	0.2% Chrysotile PCV
023	ES2 Gray	Exterior Stucco smooth	Floor	1st	Rm	Church Hall NW at Grill A	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
024	ES2 Gray	Exterior Stucco smooth	Floor	1st	Rm	Church Hall NW at Grill A	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
025	ES2 Gray	Exterior Stucco smooth	Floor	1st	Rm	Church Hall NW at Grill A	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
026	ES3 Gray	Exterior Stucco exterior ceiling stucco, rough	Floor	1st	Rm	Church Hall North Wall	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 99.9%	<input type="checkbox"/>	0.1% Chrysotile PCV
027	ES3 Gray	Exterior Stucco exterior ceiling stucco, rough	Floor	1st	Rm	Church Hall West Wall	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
028	ES3 Gray	Exterior Stucco exterior ceiling stucco, rough	Floor	1st	Rm	Church Hall South Wall	Chrysotile Crocidolite	0.39% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 99.61%	<input type="checkbox"/>	0.39% Chrysotile PCV
029	SAC1 White	Spray-Applied Acoustic Ceiling textured	Floor	1st	Rm	Church Hall Room 11, East	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	
030	12VFT1 Beige	12x12 Vinyl Floor Tile w/brown mottles	Floor	1st	Rm	Church Hall Room 11, NW	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk 100.0%	<input type="checkbox"/>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description		Area/Location			Asbestos Content - Percent:					Non-ACM - Percent:	Not Analyzed	Comments	
031	FTM1 Yellow	Floor Tile Mastic a/w 12VFT1	Floor	1st	Rm	Church Hall Room 11, NW	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
032	12VFT1 Beige	12x12 Vinyl Floor Tile w/brown mottles	Floor	1st	Rm	Church Hall Room 11, NE	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
033	FTM1 Yellow	Floor Tile Mastic a/w 12VFT1	Floor	1st	Rm	Church Hall Room 11, NE	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
034	12VFT1 Beige	12x12 Vinyl Floor Tile w/brown mottles	Floor	1st	Rm	Church Hall Room 11, SW	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
035	FTM1 Yellow	Floor Tile Mastic a/w 12VFT1	Floor	1st	Rm	Church Hall Room 11, SW	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
036	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Hall West Wall, 10	Chrysotile Crocidolite	<u>10.0%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>90.0%</u>	<input type="checkbox"/>	
037	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Hall West Wall, N	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
038	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Hall Middle of S W	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
039	RFM1 Rust	Roof Field Membrane rolled on membrane, cap sheet	Floor	Roof	Rm	Church Hall Middle of Wes	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
040	RFM1 Rust	Roof Field Membrane rolled on membrane, cap sheet	Floor	Roof	Rm	Church Hall N Wall, NE C	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
041	RFM1 Rust	Roof Field Membrane rolled on membrane, cap sheet	Floor	Roof	Rm	Church Hall Middle of S W	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
042	ES8 Gray	Exterior Stucco	Floor	Roof	Rm	Church Hall Upper Roof, N	Chrysotile Crocidolite	<u>0.2%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>99.8%</u>	<input type="checkbox"/>	0.2% Chrysotile PCV
043	ES8 Gray	Exterior Stucco	Floor	Roof	Rm	Church Hall Upper Roof, S	Chrysotile Crocidolite	<u>0.3%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>99.7%</u>	<input type="checkbox"/>	0.29% Chrysotile PCV
044	RS1 Red	Shingles upper layer	Floor	Roof	Rm	Church Hall Middle of Wes	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
045	RS2 Black	Shingles bottom layer	Floor	Roof	Rm	Church Hall Middle of Wes	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description		Area/Location		Asbestos Content - Percent:					Non-ACM - Percent:	Not Analyzed	Comments		
046	RS1 Red	Shingles upper layer	Floor	Roof	Rm	Church Hall NE End	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
047	RS2 Black	Shingles bottom layer	Floor	Roof	Rm	Church Hall NE End	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
048	RS1 Red	Shingles upper layer	Floor	Roof	Rm	Church Hall Upper Roof, S	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
049	RS2 Black	Shingles lower layer	Floor	Roof	Rm	Church Hall Upper Roof, S	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
050	2CP1 White	2x2 Ceiling Panel pinholes, fissures	Floor	2nd	Rm	Church Office Room 14, Cen	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
051	WSR1 White	Wall Sheetrock	Floor	2nd	Rm	Church Office Room 14, East	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
052	WJC1 White	Wall Joint Compound a/w WSR1	Floor	2nd	Rm	Church Office Room 14, East	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
053	CSR1 White	Ceiling Sheetrock	Floor	2nd	Rm	Church Office Room 14, Cen	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
054	CJC1 White	Ceiling Joint Compound a/w CSR1	Floor	2nd	Rm	Church Office Room 14, Cen	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
055	2CP1 White	2x2 Ceiling Panel lay-in ceiling panel	Floor	2nd	Rm	Church Office Corridor Outsi	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
056	WSR1 White	Wall Sheetrock	Floor	2nd	Rm	Church Office Corridor Outsi	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
057	WJC1 White	Wall Joint Compound a/w WSR1	Floor	2nd	Rm	Church Office Corridor Outsi	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
058	CSR1 White	Ceiling Sheetrock	Floor	2nd	Rm	Church Office Corridor Outsi	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
059	CJC1 White	Ceiling Joint Compound a/w CSR1	Floor	2nd	Rm	Church Office Corridor Outsi	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
060	2CP1 White	2x2 Ceiling Panel lay-in ceiling panel	Floor	2nd	Rm	Church Office Room 8, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description	Area/Location	Asbestos Content - Percent:				Non-ACM - Percent:	Not Analyzed	Comments					
061	WSR1 White	Wall Sheetrock	Floor	2nd	Rm	Church Office Room 8, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
062	WJC1 White	Wall Joint Compound a/w WSR1	Floor	2nd	Rm	Church Office Room 8, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
063	CSR1 White	Ceiling Sheetrock	Floor	2nd	Rm	Church Office Room 8, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
064	CJC1 White	Ceiling Joint Compound a/w CSR1	Floor	2nd	Rm	Church Office Room 8, West	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
065	WSR1 White	Wall Sheetrock	Floor	3rd	Rm	Church Office Room 8, NE C	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
066	WJC1 White	Wall Joint Compound a/w WSR1	Floor	3rd	Rm	Church Office Room 8, NE C	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
067	WSR1 White	Wall Sheetrock	Floor	3rd	Rm	Church Office Room 24, Kitc	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
068	WJC1 White	Wall Joint Compound a/w WSR1	Floor	3rd	Rm	Church Office Room 24, Kitc	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
069	WSR1 White	Wall Sheetrock	Floor	3rd	Rm	Church Office N Stairwell, R	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
070	WJC1 White	Wall Joint Compound a/w WSR1	Floor	3rd	Rm	Church Office N Stairwell, R	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
071	WSR1 White	Wall Sheetrock	Floor	1st	Rm	Church Office Elevator Mech	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
072	WJC1 White	Wall Joint Compound a/w WSR1	Floor	1st	Rm	Church Office Elevator Mech	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
073	2CP1 White	2x2 Ceiling Panel lay-in ceiling panel	Floor	2nd	Rm	Church Office Main Corridor	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
074	2CP1 White	2x2 Ceiling Panel lay-in ceiling panel	Floor	2nd	Rm	Church Office Room 15, NE	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
075	RFM2 Silver/Black	Roof Field Membrane rolled field membrane w/felts	Floor	Roof	Rm	Church Office N End	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description		Area/Location			Asbestos Content - Percent:					Non-ACM - Percent:	Not Analyzed	Comments	
076	RFM2 Silver/Black	Roof Field Membrane rolled field membrane w/felts	Floor	Roof	Rm	Church Office Center	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
077	RFM2 Silver/Black	Roof Field Membrane rolled field membrane w/felts	Floor	Roof	Rm	Church Office S End	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
078	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Office West Wall, W	Chrysotile Crocidolite	<u>10.0%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>90.0%</u>	<input type="checkbox"/>	
079	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Office West Wall, Ro	Chrysotile Crocidolite	<u>10.0%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>90.0%</u>	<input type="checkbox"/>	
080	RPM1 Gray	Roof Penetration Mastic	Floor	Roof	Rm	Church Office Center, HVAC	Chrysotile Crocidolite	<u>10.0%</u> 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>90.0%</u>	<input type="checkbox"/>	
081	HVT1 Gray	HVAC Duct Tape HVAC duct seam sealant, rubberlike	Floor	Roof	Rm	Church Office NE Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
082	HVT1 Gray	HVAC Duct Tape HVAC duct seam sealant, rubberlike	Floor	Roof	Rm	Church Office Center	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
083	HVT1 Gray	HVAC Duct Tape HVAC duct seam sealant, rubberlike	Floor	Roof	Rm	Church Office SW Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
084	VSF1 Beige	Vinyl Sheet Flooring square pattern	Floor	2nd	Rm	Church Office Room 10	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
085	VSFM1 Yellow	Vinyl Sheet Flooring Mastic a/w VSF1	Floor	2nd	Rm	Church Office Room 10	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
086	ES4 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Office NW Corner at	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
087	ES4 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Office NE Corner at	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
088	ES4 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Office Garage Room	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
089	ES4 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Office SE Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
090	ES4 Gray	Exterior Stucco rough	Floor	1st	Rm	Church Office SW Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	



**TABLE 1.0
BULK SAMPLE RESULTS**

Project Number: 1097.1002.0

Our Lady of Mt. Lebanon

333 S. San Vicenta Blvd, Los Angeles, CA 90048

Updated 9/5/2017

Consultant Sample No	Material Description	Area/Location	Asbestos Content - Percent:				Non-ACM - Percent:	Not Analyzed	Comments
091	VSF2 Beige Vinyl Sheet Flooring w/blue squares	Floor 3rd Rm Church Office Room 21A, N	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
092	VSF2 Yellow/White Vinyl Sheet Flooring Mastic a/w VSF2	Floor 3rd Rm Church Office Room 21A, N	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
093	VSF2 Beige Vinyl Sheet Flooring w/blue squares	Floor 3rd Rm Church Office Room 21A, Ea	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
094	VSF2 Yellow/White Vinyl Sheet Flooring Mastic a/w VSF2	Floor 3rd Rm Church Office Room 21A, Ea	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
095	VSF2 Beige Vinyl Sheet Flooring w/blue squares	Floor 3rd Rm Church Office Room 23A, W	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
096	VSF2 Yellow/White Vinyl Sheet Flooring Mastic a/w VSF2	Floor 3rd Rm Church Office Room 23A, W	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
097	SAC2 White Spray-Applied Acoustic Ceiling rough	Floor 1st Rm Church Office Room 1A, Nor	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
098	SAC2 White Spray-Applied Acoustic Ceiling rough	Floor 1st Rm Church Office Room 1A, Nor	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
099	SAC2 White Spray-Applied Acoustic Ceiling rough	Floor 1st Rm Church Office Room 1A, Mi	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
100	HVT2 White HVAC Duct Tape HVAC seam sealant, rubbery	Floor 1st Rm Church Office Room 1A, Sou	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
101	HVT2 White HVAC Duct Tape HVAC seam sealant, rubbery	Floor 1st Rm Church Office Room 1A, Mi	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
102	HVT2 White HVAC Duct Tape HVAC seam sealant, rubbery	Floor 1st Rm Church Office Room 1A, Mi	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
103	HVD1 Gray HVAC Vibration Dampener HVAC vibration dampner, smooth	Floor 1st Rm Church Office Room 1A, Mi	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
104	WPF2 Gray Wall Plaster Finish Coat troweled on, rough	Floor 1st Rm Church House Room 109, N	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
105	WPF2 Gray Wall Plaster Finish Coat troweled on, rough	Floor 1st Rm Church House Room 109, S	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description	Area/Location	Asbestos Content - Percent:				Non-ACM - Percent:	Not Analyzed	Comments
106	WPF2 Gray Wall Plaster Finish Coat troweled on, rough	Floor 1st Rm Church House Room 109, Ce	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
107	CF1 Gray Cement Flue 6" flue pipe, hard	Floor 1st Rm Church House Room 109, E	Chrysotile	<u>10.0%</u>	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>90.0%</u>	
108	PJ/C1 Gray Pipe Jacket/Covering flue pipe cover, soft	Floor 1st Rm Church House Room 109, E	Chrysotile	<u>60.0%</u>	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>40.0%</u>	
109	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 1st Rm Church House Hallway Close	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
110	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 1st Rm Church House Room 106, N	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
111	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 1st Rm Church House Room 102, E	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
112	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 1st Rm Church House Room 105, N	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
113	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 2nd Rm Church House Room 207, R	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
114	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 2nd Rm Church House Room 202, R	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
115	WPF3 Beige Wall Plaster Finish Coat smooth	Floor 2nd Rm Church House Room 200, Ha	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
116	WSR2 White Wall Sheetrock	Floor 1st Rm Church House Room 106 Clo	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
117	WJC2 White Wall Joint Compound a/w WSR2	Floor 1st Rm Church House Room 106 Clo	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
118	WP2 White/Gray Window Putty	Floor 1st Rm Church House Middle of S W	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
119	WP2 White/Gray Window Putty	Floor 1st Rm Church House E Wall, S End	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	
120	WP2 White/Gray Window Putty	Floor 1st Rm Church House E Wall, N End	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	<u>100.0%</u>	



TABLE 1.0
BULK SAMPLE RESULTS
Project Number: 1097.1002.0
Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Consultant Sample No	Material Description		Area/Location			Asbestos Content - Percent:					Non-ACM - Percent:	Not Analyzed	Comments	
121	ES5 White	Exterior Stucco finish coat	Floor	1st	Rm	Church House E Wall, Center	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
122	ES6 Gray	Exterior Stucco base coat	Floor	1st	Rm	Church House E Wall, Center	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
123	ES5 White	Exterior Stucco finish coat	Floor	1st	Rm	Church House SE Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
124	ES6 Gray	Exterior Stucco base coat	Floor	1st	Rm	Church House SE Corner	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
125	ES5 White	Exterior Stucco finish coat	Floor	1st	Rm	Church House S Wall, W En	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
126	ES6 Gray	Exterior Stucco base coat	Floor	1st	Rm	Church House S Wall, W En	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
127	ES5 White	Exterior Stucco finish coat	Floor	1st	Rm	Church House W Wall, Belo	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
128	ES6 Gray	Exterior Stucco base coat	Floor	1st	Rm	Church House W Wall, Belo	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
129	ES5 White	Exterior Stucco finish coat	Floor	1st	Rm	Church House N Wall, W Co	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
130	ES6 Gray	Exterior Stucco base coat	Floor	1st	Rm	Church House N Wall, W Co	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
131	MISC2 Black	Miscellaneous Material felt barrier paper	Floor	1st	Rm	Church House S Wall, W En	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
132	MISC2 Black	Miscellaneous Material felt barrier paper	Floor	1st	Rm	Church House Middle of Wes	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
133	MISC2 Black	Miscellaneous Material felt barrier paper	Floor	1st	Rm	Church House Middle of Wes	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
134	MISC3 Black	Miscellaneous Material felt paper, smooth below tile	Floor	Roof	Rm	Church House S Wall, W En	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	
135	MISC3 Black	Miscellaneous Material felt paper, smooth below tile	Floor	Roof	Rm	Church House S Wall, E End	Chrysotile Crocidolite	0.0% 0.0%	Amosite Tremolite/Actinolite	0.0% 0.0%	Anthophyllite 0.0%	OtherOk <u>100.0%</u>	<input type="checkbox"/>	



**TABLE 1.0
BULK SAMPLE RESULTS**

Project Number: 1097.1002.0

Our Lady of Mt. Lebanon

333 S. San Vicenta Blvd, Los Angeles, CA 90048

Updated 9/5/2017

Consultant Sample No	Material Description	Area/Location	Asbestos Content - Percent:				Non-ACM - Percent:	Not Analyzed	Comments
136	MISC3 Black Miscellaneous Material felt paper, smooth below tile	Floor Roof Rm Church House E Wall, N End	Chrysotile	0.0%	Amosite	0.0%	Anthophyllite	OtherOk	<input type="checkbox"/>
			Crocidolite	0.0%	Tremolite/Actinolite	0.0%	0.0%	100.0%	

Grand Total 136



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix D

Table 2.0 - Summary by Material



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
12VFT1	12x12 Vinyl Floor Tile, Beige, w/brown mottles	1st	Church Hall	Room 11, NE Corner	0	032	<input type="checkbox"/>	No	
		1st		Room 11, NW Corner	0	030	<input type="checkbox"/>		
		1st		Room 11, SW Corner	0	034	<input type="checkbox"/>		
2CP1	2x2 Ceiling Panel, White, lay-in ceiling panel	2nd	Church Office	Corridor Outside North Stairs, Room 16	0	055	<input type="checkbox"/>	No	
		2nd		Main Corridor Between Rooms 12 & 13	0	073	<input type="checkbox"/>		
		2nd		Room 15, NE Corner	0	074	<input type="checkbox"/>		
		2nd		Room 8, West Side	0	060	<input type="checkbox"/>		
	2x2 Ceiling Panel, White, pinholes, fissures	2nd	Room 14, Center	0	050	<input type="checkbox"/>			
CF1	Cement Flue, Gray, 6" flue pipe, hard	1st	Church House	Room 109, E End	107	0	<input type="checkbox"/>	No	
CJC1	Ceiling Joint Compound, White, a/w CSR1	2nd	Church Office	Corridor Outside North Stairs, Room 16	0	059	<input type="checkbox"/>	No	
		2nd		Room 14, Center	0	054	<input type="checkbox"/>		
		2nd		Room 8, West Side	0	064	<input type="checkbox"/>		
CSR1	Ceiling Sheetrock, White	2nd	Church Office	Corridor Outside North Stairs, Room 16	0	058	<input type="checkbox"/>	No	
		2nd		Room 14, Center	0	053	<input type="checkbox"/>		
		2nd		Room 8, West Side	0	063	<input type="checkbox"/>		
ES1	Exterior Stucco, Gray/Brown, rough	1st	Church Hall	N Wall at Grills	016	0	<input type="checkbox"/>	No	0.29% Chrysotile PCV
		1st			018	0	<input type="checkbox"/>		0.3% Chrysotile PCV
ES2	Exterior Stucco, Gray, smooth	1st	Church Hall	NW at Grill Area	0	023	<input type="checkbox"/>	No	
		1st			0	024	<input type="checkbox"/>		
		1st			0	025	<input type="checkbox"/>		
ES3	Exterior Stucco, Gray, exterior ceiling stucco, rough	1st	Church Hall	North Wall	0	026	<input type="checkbox"/>	No	0.1% Chrysotile PCV
		1st		South Wall	028	0	<input type="checkbox"/>		0.39% Chrysotile PCV
		1st		West Wall	0	027	<input type="checkbox"/>		



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
ES4	Exterior Stucco, Gray, rough	1st	Church Office	Garage Room 1 at Elevator Mech Room	0	088	<input type="checkbox"/>	No	
		1st		NE Corner at Door to Courtyard	0	087	<input type="checkbox"/>		
		1st		NW Corner at Stair Exit	0	086	<input type="checkbox"/>		
		1st		SE Corner	0	089	<input type="checkbox"/>		
		1st		SW Corner	0	090	<input type="checkbox"/>		
ES5	Exterior Stucco, White, finish coat	1st	Church House	E Wall, Center	0	121	<input type="checkbox"/>	No	
		1st		N Wall, W Corner	0	129	<input type="checkbox"/>		
		1st		S Wall, W End	0	125	<input type="checkbox"/>		
		1st		SE Corner	0	123	<input type="checkbox"/>		
		1st		W Wall, Below Stairs	0	127	<input type="checkbox"/>		
ES6	Exterior Stucco, Gray, base coat	1st	Church House	E Wall, Center	0	122	<input type="checkbox"/>	No	
		1st		N Wall, W Corner	0	130	<input type="checkbox"/>		
		1st		S Wall, W End	0	126	<input type="checkbox"/>		
		1st		SE Corner	0	124	<input type="checkbox"/>		
		1st		W Wall, Below Stairs	0	128	<input type="checkbox"/>		
ES7	Exterior Stucco, Gray, rough	1st	Church Hall	Exterior S Wall, East End	022	0	<input type="checkbox"/>	No	0.2% Chrysotile PCV
		1st		Exterior, North Wall, East Corner	0	021	<input type="checkbox"/>		
		1st		Exterior, West Wall at Door	0	020	<input type="checkbox"/>		<0.1% Chrysotile PCV
ES8	Exterior Stucco, Gray	Roof	Church Hall	Upper Roof, NW Corner	042	0	<input type="checkbox"/>	No	0.2% Chrysotile PCV
		Roof		Upper Roof, SE Corner	043	0	<input type="checkbox"/>		0.29% Chrysotile PCV
FTM1	Floor Tile Mastic, Yellow, a/w 12VFT1	1st	Church Hall	Room 11, NE Corner	0	033	<input type="checkbox"/>	No	
		1st		Room 11, NW Corner	0	031	<input type="checkbox"/>		
		1st		Room 11, SW Corner	0	035	<input type="checkbox"/>		



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
HVD1	HVAC Vibration Dampener, Gray, HVAC vibration damp	1st	Church Office	Room 1A, Middle	0	103	<input type="checkbox"/>	No	
HVT1	HVAC Duct Tape, Gray, HVAC duct seam sealant, rubberl	Roof	Church Office	Center	0	082	<input type="checkbox"/>	No	
		Roof		NE Corner	0	081	<input type="checkbox"/>		
		Roof		SW Corner	0	083	<input type="checkbox"/>		
HVT2	HVAC Duct Tape, White, HVAC seam sealant, rubbery	1st	Church Office	Room 1A, Middle	0	101	<input type="checkbox"/>	No	
		1st			0	102	<input type="checkbox"/>		
		1st		Room 1A, South End	0	100	<input type="checkbox"/>		
MISC1	Miscellaneous Material, Black, felt barrier paper, smooth	1st	Church Hall	N Wall at Grills	0	017	<input type="checkbox"/>	No	
		1st			0	019	<input type="checkbox"/>		
MISC2	Miscellaneous Material, Black, felt barrier paper	1st	Church House	Middle of West Wall, Below Stairs	0	132	<input type="checkbox"/>	No	
		1st			0	133	<input type="checkbox"/>		
		1st		S Wall, W End, Inside Storage	0	131	<input type="checkbox"/>		
MISC3	Miscellaneous Material, Black, felt paper, smooth below til	Roof	Church House	E Wall, N End	0	136	<input type="checkbox"/>	No	
		Roof		S Wall, E End	0	135	<input type="checkbox"/>		
		Roof		S Wall, W End	0	134	<input type="checkbox"/>		
PJ/C1	Pipe Jacket/Covering, Gray, flue pipe cover, soft	1st	Church House	Room 109, E End	108	0	<input type="checkbox"/>	No	
RFM1	Roof Field Membrane, Rust, rolled on membrane, cap shee	Roof	Church Hall	Middle of S Wall	0	041	<input type="checkbox"/>	No	
		Roof		Middle of West Wall	0	039	<input type="checkbox"/>		
		Roof		N Wall, NE Center of Canopy	0	040	<input type="checkbox"/>		
RFM2	Roof Field Membrane, Silver/Black, rolled field membrane	Roof	Church Office	Center	0	076	<input type="checkbox"/>	No	
		Roof		N End	0	075	<input type="checkbox"/>		
		Roof		S End	0	077	<input type="checkbox"/>		



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
RPM1	Roof Penetration Mastic, Gray	Roof	Church Office	Center, HVAC Duct, Base	080	0	<input type="checkbox"/>	No	
		Roof	Church Hall	Middle of S Wall at Drain	0	038	<input type="checkbox"/>		
		Roof		West Wall, 10" Vent	036	0	<input type="checkbox"/>		
		Roof		West Wall, N End, Kitchen Exhaust	0	037	<input type="checkbox"/>		
		Roof	Church Office	West Wall, Roof Vent Pipe	079	0	<input type="checkbox"/>		
		Roof		West Wall, Wall Vent	078	0	<input type="checkbox"/>		
RS1	Shingles, Red, upper layer	Roof	Church Hall	Middle of West Wall	0	044	<input type="checkbox"/>	No	
		Roof		NE End	0	046	<input type="checkbox"/>		
		Roof		Upper Roof, SE Corner	0	048	<input type="checkbox"/>		
RS2	Shingles, Black, bottom layer	Roof	Church Hall	Middle of West Wall	0	045	<input type="checkbox"/>	No	
		Roof		NE End	0	047	<input type="checkbox"/>		
		Roof		Upper Roof, SE Corner	0	049	<input type="checkbox"/>		
SAC1	Spray-Applied Acoustic Ceiling, White, rough texture	1st	Church Hall	Room #2, Center	0	002	<input type="checkbox"/>	No	
		1st		Room #2, NW End	0	001	<input type="checkbox"/>		
		1st		Room #2, SE End	0	003	<input type="checkbox"/>		
	1st		Room 11, East Wall	0	029	<input type="checkbox"/>			
SAC2	Spray-Applied Acoustic Ceiling, White, rough	1st	Church Office	Room 1A, Middle	0	099	<input type="checkbox"/>	No	
		1st		Room 1A, North End	0	097	<input type="checkbox"/>		
		1st			0	098	<input type="checkbox"/>		
VSF1	Vinyl Sheet Flooring, Beige, square pattern	2nd	Church Office	Room 10	0	084	<input type="checkbox"/>	No	
VSF2	Vinyl Sheet Flooring, Beige, w/blue squares	3rd	Church Office	Room 21A, East Wall	0	093	<input type="checkbox"/>	No	
		3rd		Room 21A, Next to Tub	0	091	<input type="checkbox"/>		
		3rd		Room 23A, West Wall	0	095	<input type="checkbox"/>		
VSFM1	Vinyl Sheet Flooring Mastic, Yellow, a/w VSF1	2nd	Church Office	Room 10	0	085	<input type="checkbox"/>	No	



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
VSFM2	Vinyl Sheet Flooring Mastic, Yellow/White, a/w VSF2	3rd	Church Office	Room 21A, East Wall	0	094	<input type="checkbox"/>	No	
		3rd		Room 21A, Next to Tub	0	092	<input type="checkbox"/>		
		3rd		Room 23A, West Wall	0	096	<input type="checkbox"/>		
WJC1	Wall Joint Compound, White, a/w WSR1	1st	Church Office	Elevator Mech Room, Room 3, NE Corner	0	072	<input type="checkbox"/>	No	
		2nd		Corridor Outside North Stairs, Room 16	0	057	<input type="checkbox"/>		
		2nd		Room 14, East Wall	0	052	<input type="checkbox"/>		
		2nd		Room 8, West Side	0	062	<input type="checkbox"/>		
		3rd		N Stairwell, Room 26, SE Corner	0	070	<input type="checkbox"/>		
		3rd		Room 24, Kitchen, NW Corner	0	068	<input type="checkbox"/>		
		3rd		Room 8, NE Corner	0	066	<input type="checkbox"/>		
WJC2	Wall Joint Compound, White, a/w WSR2	1st	Church House	Room 106 Closet, SW	0	117	<input type="checkbox"/>	No	
WP1	Window Putty, Gray, smooth	1st	Church Hall	Exterior, N Wall Outside Kitchen Room 5	014	0	<input type="checkbox"/>	No	
		1st		Exterior, West Wall Outside Kitchen, Room 5	015	0	<input type="checkbox"/>		
WP2	Window Putty, White/Gray	1st	Church House	E Wall, N End	0	120	<input type="checkbox"/>	No	
		1st		E Wall, S End	0	119	<input type="checkbox"/>		
		1st		Middle of S Wall	0	118	<input type="checkbox"/>		
WPB1	Wall Plaster Brown Coat, Gray	1st	Church Hall	Room #1, West of East Wall	0	010	<input type="checkbox"/>	No	
		1st		Room #1, West Side at Stage	0	008	<input type="checkbox"/>		
		1st		Room #10, Men's RR, NE End	0	012	<input type="checkbox"/>		



TABLE 2.0
SUMMARY BY MATERIAL
Project Number 1097.1002.0

Our Lady of Mt. Lebanon
333 S. San Vicenta Blvd, Los Angeles, CA 90048
Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
WPB1	Wall Plaster Brown Coat, Gray	1st	Church Hall	Room #4, Janitor Closet	0	004	<input type="checkbox"/>	No	
		1st		Room #8, Kitchen Closet, North	0	006	<input type="checkbox"/>		
WPF1	Wall Plaster Finish Coat, White, a/w WPB1	1st	Church Hall	Room #1, West of East Wall	0	011	<input type="checkbox"/>	No	<0.1% Chrysotile PCV
		1st		Room #1, West Side at Stage	0	009	<input type="checkbox"/>		<0.1% Chrysotile PCV
		1st		Room #10, Men's RR, NE End	0	013	<input type="checkbox"/>		<0.1% Chrysotile PCV
		1st		Room #4, Janitor Closet	005	0	<input type="checkbox"/>		0.2% Chrysotile
		1st		Room #8, Kitchen Closet, North	0	007	<input type="checkbox"/>		0.1% Chrysotile PCV
WPF2	Wall Plaster Finish Coat, Gray, troweled on, rough	1st	Church House	Room 109, Center, Ceiling	0	106	<input type="checkbox"/>	No	
		1st		Room 109, N Wall	0	104	<input type="checkbox"/>		
		1st		Room 109, S Wall	0	105	<input type="checkbox"/>		
WPF3	Wall Plaster Finish Coat, Beige, smooth	1st	Church House	Hallway Closet Below Stairs	0	109	<input type="checkbox"/>	No	
		1st		Room 102, E Wall, N End	0	111	<input type="checkbox"/>		
		1st		Room 105, NW Corner, Kitchen	0	112	<input type="checkbox"/>		
		1st		Room 106, N Wall at Closet	0	110	<input type="checkbox"/>		
		2nd		Room 200, Hallway, S Closet	0	115	<input type="checkbox"/>		
		2nd		Room 202, RR, NW Corner	0	114	<input type="checkbox"/>		
		2nd		Room 207, RR, E Wall	0	113	<input type="checkbox"/>		
WSR1	Wall Sheetrock, White	1st	Church Office	Elevator Mech Room, Room 3, NE Corner	0	071	<input type="checkbox"/>	No	
		2nd		Corridor Outside North Stairs, Room 16	0	056	<input type="checkbox"/>		



**TABLE 2.0
SUMMARY BY MATERIAL**

Project Number 1097.1002.0

Our Lady of Mt. Lebanon

333 S. San Vicenta Blvd, Los Angeles, CA 90048

Updated 9/5/2017

Homogeneous Materials	Material Description	Original Location			Sample Results:		Not Analyzed	100% Abated	Comments
		Floor	Room	Area	Positive	Negative			
WSR1	Wall Sheetrock, White	2nd	Church Office	Room 14, East Wall	0	051	<input type="checkbox"/>	No	
		2nd		Room 8, West Side	0	061	<input type="checkbox"/>		
		3rd		N Stairwell, Room 26, SE Corner	0	069	<input type="checkbox"/>		
		3rd		Room 24, Kitchen, NW Corner	0	067	<input type="checkbox"/>		
		3rd		Room 8, NE Corner	0	065	<input type="checkbox"/>		
WSR2	Wall Sheetrock, White	1st	Church House	Room 106 Closet, SW	0	116	<input type="checkbox"/>	No	



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix E

Asbestos Laboratory Results



LA Testing

520 Mission Street South Pasadena, CA 91030

Phone/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321721450

Customer ID: 32CITA50

Customer PO:

Project ID:

Attention: Jeff Klein
Citadel Environmental Services, Inc.
1725 Victory Boulevard
Glendale, CA 91201

Phone: (818) 246-2707
Fax:
Received: 09/08/2017 1:35 PM
Analysis Date: 09/12/2017
Collected:

Project: Reference Order: 321719809/ Our Lady of Mt. Lebanon - 1097.1002.0

Test Report: Asbestos Analysis of Bulk Material via EPA 600/R-93/116. Quantitation using the 1,000 Point Count Procedure

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WPF1-005 321721450-0001	Church Hall Level 1 Room #4 Janitor Closet - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		99.8% Non-fibrous (Other)	0.2% Chrysotile
WPF1-007 321721450-0002	Church Hall Level 1 Room #8 Kitchen Closet North - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		99.9% Non-fibrous (Other)	0.1% Chrysotile
WPF1-009 321721450-0003	Church Hall Level 1 Room #1 - West Side at Stage - White Wall Plaster Base Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<0.1% Chrysotile
WPF1-011 321721450-0004	Church Hall Level 1 Room #1CEnter of East Wall - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<0.1% Chrysotile
WPF1-013 321721450-0005	Church Hall Level 1 Room #10 News RR NE End - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<0.1% Chrysotile
ES1-016-Comp 321721450-0006	Church Hall Level 1 No Wall @ Grills - Gray Brown Exterior Wall Stucco - Rough	Gray Non-Fibrous Homogeneous		99.71% Non-fibrous (Other)	0.29% Chrysotile
ES1-018-Comp 321721450-0007	Church Hall Level 1 No Wall @ Grills - Hry/Brown Exterior Wall Stucco - Rough	Gray/Tan Non-Fibrous Heterogeneous		99.7% Non-fibrous (Other)	0.3% Chrysotile
ES1-020 321721450-0008	Church Hall Level 1 Exterior - West Wall @ Door - Gray Exterior Wall Stucco Rough	Gray/Beige Non-Fibrous Heterogeneous		100% Non-fibrous (Other)	<0.1% Chrysotile
ES1-022 321721450-0009	Church Hall Level 1 Exterior - South Wall East End - Gray Exterior Wall Stucco Rough	Gray Non-Fibrous Homogeneous		99.8% Non-fibrous (Other)	0.2% Chrysotile

Some samples may contain asbestos fibers present in dimensions below PLM resolution limits. The limit of detection as stated in the method is 0.1%. EMSL Analytical Inc suggests that samples reported as <0.1% or none detected undergo additional analysis via TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval EMSL Analytical Inc. This test report must not be used by the client to claim product endorsement by NVLAP or any agency of the United States Government. EMSL Analytical Inc. bears no responsibility for sample collection activities, analytical method limitations, or the accuracy of results when requested to separate layered samples. EMSL Analytical Inc liability is limited to the cost of sample analysis. The test results contained within this report meet the requirements of NELAC unless otherwise noted. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by LA Testing South Pasadena, CA NVLAP Lab Code 200232-0, CA ELAP 2283

Initial report from: 09/12/2017 09:12:18



LA Testing

520 Mission Street South Pasadena, CA 91030
Phone/Fax: (323) 254-9960 / (323) 254-9982
<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321721450
Customer ID: 32CITA50
Customer PO:
Project ID:

Attention: Jeff Klein
Citadel Environmental Services, Inc.
1725 Victory Boulevard
Glendale, CA 91201

Phone: (818) 246-2707
Fax:
Received: 09/08/2017 1:35 PM
Analysis Date: 09/12/2017
Collected:

Project: Reference Order: 321719809/ Our Lady of Mt. Lebanon - 1097.1002.0

Test Report: Asbestos Analysis of Bulk Material via EPA 600/R-93/116. Quantitation using the 1,000 Point Count Procedure

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
ECS1-026 321721450-0010	Church Hall Level 1 North Wall - Gray Exterior Ceiling Stucco Rough	Gray Non-Fibrous Homogeneous		99.9% Non-fibrous (Other)	0.1% Chrysotile
ECS1-028 321721450-0011	Church Hall Level 1 South Wall - Gray Exterior Ceiling Stucco Rough	Gray Non-Fibrous Homogeneous		99.61% Non-fibrous (Other)	0.39% Chrysotile
ES1-042 321721450-0012	Church Hall Level Roof - Upper Roof - NW Corner - Gray Exterior Wall Stucco	Gray Non-Fibrous Homogeneous		99.8% Non-fibrous (Other)	0.2% Chrysotile
ES1-043 321721450-0013	Church Hall Level Roof - Upper Roof -SE Corner - Gray Exterior Wall Stucco	Gray Non-Fibrous Homogeneous		99.71% Non-fibrous (Other)	0.29% Chrysotile

Analyst(s)

Rosa Mendoza (13)

Jerry Drapala Ph.D, Laboratory Manager
or other approved signatory

Some samples may contain asbestos fibers present in dimensions below PLM resolution limits. The limit of detection as stated in the method is 0.1%. EMSL Analytical Inc suggests that samples reported as <0.1% or none detected undergo additional analysis via TEM. The above test report relates only to the items tested. This report may not be reproduced, except in full, without written approval EMSL Analytical Inc. This test report must not be used by the client to claim product endorsement by NVLAP or any agency of the United States Government. EMSL Analytical Inc. bears no responsibility for sample collection activities, analytical method limitations, or the accuracy of results when requested to separate layered samples. EMSL Analytical Inc liability is limited to the cost of sample analysis. The test results contained within this report meet the requirements of NELAC unless otherwise noted. Samples received in good condition unless otherwise noted. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample.

Samples analyzed by LA Testing South Pasadena, CA NVLAP Lab Code 200232-0, CA ELAP 2283

Initial report from: 09/12/2017 09:12:18



LA Testing

520 Mission Street South Pasadena, CA 91030
 Tel/Fax: (323) 254-9960 / (323) 254-9982
<http://www.LATesting.com/pasadenalab@lateesting.com>

LA Testing Order: 321719809
Customer ID: 32CITA50
Customer PO:
Project ID:

Attention: Jeff Klein
 Citadel Environmental Services, Inc.
 1725 Victory Boulevard
 Glendale, CA 91201

Phone: (818) 246-2707

Fax:

Received Date: 08/18/2017 3:30 PM

Analysis Date: 08/25/2017

Collected Date: 08/14/2017

Project: Our Lady of Mt. Lebanon - 1097.1002.0

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
SAL1-001 321719809-0001	Church Hall Level 1 Room #2 NW End - White Spray Applies Acoustic Ceiling Rough Texture	White/Gold Non-Fibrous Heterogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
SAL1-002 321719809-0002	Church Hall Level 1 Room#2 Centet - White Spray Applies Acoustic Ceiling Rough Texture	White Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
SAL1-003 321719809-0003	Church Hall Level 1 Room #2 OF end - White Spray Applies Acoustic Ceiling Rough Texture	Gray Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
WPB1-004 321719809-0004	Church Hall Level 1 Rpp, #4 - Janitor Closet - Gray Wall Plaster - Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF1-005 321719809-0005	Church Hall Level 1 Room #4 Janitor Closet - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
WPB1-006 321719809-0006	Church Hall Level 1 Room #8 - Kitchen Closet North - Gray Wall Plaster Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF1-007 321719809-0007	Church Hall Level 1 Room #8 Kitchen Closet North - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
WPB1-008 321719809-0008	Church Hall Level 1 Room #1 - West Side at Stage - Gray Wall Plaster Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF1-009 321719809-0009	Church Hall Level 1 Room #1 - West Side at Stage - White Wall Plaster Base Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
WPB1-010 321719809-0010	Church Hall Level 1 Room #1Center of East Wall - Gray Wall Plaster Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF1-011 321719809-0011	Church Hall Level 1 Room #1Center of East Wall - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WPB1-012 321719809-0012	Church Hall Level 1 Room #10 News RR- NE End - Gray Wall Plaster Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF1-013 321719809-0013	Church Hall Level 1 Room #10 News RR- NE End - White Wall Plaster Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
WP1-014 321719809-0014	Church Hall Level 1Exterior - North Wall Outside Kitchen (RMS) - Gray Window Putty Smooth	Beige Non-Fibrous Homogeneous		98% Non-fibrous (Other)	2% Chrysotile
WP1-015 321719809-0015	Church Hall Level 1 Exterior - West Wall Outside Kitchen Rm5 - Gray Window Putty Smooth	Gray Non-Fibrous Homogeneous		97% Non-fibrous (Other)	3% Chrysotile
ES1-016-Comp 321719809-0016	Church Hall Level 1 No Wall @ Grills - Gray Brown Exterior Wall Stucco - Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
MISC1-017 321719809-0017	Church Hall Level 1 No Wall @ Grills - Black Felt Paper Barrier - Smooth	Black Fibrous Homogeneous	70% Cellulose	30% Non-fibrous (Other)	None Detected
ES1-018-Comp 321719809-0018	Church Hall Level 1 No Wall @ Grills - Hry/Brown Exterior Wall Stucco - Rough	Gray/Tan Non-Fibrous Heterogeneous		100% Non-fibrous (Other)	<1% Chrysotile
MISC1-019 321719809-0019	Church Hall Level 1 No Wall @ Grills - Black Felt Paper Barrier Smooth	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected
ES1-020 321719809-0020	Church Hall Level 1 Exterior - West Wall @ Door - Gray Exterior Wall Stucco Rough	Gray/Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
ES1-021 321719809-0021	Church Hall Level 1 Exterior - No wall East Center - Gray Exterior Wall Stucco Rough	Gray/Beige Non-Fibrous Heterogeneous		100% Non-fibrous (Other)	None Detected
ES1-022 321719809-0022	Church Hall Level 1 Exterior - South Wall East End - Gray Exterior Wall Stucco Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
ES2-023 321719809-0023	Church Hall Level 1 NW @ Grill Area - Gray Ext Wall Stucco Smooth Finish	Gray/Beige Non-Fibrous Heterogeneous		100% Non-fibrous (Other)	None Detected
ES2-024 321719809-0024	Church Hall Level 1 NW @ Grill Area - Gray Ext Wall Stucco Smooth Finish	Gray/Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
ES2-025 321719809-0025	Church Hall Level 1 NW @ Grill Area - Gray Ext Wall Stucco Smooth Finish	Gray Non-Fibrous Heterogeneous		100% Non-fibrous (Other)	None Detected
ECS1-026 321719809-0026	Church Hall Level 1 North Wall - Gray Exterior Ceiling Stucco Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
ECS1-027 321719809-0027	Church Hall Level 1 West Wall - Gray Exterior Ceiling Stucco Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ECS1-028 321719809-0028	Church Hall Level 1 South Wall - Gray Exterior Ceiling Stucco Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
SAC1-029 321719809-0029	Church Hall Level 1 Room 11 East Wall - White Spray Applied Acoustic Ceiling - Textures	White Non-Fibrous Homogeneous		2% Mica 98% Non-fibrous (Other)	None Detected
12VFT 030 321719809-0030	Church Hall Level 1 - NW Corner Room 11 - Beige 12'x12' FT With Brown Mottles	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
FTM1-031 321719809-0031	Church Hall Level 1 - NW Corner Room 11 - Yellow - FT Mastic A/W 12VFT1	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
12VFT1-032 321719809-0032	Church Hall Level 1 - NE Corner Room 11 - Beige 12'x12' VFT W/ Brn Mottles	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
FTM1- 033 321719809-0033	Church Hall Level 1 - NE Corner Room 11 - Yellow FT Mastic A/W 12vft1	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
12VFT1-034 321719809-0034	Church Hall Level 1 - SW Corner Room 11 - Beige 12'x12' VFT w/ Brn Mottles	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
FTM1-035 321719809-0035	Church Hall Level 1 - SW Corner Room 11 - Yellow - FT Mastic A/W 12VFT1	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
RFM1-036 321719809-0036	Church Hall Level 1 - West Wall 10' Vent - Grey Roof Renetration Mastic	Black Non-Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile
BPM1-037 321719809-0037	Church Hall Level Roof - West Wall - North End Rt eshaust - Grey Roof Renetration Mastic	Black Non-Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected
RPM1-038 321719809-0038	Church Hall Level Roof - Middle if go, wall @ drain - Grey Roof Renetration Mastic	Black Non-Fibrous Homogeneous	10% Cellulose	90% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@lateesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
RFM1-039 321719809-0039	Church Hall Level Roof - Middle of West Wall - Rust Rolled on Field Membrane Cap Sheet	Red/Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RFM1-040 321719809-0040	Church Hall Level Roof - N Wall - NEC of canopy - Rust Rolled on Field Membrane Cap Sheet	Red/Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RFM1-041 321719809-0041	Church Hall Level Roof - Middle of S Wall - Rust Rolled on Field Membrane Cap Sheet	Red/Black Fibrous Heterogeneous	20% Synthetic	80% Non-fibrous (Other)	None Detected
ES1-042 321719809-0042	Church Hall Level Roof - Upper Roof - NW Corner - Gray Exterior Wall Stucco	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
ES1-043 321719809-0043	Church Hall Level Roof - Upper Roof - SE Corner - Gray Exterior Wall Stucco	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	<1% Chrysotile
RS1-044 321719809-0044	Church Hall Level Roof - Middle of West Wall - Red Roof Shingle Upper Layer	Red/Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RS2-045 321719809-0045	Church Hall Level Roof - Middle of West Wall - Black Roof Shingle Bottom Layer	Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RS1-046 321719809-0046	Church Hall Level Roof - North East End - Red Roof Shingle Upper Layer	Red/Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RS2-047 321719809-0047	Church Hall Level Roof - North East End - Black Roof Shingles Bottom Layer	Black Fibrous Heterogeneous	20% Glass	80% Non-fibrous (Other)	None Detected
RS1-048 321719809-0048	Church Hall Level Roof - Upper Roof SE Corner - Red Roof Shingle Upper Layer	Red/Black Fibrous Heterogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
RS2-049 321719809-0049	Church Hall Level Roof - Upper Roof SE Corner - Black Roof Shingles Lower Layer	Black Fibrous Heterogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
2CP1-050 321719809-0050	Church Hall Level 2 - Room 14 Center - White 2'x2' Lay Ceiling Panel Pinholes/Fissures Sheetrock	Gray/White Fibrous Heterogeneous	40% Cellulose 20% Min. Wool	20% Perlite 20% Non-fibrous (Other)	None Detected
WSR1-051 321719809-0051	Church Hall Level 2 - Room 14 East Wall - White 2'x2' Lay Ceiling Panel Pinholes/Fissures Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WJC1-052 321719809-0052	Church Hall Level 2 - Room 14 East Wall - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
CSR1-053 321719809-0053	Church Hall Level 2 - Room 14 Center - White Ceiling Sheetrock	Brown/Pink Fibrous Heterogeneous	15% Cellulose 2% Glass	83% Non-fibrous (Other)	None Detected
CJC1-054 321719809-0054	Church Hall Level 2 - Room 12 Center - White Ceiling Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
2CP1-055 321719809-0055	Church Hall Level 2 - Corridor Outside North Stairs Rm 16 - White 2'x2' Lay Ceiling Panel	Gray/White Fibrous Heterogeneous	40% Cellulose 20% Min. Wool	20% Perlite 20% Non-fibrous (Other)	None Detected
WSR1-056 321719809-0056	Church Hall Level 2 - Corridor Outside North Stairs Rm 16 - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
WJC1-057 321719809-0057	Church Hall Level 2 - Corridor Outside North Stairs Rm 16 - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
CSR1-058 321719809-0058	Church Hall Level 2 - Corridor Outside North Stairs Rm 16 - White Ceiling Sheetrock	Brown/White Fibrous Heterogeneous	15% Cellulose 2% Glass	83% Non-fibrous (Other)	None Detected
CJC-059 321719809-0059	Church Hall Level 2 - Corridor Outside North Stairs Rm 16 - White Ceiling Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
2CP1-060 321719809-0060	Church Hall Level 2 - Room 8 NE Side - White 2'x2' Lay Ceiling Panel	Gray/White Fibrous Heterogeneous	40% Cellulose 20% Min. Wool	20% Perlite 20% Non-fibrous (Other)	None Detected
WSR1-061 321719809-0061	Church Hall Level 2 - Room 8 NE Side - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
WJC1-062 321719809-0062	Church Hall Level 2 - Room 8 NE Side - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
CSR1-063 321719809-0063	Church Hall Level 2 - Room 8 NE Side - White Ceiling Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
CJC1-064 321719809-0064	Church Hall Level 2 - Room 8 West Side - White Ceiling Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WSR1-065 321719809-0065	Church Hall Level 3 - Room 8 NE Corner - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@lateesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WJC1-066 321719809-0066	Church Hall Level 3 - Room 8 NE Corner - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WSR1-067 321719809-0067	Church Hall Level 3 - Room24Kitchen N/E Corner - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
WJC11-068 321719809-0068	Church Hall Level 3 - Room 24 Kitchen NW Corner - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WSR1-069 321719809-0069	Church Hall Level 3 - North Stairwell Rm 26 SE Corner - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose 2% Glass	78% Non-fibrous (Other)	None Detected
WJC1-070 321719809-0070	Church Hall Level 3 - North Stairwell Rm 26 SE Corner - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WSR1-071 321719809-0071	Church Hall Level 1 - Elevator Mech Rm, Room 3 NE Corner - White4 Wall Sheetrock	Brown/White Fibrous Heterogeneous	15% Cellulose 2% Glass	83% Non-fibrous (Other)	None Detected
WJC1-072 321719809-0072	Church Hall Level 1 - Elevator Mech Rm Rm 3 NE Corner - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
2CP1-073 321719809-0073	Church Hall Level 2 - Main Corridor between Rms 12&13 - White 2'x2' Lay in Ceiling Panel	Gray/White Fibrous Heterogeneous	40% Cellulose 20% Min. Wool	20% Perlite 20% Non-fibrous (Other)	None Detected
2CP1-074 321719809-0074	Church Hall Level 2 - Rm 15 NE corner - White 2'x2' Lay in Ceiling Panel	White/Beige Fibrous Homogeneous	50% Cellulose	30% Perlite 20% Non-fibrous (Other)	None Detected
RFM2-075 321719809-0075	Church Hall Roof North End - Black/Silver Rollers on Field Memb. w/ Felts	White/Black Fibrous Heterogeneous	15% Glass	85% Non-fibrous (Other)	None Detected
RFM2-076 321719809-0076	Church Hall Roof - Center - Black/Silver Rollers on Field Memb. w/ Felts	White/Black Fibrous Heterogeneous	15% Glass	85% Non-fibrous (Other)	None Detected
RFM2-077 321719809-0077	Church Hall Roof - South End - Black/Silver Rollers on Field Memb. w/ Felts	Gray/Black Fibrous Heterogeneous	10% Glass	90% Non-fibrous (Other)	None Detected
RPM1-078 321719809-0078	Church Hall Roof - West Wall - Wall vent - Gray Penetration Mastic	Black Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
RPM1-079 321719809-0079	Church Hall Roof - West Wall - Roof Vent Pipe - Gray Penetration Mastic	Black Non-Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile
RPM1-080 321719809-0080	Church Hall Roof - Center - HVAC Duct Base - Gray Penetration Mastic	Gray/Black Non-Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile
HVT1-081 321719809-0081	Church Hall Roof - North East Corner - Gray HVAC Duct Seam Sealant Rubber Like	White Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
HVT1-082 321719809-0082	Church Hall Roof - Center - Gray HVAC Duct Seam Sealant Rubber Like	White Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
HVT1-083 321719809-0083	Church Hall Roof - South West Corner - Gray HVAC Duct Seam Sealant Rubber Like	Gray/Beige Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
VSF1-084 321719809-0084	Church Hall Level 2 - Rm 10 - Beige Vinyl Sheet Flooring Square Pattern	Beige Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
SFM1-085 321719809-0085	Church Hall Level 2 - Rm 10 - Yellow Mastic A/W VSF1	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES3-086 321719809-0086	Church Hall Level 1 - North West Corner at Stair Exit - Gray Exterior Wall Stucco Rough Finish	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES3-087 321719809-0087	Church Hall Level 1 - North East Corner at Door to Courtyard - Gray Exterior Wall Stucco Rough Finish	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES3-088 321719809-0088	Church Hall Level 1 - Garage Rm 1 @ elevator mech room - Gray Exterior Wall Stucco Rough Finish	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES3-089 321719809-0089	Church Hall Level 1 - South East Corner - Gray Exterior Wall Stucco Rough Finish	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES3-090 321719809-0090	Church Hall Level 1 - South West Corner - Gray Exterior Wall Stucco Rough Finish	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
VSF2-091 321719809-0091	Church Hall Level 3 - Room 2A Next to Tub - Beige Vinyl Sheet Flooring w/ Blue Squares	White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
SFM2-092 321719809-0092	Church Hall Level 3 - Room 2A Next to Tub - Yellow/White Mastic A/W VSF 2	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
VSF2-093 321719809-0093	Church Hall Level 3 - Room 2A East Wall - Beige Vinyl Sheet Flooring w/ Blue Square	Beige Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
SFM2-094 321719809-0094	Church Hall Level 3 - Room 2A East Wall - Yellow/White Sheet Flooring Mastic A/W VSF 2	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
VSF2-095 321719809-0095	Church Hall Level 3 - Room 2A West Wall - Beige Vinyl Sheet Flooring w/ blue squares	Beige Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
SFM2-096 321719809-0096	Church Hall Level 3 - Room 2A West Wall - Yellow/White Mastic A/W VSF 2	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
SAL2-097 321719809-0097	Church Hall Level 1 - Room1A North End - White Spray Acoustic Ceiling Rough	White/Gold Non-Fibrous Heterogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
SAC2-098 321719809-0098	Church Hall Level 1 - Room1A North End - White Spray Acoustic Ceiling Rough	White/Gold Non-Fibrous Heterogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
SAC2-099 321719809-0099	Church Hall Level 1 - Room1A Middle - White Spray Acoustic Ceiling Rough	White/Beige Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
HVT2-100 321719809-0100	Church Hall Level 1 - Room 1A South End - White HVAC Seam Sealant Rubbery	White Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
HVT2-101 321719809-0101	Church Hall Level 1 - Room 1A Middle - White HVAC Seam Sealant Rubbery	White Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
HVT2-102 321719809-0102	Church Hall Level 1 - Room 1A Middle - White HVAC Seam Sealant Rubbery	Beige Non-Fibrous Homogeneous		5% Mica 95% Non-fibrous (Other)	None Detected
AVD1-103 321719809-0103	Church Hall Level 1 - Room 1A Middle - Gray HVAC Vibration Damper Smooth	Gray Fibrous Homogeneous	10% Synthetic	90% Non-fibrous (Other)	None Detected
WPF2-104 321719809-0104	Church Hall Level 1 - Room 109 North Wall - Gray Wall Plaster Troweles on Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF2-105 321719809-0105	Church Hall Level 1 - Room 109 South Wall - Gray Wall Plaster Troweles on Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WPF2-106 321719809-0106	Church Hall Level 1 - Room 109 Center - Gray Wall Plaster Troweles on Rough	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
CF1-107 321719809-0107	Church Hall Level 1 - Room 109 East End - Gray 6" Flue Pipe HARD	Beige Fibrous Homogeneous		90% Non-fibrous (Other)	10% Chrysotile
PJ/C1 -108 321719809-0108	Church Hall Level 1 - Room 109 East End - Flue Pipe Cover soft	Beige Fibrous Homogeneous		40% Non-fibrous (Other)	60% Chrysotile
WPF3-109 321719809-0109	Church Hall Level 1 - Hallway Closet Below Stairs - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF3-110 321719809-0110	Church Hall Level 1 - Room 106 North Wall @ Closet - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF3-111 321719809-0111	Church Hall Level 1 - Room 102 East Wall North End - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF3-112 321719809-0112	Church Hall Level 1 - Room 105- NW Corner Kitchen - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
W[F3-113 321719809-0113	Church Hall Level 2 - Room 207 RR East Wall - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF3-114 321719809-0114	Church Hall Level 2 - Room 202 RR North East Corner - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WPF3-115 321719809-0115	Church Hall Level 2 - Room 200 Hallway South Closet - Beige Wall Plaster Smooth	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WSR2-116 321719809-0116	Church Hall Level 1 - Room 106 Closet South Vent - White Wall Sheetrock	Brown/White Fibrous Heterogeneous	20% Cellulose	80% Non-fibrous (Other)	None Detected
WJ42-117 321719809-0117	Church Hall Level 1 - Room 106 Closet South Vent - White Wall Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WP2-118 321719809-0118	Church Hall Level 1 - Middle of South Wall - white/gray Window Putty Throw	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
WP2-119 321719809-0119	Church Hall Level 1 - East Wall - South End - white/gray Window Putty Throw	Gray/White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
WP2-120 321719809-0120	Church Hall Level 1 - East Wall - No End - white/gray Window Putty Throw	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES4-121 321719809-0121	Church Hall Level 1 - East Wall Center - White Ext. Wasll Stucco Finish Coat	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES5-122 321719809-0122	Church Hall Level 1 - East Wall Center - Gray Ext. Wall Stucco Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES4-123 321719809-0123	Church Hall Level 1 - South East Corner - White Ext. Wasll Stucco Finish Coat	Beige Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES5-124 321719809-0124	Church Hall Level 1 - South East Corner - Gray Ext. Wall Stucco Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES54-125 321719809-0125	Church Hall Level 1 - South Wall West End - White Ext. Wasll Stucco Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES5-126 321719809-0126	Church Hall Level 1 - South Wall West End - Gray Ext. Wall Stucco Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES4-127 321719809-0127	Church Hall Level 1 - West Wall Below Stairs - White Ext. Wasll Stucco Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES5-128 321719809-0128	Church Hall Level 1 - West Wall West Corner - Gray Ext. Wall Stucco Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES4-129 321719809-0129	Church Hall Level 1 - No Wall West Corner - White Ext. Wasll Stucco Finish Coat	White Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
ES5-130 321719809-0130	Church Hall Level 1 - No wall West Corner - Gray Ext. Wall Stucco Base Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (Other)	None Detected
MBE2-131 321719809-0131	Church Hall Level 1 - South Wall West End Inside Storage - Black Felt Paper Barrier	Black Fibrous Homogeneous	70% Cellulose	30% Non-fibrous (Other)	None Detected
MISC2-132 321719809-0132	Church Hall Level 1 - Middle of West Wall Below Stairs - Black Felt Paper Barrier	Black Fibrous Homogeneous	70% Cellulose	30% Non-fibrous (Other)	None Detected
MISC2-133 321719809-0133	Church Hall Level 1 - Middle of West Wall Below Stairs - Black Felt Paper Smooth Below Tile	Black Fibrous Homogeneous	80% Cellulose	20% Non-fibrous (Other)	None Detected

Initial report from: 08/25/2017 15:16:21



LA Testing

520 Mission Street South Pasadena, CA 91030

Tel/Fax: (323) 254-9960 / (323) 254-9982

<http://www.LATesting.com> / pasadenalab@latesting.com

LA Testing Order: 321719809

Customer ID: 32CITA50

Customer PO:

Project ID:

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
MISC3-134 321719809-0134	Church Hall Level Roof - South Wall West End - Black Felt Paper Smooth Below Tile	Brown/White/Black Fibrous Homogeneous	70% Cellulose	30% Non-fibrous (Other)	None Detected
MISC3-135 321719809-0135	Church Hall Level Roof - South Wall East End - Black Felt Paper Smooth Below Tile	Brown/White/Black Fibrous Homogeneous	70% Cellulose	30% Non-fibrous (Other)	None Detected
MISC3-136 321719809-0136	Church Hall Level Roof - East Wall North End - Black Felt Paper Smooth Below Tile	Black Fibrous Homogeneous	60% Cellulose	40% Non-fibrous (Other)	None Detected

Analyst(s)

Julie Vong (44)

Rosa Mendoza (92)

Jerry Drapala Ph.D, Laboratory Manager
or Other Approved Signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%

Samples analyzed by LA Testing South Pasadena, CA NVLAP Lab Code 200232-0, CA ELAP 2283

Initial report from: 08/25/2017 15:16:21

321719809

CITADEL ENVIRONMENTAL SERVICES, INC. CHAIN OF CUSTODY



CITADEL LOCATION:

<input checked="" type="checkbox"/> GLENDALE	<input type="checkbox"/> VALENCIA	<input type="checkbox"/> ORANGE COUNTY	<input type="checkbox"/> TORRANCE OFFICE
Contact: Jeff Klein email: _____ 1725 Victory Boulevard Glendale, CA 91201 Phone: (818) 246-2707 Fax: (818) 246-3145	Contact: _____ email: _____ 28212 Kelly Johnson Parkway, Suite 250 Valencia, CA 91355 Phone: (661) 257-9009 Fax: (661) 257-9019	Contact: _____ email: _____ 151 Kalmus Drive, Suite F-4 Costa Mesa, CA 92626 Phone: (714) 547-4301 Fax: (714) 547-4647	Contact: _____ email: _____ 3700 West 190th Street Torrance, CA 90509 Phone: (310) 212-4113 Fax: (818) 246-3415

PROJECT AND SAMPLE INFORMATION

PROJECT NUMBER: 1097.1002.0

PROJECT NAME: Our Lady of Mt. Lebanon Contact: _____

NUMBER OF SAMPLES: 136 SAMPLE NUMBERS: 001-136

TYPE OF SAMPLES (CIRCLE ONE):

AIR	TAPE	WATER	ANDERSEN PLATE	
Bulk	SOIL	WIPE	ZEFON	OTHER
			AIR-O-CELL	

TYPE OF ANALYSIS:

Asbestos

Phase Contrast Microscopy _____

Polarized Light Microscopy _____

1st Positive Stop (per H.A.) _____

Point Count _____ 400 Point Count _____ 1000 Point Count _____

Transmission Electron Microscopy _____

Qualitative _____ Quantitative _____

Lead

Flame Atomic Absorption _____

TTLc _____ STLC _____ TCLP _____

Culturable Air

Andersen Fungi (genue ID, Aspergillus) _____

Andersen Bacteria _____

Non-Culturable Air

Non-Viable Spore Trap /Air-o-Cell _____

Surface Samples

Surface Sample (direct examination) _____

Culturable Samples

Quantitative Fungi-dust, bulk swab-1 medium _____

Quantitative Fungi-dust, bulk swab-3 media _____

Quantitative Bacteria-dust, bulk swab-1 medium _____

Quantitative Bacteria-dust, bulk, swab-3 media _____

Sewage Contamination _____

Other _____

TURNAROUND TIME (CIRCLE ONE):

3 Hours 24 Hours 48 Hours 3 Days

5 Days 5-10 Days Other

REPORT RESULTS VIA (CIRCLE ALL THAT APPLY):

VERBAL FAX WRITTEN REPORT **PDF**

NOTES/COMMENTS: Email to: jklein@citadelenvironmental.com

TRANSMITTAL RECORD:

Relinquished By: Jeffrey Klein	Received By:
Date: 8/18/2017 Time: 12:00	Date: 8/18/17 Time: 1530
Relinquished By: _____	Received By: _____
Date: _____ Time: _____	Date: _____ Time: _____

LABORATORY INFORMATION: NAME: LA Testing - LOCATION: South Pasadena, CA

DISPOSITION OF SAMPLES:

RETURN _____ DAYS AFTER ANALYSIS OTHER _____

RETAIN FOR _____ DAYS YEAR (S) _____

#321719809

BULK SAMPLE DATA FORM

PROJECT NO.: 1097 10020	DATE: 081417	PAGE 1
CLIENT: WRSSR	INSPECTOR(S): Jeffrey Klein	OF
PROJECT ID: Our Lady of Mt. Lebanon	CSST/CAC NO: CAC 07-4240	11



HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
SAC(1)	001	white	SPRAY Applied Acoustic ceiling Rough Texture	church Hall	1	Room #2 NW END	864	SF	F	G	N/A
SAC(1)	002	↓	↓			" CENTER	↓		↓		↓
SAC(1)	003	↓	↓			" SE END	↓		↓		↓
WPB(1)	004	Gray	Wall plaster - BASE COAT			Room #4 - Junk box closet			NF	G	N/A
WPF(1)	005	white	" " Finish COAT			↓					
WPB(1)	006	gray	Wall plaster BASE COAT			Room #8 - (Kitchen) closet (North)					
WPF(1)	007	white	" " Finish COAT			↓					
WPB(1)	008	gray	Wall plaster BASE COAT			Room #1 - WEST SIDE AT Stage					
WPF(1)	009	white	Wall plaster Finish COAT			↓					
WPB(1)	010	gray	Wall plaster BASE COAT			Room #1 - CREAT. OF EAST Wall					
WPF(1)	011	white	Wall plaster Finish COAT			↓					
WPB(1)	012	gray	Wall plaster BASE COAT			Room #10 - Mens RR - NE END					
WPF(1)	013	white	Wall plaster Finish COAT			↓					
WP(1)	014	gray	Window Poly - Smooth			EXTERIOR - NO WALL OUTSIDE Kitchen (RMS)	5	EA	NA	G	N/A

PROJECT NO.: 1097 1002 0

CLIENT: WRSSR

PROJECT ID: OUR LADY of Mt. Lebanon

SITE ADDRESS: _____

DATE: 08 14 17


INSPECTOR(S): Jeffrey Klein

CSSST/CAC NO: CAC 07-4240




PAGE 2
OF 11

HA TYPE HA NO.	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
WP(1)	015	gray	Window Putty - Smooth	Church Hall	1	EXTERIOR - West Wall Outside Kitchen (RM 5)			NF	G	N/A
ES(1)	016	Brown	Exterior Stucco (Rough) Wall			No. Wall @ GRILL			NF	D	P
MIX(1) ES(2)	017	Black	Felt Paper Barrier (Smooth)						F	D	P
ES(1)	018	Green	Exterior Wall Stucco - Rough						NF	D	P
MIX(1)	019	Black	Felt Paper Barrier Smooth						F	D	P
ES(1)	020	Gray	Ext. Wall Stucco - Rough			EXTERIOR - WEST WALL @ DOOR			NF	G	N/A
ES(1)	021	gray	Ext. Wall Stucco - Rough			Ext. - NO. WALL East corner					
ES(1)	022	"	"			Ext. So. Wall - EAST END					
ES(2)	023	gray	Ext. Wall Stucco - Smooth Finish			N.W @ GRILL AREA					
ES(2)	024					" "					
ES(2)	025					" "					
ECS(1)	026	gray	Ext. Ceiling Stucco - Rough			North Wall -					
ECS(1)	027	gray				West Wall					
ECS(1)	028	gray				South Wall					

PROJECT NO.: 1097 10020				DATE: 081417				PAGE 3			
CLIENT: WRSSR				INSPECTOR(S): Jeffrey Klein				OF			
PROJECT ID: Our Lady of Mt. Lebanon				SITE ADDRESS:				CSST/CAC NO: CAC 07-4240		U	
HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		HA NO.	COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.			
SAC(1)	029	white	SPRAY Applied Acoustic ceiling - Textured	12" x 12" VFT W/	1	ROOM 11 EAST Wall	150	SF	F	G	NA
12VFT(1)	030	Beige	BRN Mottles	F.T. MASTIC A/W		ROOM 11 - N.W. corner			NF	G	N/A
FTM(1)	031	yellow	12" x 12" VFT W/			↓					
12VFT(1)	032	Beige	BRN Mottles	FT MASTIC A/W		ROOM 11 - NE corner					
FTM(1)	033	yellow	12" x 12" VFT W/			↓					
12VFT(1)	034	Beige	BRN Mottles	F.T. MASTIC A/W		ROOM 11 - So. West corner					
FTM(1)	035	yellow	12" x 12" VFT W/			↓					
RPM(1)	036	grey	Roof Penetration MASTIC	R4	ROOF	West Wall - 10" Vent	50	SF	NF	G	N/A
RPM(1)	037					West Wall - NO Eng. Rft. exhaust					
RPM(1)	038					Middle of So. Wall @ DRAIN					
RFM(1)	039		Rolled on field RUST Membrane (Cap sheet)			Middle of West Wall					
RFM(1)	040					No wall - NEC of canopy					
RFM(1)	041					Middle of So. Wall					
ES(1)	042	gray	Ext. Wall Stucco			Upper Roof - N.W. corner					

BULK SAMPLE DATA FORM


#321719809

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0				DATE: 0 8 1 6 1 7				PAGE					
CLIENT: <u>Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP</u>				INSPECTOR(S): Jeffrey Klein				4					
PROJECT ID: <u>Our Lady of Mt Lebanon Church Redevelopment Project</u>				CSST/CAC NO: CAC 07-4240				OF					
SITE ADDRESS: <u>333 S San Vicente Boulevard, Los Angeles, California 90048</u>								11					
HA TYPE HA NO.	SAMPLE NO.			MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
	COLOR	TEXTURE/PATTERN		UNIT	LEVEL	AREA/LOCATION		NO.	UNIT				
ES(1)	1	4	3	gray	Ext. Wall stucco	Church Hall	Roof	Upper Roof- SE corner			NF	G	N/A
RS(1)	0	4	4	Red	Roof Shingle Upper layer			Middle of West Wall					
RS(2)	0	4	5	BLK	Bottom layer								
RS(1)	0	4	6	Red	Upper layer			North East End					
RS(2)	0	4	7	BLK	Bottom layer								
RS(1)	0	4	8	Red	Upper layer			Upper Roof- SE corner					
RS(2)	0	4	9	BLK	Lower layer								
	0	5	0										
/													


BULK SAMPLE DATA FORM

#321719809

Order ID: 321719809

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0				DATE: 0 8 1 6 1 7				PAGE 5			
CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP				INSPECTOR(S): Jeffrey Klein				OF			
PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project				CSST/CAC NO: CAC 07-4240				11			
SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048											
HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
2CP(1)	050	White	2'x2' Lay-in Ceiling Panel Profiles/Figures of ^{Church} House _{outside}		2	Room 14 Center			F	G	N/A
WSR(1)	051		Wall Sheetrock			Room 14 East Wall					
WJC(1)	052		Wall Joint Compound			↓					
CSR(1)	053		Ceiling Sheetrock			Room 14 Center					
CJC(1)	054		Ceiling Joint Compound			↓					
2CP(1)	055		2' x 2' Lay-in Ceiling Panel			Corridor Outside North Stairs (RM. 16)					
WSR(1)	056		Wall Sheetrock			↓					
WJC(1)	057		Wall Joint Compound			↓					
CSR(1)	058		Ceiling Sheetrock			↓					
CJC(1)	059		Ceiling Joint Compound			↓					
2CP(1)	060		2' x 2' Lay-in Ceiling Panel			Room 8 - West Side					
WSR(1)	061		(Wall) Sheetrock			↓					
WJC(1)	062		Wall Joint Compound			↓					
CSR(1)	063		Ceiling Sheetrock			↓					

BULK SAMPLE DATA FORM

PROJECT NO.: 1097 . 1002 . 0	DATE: 081617	PAGE 6	
CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP	INSPECTOR(S): Jeffrey Klein	OF 11	
PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project	CSST/CAC NO: CAC 07-4240		
SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048			

HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
CJC(1)	064	White	Ceiling Joint Compound	Church House Office	2	Room 8 - West Side			F	G	N/A
WSR(1)	065		Sheetrock Wall		3	Room 19 - NE Corner					
WJC(1)	066		Joint Compound Wall			Room 24 (Kitchen) N.W. Corner					
WJC(1)	067		Sheetrock Wall			Room 24 (Kitchen) N.W. Corner					
WJC(1)	068		Joint Compound Wall			No. Stairwell Rm 26 S.E. Corner					
WSR(1)	069		Sheetrock Wall			Elevator Mech Rm Room 3 - NE Corner					
WJC(1)	070		Joint Compound Wall								
WSR(1)	071		Sheetrock Wall								
WJC(1)	072		Joint Compound								
ZCP(1)	073		2' x 2' Lay in Ceiling Panel		2	AAAW Corridor between Rms 12 & 13					
ZCP(1)	074				2	Room 15 - NE Corner					
RFM(2)	075	Grk/Silver	Roller on Field Memb. w/Felts	Roof		NO. END	60 SF		NF	G	N/A
RFM(2)	076					Center					
RFM(2)	077					So. End					

BULK SAMPLE DATA FORM

#321719809

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0
 CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP
 PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project
 SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048
 DATE: 08/14/17
 INSPECTOR(S): Jeffrey Klein
 CSST/CAC NO: CAC 07-4240
 PAGE 7 OF 11



HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
RPM(1)	078	Gray	Penetration MASTIC	Church House office	Roof	West Wall Wall Vent	60	SF	RF	D	P
RPM(1)	079					West Wall-Roof Vent Pipe					
RPM(1)	080					Center-HVAC Duct (base)					
HVT(1)	081	Gray	HVAC DUCT Seam Sealant Rubberlike			North East Corner			NF	G	N/A
HVT(1)	082					Center					
HVT(1)	083					Southwest Corner					
VSF(1)	084	Beige	Vinyl Sheet Flooring Square Pattern		2	Room 10			F	G	N/A
SFM(1)	085	yellow	MASTIC/W VSF-1		2				NF	G	N/A
ES(3)	086	Gray	Ext. Wall Stucco Rough finish		1	No West corner at stair exit					
BS(3)	087				1	No East corner at door to courtyard					
BS(3)	088					Garage - Room #1 @ Elevator Mech Room					
ES(3)	089					So. East Corner					
ES(3)	090					So. West Corner					
VSF(2)	091	Beige	Vinyl Sheet Flooring w/ Blue squares		3	Room 2 PA Next to tub					

BULK SAMPLE DATA FORM

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0

DATE: 0 8 / 1 7 / 1 7

PAGE

8



CITADEL ENVIRONMENTAL SERVICES, INC.

CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP

PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project

INSPECTOR(S): Jeffrey Klein

OF


SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048

CSST/CAC NO: CAC 07-4240

11


HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
SFM(2)	092	yellow/white	MASTIC A/W VSF-2	Church office	3	ROOM 2BA NEXT to tub			NF	G	N/A
VSF(2)	093	Beige	Vinyl sheet flooring w/ Blue squares			Room 2BA - EAST WALL			NF		
SFM(2)	094	yellow/white	MASTIC A/W VSF-2						NF		
VSF(2)	095	Beige	Vinyl sheet flooring w/ Blue squares			Room 23A WEST WALL			F		
SFM(2)	096	yellow/white	MASTIC A/W VSF-2						NF		
SAC(2)	097	white	SPRAY ACOUSTIC ceiling (Rough)			Room 1A North End	200	sf	F		
SAC(2)	098					"					
SAC(2)	099					middle					
HVT(2)	100	white	HVAC Seam SEALANT - Rubber			" South End			NF		
HVT(2)	101					" Middle					
HVT(2)	102										
HVD(1)	103	GRAY	HVAC Vibration Damper - Smooth								

BULK SAMPLE DATA FORM



PROJECT NO.: 1097 . 1002 . 0	DATE: 081716	PAGE 9	
CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP	INSPECTOR(S): Jeffrey Klein	OF	
PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project	CSST/CAC NO: CAC 07-4240	"	
SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048			

HA TYPE HA NO.	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
WPF (2)	104	gray	Wall Plaster irregular on Rough House	Church	1	Rm 109 No. Wall			NF	G	NA
WPF (2)	105		" "			Room 109 - South Wall			↓		
WPF (2)	106		" "			Room 109 Center (ceiling)			↓		
CF (1)	107		6" Flue Pipe -HARD			Room 109 EAST END	30	SF	NF		
PJ/c (4)	108		Flue pipe cover SOFT.			↓ closet	5	SF	F		
WPF (3)	109	Beige	Wall Plaster Smooth			Hallway below stairs					
WPF (3)	110					Room 106 - No Wall @ closet					
WPF (3)	111					Room 102 - E. Wall, NO END					
WPF (2)	112					Room 105 - N. W. corner (Kitchen)					
WPF (3)	113				2	Room 207 (RR) EAST Wall					
WPF (3)	114				2	Room 202 (RR) No EAST corner					
WPF (3)	115				2	Room 200 (Hallway) SO. closet			↓		
WJR (2)	116	white	Wall Sheetrock		1	Room 106 closet South West			F		
WJR (2)	117		Wall JOINT compound		1				↓		

BULK SAMPLE DATA FORM

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0				DATE: 0 8 1 7 1 7				PAGE 10				
CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP				INSPECTOR(S): Jeffrey Klein				OF 11				
PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project				CSST/CAC NO: CAC 07-4240								
SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048												
HA TYPE	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE	
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT				
WP(2)	118	White gray	Window Putty traces	Church Hase	1	Middle of So. Wall			F	D	P	
WP(2)	119	↓	↓	↓	↓	EAST Wall - So. End			↓	↓	↓	
WP(2)	120	↓	↓	↓	↓	EAST Wall - NO END			↓	↓	↓	
ES(4)	121	White	Ext. Wall stucco Finish COAT	↓	↓	EAST WALL CENTER			NF	G	N/A	
ES(5)	122	gray	" Base COAT	↓	↓	↓			↓	↓	↓	
ES(4)	123	White	" Finish COAT	↓	↓	So EAST corner			↓	↓	↓	
ES(5)	124	gray	" Base COAT	↓	↓	↓			↓	↓	↓	
ES(4)	125	White	" Finish COAT	↓	↓	So. Wall - WEST END			↓	↓	↓	
ES(5)	126	gray	" Base COAT	↓	↓	↓			↓	↓	↓	
ES(4)	127	White	" Finish COAT	↓	↓	West Wall - Below Stairs			↓	↓	↓	
ES(5)	128	gray	" Base COAT	↓	↓	↓			↓	↓	↓	
ES(4)	129	White	" Finish COAT	↓	↓	No wall - WEST corner			↓	↓	↓	
ES(5)	130	gray	" Base COAT	↓	↓	↓			↓	↓	↓	
MKE(2)	131	Black	Felt paper BARRIER	↓	↓	So Wall - West End, Inside Storage			F	G	N/A	

BULK SAMPLE DATA FORM

PROJECT NO.: 1 0 9 7 . 1 0 0 2 . 0					DATE: 0 8 1 7 1 7			PAGE 11			
CLIENT: Wolf, Rifkin, Shapiro, Schulman & Rabkin, LLP					INSPECTOR(S): Jeffrey Klein			OF			
PROJECT ID: Our Lady of Mt Lebanon Church Redevelopment Project					CSST/CAC NO: CAC 07-4240			11			
SITE ADDRESS: 333 S San Vicente Boulevard, Los Angeles, California 90048											
HA TYPE HA NO.	SAMPLE NO.	MATERIAL DESCRIPTION		BULK SAMPLE LOCATION			QUANTITY		FRIABILITY	MATERIAL CONDITION	DAMAGE TYPE
		COLOR	TEXTURE/PATTERN	UNIT	LEVEL	AREA/LOCATION	NO.	UNIT			
MISC (2)	1 3 2	Black	Felt Paper BARRIER	Church House	1	Middle of West Wall at below stairs			F	G	N/A
MISC (2)	1 3 3	↓	↓	↓	↓	↓			F	G	N/A
MISC (3)	1 3 4	Black	Felt Paper Smooth Below Tile		Roof	So Wall- WEST END			F	↓	↓
MISC (3)	1 3 5	Black	↓	↓	↓	So. Wall- EAST END			↓	↓	↓
MISC (3)	1 3 6	Black	↓	↓	↓	EAST WALL NO. END.			↓	↓	↓
											

(Handwritten signature)



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix F

Table 3.0 - Lead XRF SA Results

TABLE 3.0 - LEAD XRF SA RESULTS
OUR LADY OF MT. LEBANON
333 SOUTH VICENTA BOULEVARD
LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
5	PAINT	mg / cm ^2	Final	WALL	PLASTER	NORTH	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
6	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	NORTH	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.06
7	PAINT	mg / cm ^2	Final	WINDOW SILL	WOOD	EAST	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.01
8	PAINT	mg / cm ^2	Final	WINDOW	METAL	EAST	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
9	PAINT	mg / cm ^2	Final	DOOR	WOOD	SW	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.03
10	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	SW	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
11	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	SW	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.04
12	PAINT	mg / cm ^2	Final	FLOOR	WOOD	SW	INTACT	VARNISH	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
13	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	SW	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
14	PAINT	mg / cm ^2	Final	CEILING	PLASTER	SW	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
15	PAINT	mg / cm ^2	Final	DOOR	WOOD	NE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
16	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	NE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
17	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	NE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
18	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
19	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
20	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
21	PAINT	mg / cm ^2	Final	WALL	PLASTER	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
22	PAINT	mg / cm ^2	Final	WALL	METAL	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
23	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	B	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
24	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	A	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	POSITIVE	0.7	3.6
25	PAINT	mg / cm ^2	Final	WALL	CERAMIC	B	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	POSITIVE	0.7	5.2
26	PAINT	mg / cm ^2	Final	URINAL	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.15
27	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
28	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.1
29	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.03
30	PAINT	mg / cm ^2	Final	WINDOW SASH	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.04
31	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
32	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	NEGATIVE	0.7	0
33	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.1
34	PAINT	mg / cm ^2	Final	DOOR	METAL	D	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.12
35	PAINT	mg / cm ^2	Final	WALL	PLASTER	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.01
36	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	POSITIVE	0.7	6.4
37	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	POSITIVE	0.7	4.6
38	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	NEGATIVE	0.7	0
39	PAINT	mg / cm ^2	Final	STAGE FLOOR	WOOD	WEST	INTACT	VARNISH	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
40	PAINT	mg / cm ^2	Final	STAGE WALL	WOOD	WEST	INTACT	VARNISH	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
41	PAINT	mg / cm ^2	Final	STAGE STEPS	WOOD	WEST	INTACT	VARNISH	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	NEGATIVE	0.7	0
43	PAINT	mg / cm ^2	Final	STAGE STEPS	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	2	CHURCH HALL	NEGATIVE	0.7	0
46	PAINT	mg / cm ^2	Final	CEILING	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	2	CHURCH HALL	NEGATIVE	0.7	0
47	PAINT	mg / cm ^2	Final	CABINET	WOOD	D	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	2	CHURCH HALL	NEGATIVE	0.7	0
48	PAINT	mg / cm ^2	Final	WALL	PLASTER	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	LCP	0.7	0.03
49	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	POSITIVE	0.7	6.7
50	PAINT	mg / cm ^2	Final	SHELF	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	LCP	0.7	0.02
51	PAINT	mg / cm ^2	Final	FLOOR	CONCRETE	D	INTACT	GRAY	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	NEGATIVE	0.7	0
52	PAINT	mg / cm ^2	Final	FLOOR	CONCRETE	D	INTACT	GRAY	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	NEGATIVE	0.7	0
53	PAINT	mg / cm ^2	Final	WALL	PLASTER	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	NEGATIVE	0.7	0
54	PAINT	mg / cm ^2	Final	WALL	METAL	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.29
55	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.07

TABLE 3.0 - LEAD XRF SA RESULTS
OUR LADY OF MT. LEBANON
333 SOUTH VICENTA BOULEVARD
LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
56	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.01
57	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.27
58	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	NEGATIVE	0.7	0
59	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.13
60	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	POSITIVE	0.7	7
61	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.02
62	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.01
63	PAINT	mg / cm ^2	Final	WINDOW	METAL	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	NEGATIVE	0.7	0
64	PAINT	mg / cm ^2	Final	WINDOW GUARD	METAL	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	NEGATIVE	0.7	0
65	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.6
66	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.4
67	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.4
69	PAINT	mg / cm ^2	Final	WALL	STUCCO	NW	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
70	PAINT	mg / cm ^2	Final	WINDOW	METAL	NW	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
71	PAINT	mg / cm ^2	Final	DOWN SPOUT	METAL	NW	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.09
72	PAINT	mg / cm ^2	Final	WALL VENT COVER	METAL	NW	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
73	PAINT	mg / cm ^2	Final	WALL	PLASTER	NW	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
74	PAINT	mg / cm ^2	Final	WALL	STUCCO	MID NORTH	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
75	PAINT	mg / cm ^2	Final	CEILING	STUCCO	MID NORTH	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
76	PAINT	mg / cm ^2	Final	RAIL	METAL	MID NORTH	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.23
77	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	MID NORTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
78	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	MID SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.09
79	PAINT	mg / cm ^2	Final	GATE	METAL	SE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
81	PAINT	mg / cm ^2	Final	WALL	CONCRETE	MID SOUTH	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
82	PAINT	mg / cm ^2	Final	WALL	CERAMIC	SE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	POSITIVE	0.7	3.6
83	PAINT	mg / cm ^2	Final	WINDOW	WOOD	SE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	NEGATIVE	0.7	0
84	PAINT	mg / cm ^2	Final	BALLER	METAL	NE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.18
85	PAINT	mg / cm ^2	Final	WALL	stucco	SOUTH	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
86	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
87	PAINT	mg / cm ^2	Final	DOWN SPOUT	METAL	WEST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
88	PAINT	mg / cm ^2	Final	GARAGE DOOR	METAL	WEST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
89	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	WEST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
90	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	WEST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
91	PAINT	mg / cm ^2	Final	GARAGE DOOR	METAL	WEST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
92	PAINT	mg / cm ^2	Final	FENCE	METAL	SW	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH OFFICE	NEGATIVE	0.7	0
93	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	ROOM 4	CHURCH OFFICE	NEGATIVE	0.7	0
94	PAINT	mg / cm ^2	Final	WALL	DRYWALL	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	ROOM 4	CHURCH OFFICE	NEGATIVE	0.7	0
95	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	C	INTACT	GREEN	OUR LADY OF MT. LEBANON	FIRST	ROOM 4	CHURCH OFFICE	NEGATIVE	0.7	0
96	PAINT	mg / cm ^2	Final	ELEVATOR DOOR	METAL	C	INTACT	GRAY	OUR LADY OF MT. LEBANON	FIRST	ROOM 3	CHURCH OFFICE	NEGATIVE	0.7	0
97	PAINT	mg / cm ^2	Final	DOOR	METAL	B	INTACT	DK GRAY	OUR LADY OF MT. LEBANON	FIRST	ROOM 3	CHURCH OFFICE	NEGATIVE	0.7	0
98	PAINT	mg / cm ^2	Final	CABINET	WOOD	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	ROOM 1	CHURCH OFFICE	NEGATIVE	0.7	0
102	PAINT	mg / cm ^2	Final	WALL	STUCCO	A	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	ROOM 1	CHURCH OFFICE	NEGATIVE	0.7	0
103	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	DK GRAY	OUR LADY OF MT. LEBANON	FIRST	ROOM 1	CHURCH OFFICE	NEGATIVE	0.7	0
104	PAINT	mg / cm ^2	Final	DOOR FRAME	METAL	A	INTACT	DK GRAY	OUR LADY OF MT. LEBANON	FIRST	ROOM 1	CHURCH OFFICE	NEGATIVE	0.7	0
105	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 7	CHURCH OFFICE	NEGATIVE	0.7	0
106	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 7	CHURCH OFFICE	NEGATIVE	0.7	0
108	PAINT	mg / cm ^2	Final	WALL	DRYWALL	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 7	CHURCH OFFICE	NEGATIVE	0.7	0
109	PAINT	mg / cm ^2	Final	WALL	DRYWALL	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 10	CHURCH OFFICE	NEGATIVE	0.7	0

TABLE 3.0 - LEAD XRF SA RESULTS
OUR LADY OF MT. LEBANON
333 SOUTH VICENTA BOULEVARD
LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
110	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 10	CHURCH OFFICE	LCP	0.7	0.01
111	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 10	CHURCH OFFICE	LCP	0.7	0.01
112	PAINT	mg / cm ^2	Final	FLOOR	WOOD	C	INTACT	BROWN	OUR LADY OF MT. LEBANON	SECOND	ROOM 13	CHURCH OFFICE	NEGATIVE	0.7	0
113	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 13	CHURCH OFFICE	NEGATIVE	0.7	0
114	PAINT	mg / cm ^2	Final	WALL	DRYWALL	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 13	CHURCH OFFICE	NEGATIVE	0.7	0
116	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 13	CHURCH OFFICE	NEGATIVE	0.7	0
117	PAINT	mg / cm ^2	Final	WALL	DRYWALL	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
118	PAINT	mg / cm ^2	Final	BASEBOARD	DRYWALL	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
119	PAINT	mg / cm ^2	Final	DOOR	WOOD	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
120	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
121	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
122	PAINT	mg / cm ^2	Final	FLOOR	WOOD	B	INTACT	BROWN	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
123	PAINT	mg / cm ^2	Final	CEILING	DRYWALL	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	THIRD	ROOM 19	CHURCH OFFICE	NEGATIVE	0.7	0
124	PAINT	mg / cm ^2	Final	WALL	PLASTER	EAST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	LCP	0.7	0.19
126	PAINT	mg / cm ^2	Final	DOWN SPOUT	METAL	EAST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.2
127	PAINT	mg / cm ^2	Final	WINDOW	METAL	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.5
128	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	2.2
129	PAINT	mg / cm ^2	Final	WINDOW CAGE	WOOD	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	LCP	0.7	0.04
130	PAINT	mg / cm ^2	Final	SQUARE DOWN SPOUT	WOOD	SE	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	2.6
131	PAINT	mg / cm ^2	Final	ROUND DOWN SPOUT	METAL	SOUTH	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	NEGATIVE	0.7	0
132	PAINT	mg / cm ^2	Final	BACK DOOR	WOOD	SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.8
133	PAINT	mg / cm ^2	Final	BACK DOOR JAM	WOOD	SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.5
134	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.25
135	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.07
136	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.06
137	PAINT	mg / cm ^2	Final	DOOR FRAME	METAL	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.2
138	PAINT	mg / cm ^2	Final	WALL	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	NEGATIVE	0.7	0
139	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	NEGATIVE	0.7	0
140	PAINT	mg / cm ^2	Final	WEST DOOR	WOOD	WEST SIDE TO GARAGE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.22
141	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.13
142	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	POSITIVE	0.7	2.5
143	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.6
144	PAINT	mg / cm ^2	Final	DOOR	WOOD	NORTH DOOR	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.3
145	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	NORTH DOOR	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	5.3
146	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	LCP	0.7	0.1
147	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	LCP	0.7	0.17
149	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BURGUNDY	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	NEGATIVE	0.7	0
151	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	A	INTACT	BURGUNDY	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	NEGATIVE	0.7	0
152	PAINT	mg / cm ^2	Final	WALL	PLASTER	C	INTACT	BURGUNDY	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.04
153	PAINT	mg / cm ^2	Final	WALL	PLASTER	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.05
154	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.03
155	PAINT	mg / cm ^2	Final	FLOOR	WOOD	B	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	NEGATIVE	0.7	0
156	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	LCP	0.7	0.04
157	PAINT	mg / cm ^2	Final	WINDOW	METAL	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	LCP	0.7	0.01
159	PAINT	mg / cm ^2	Final	COUNTER TOP	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	NEGATIVE	0.7	0
160	PAINT	mg / cm ^2	Final	CABINET DOOR	WOOD	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	NEGATIVE	0.7	0
161	PAINT	mg / cm ^2	Final	CABINET SHELF	WOOD	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	NEGATIVE	0.7	0
163	PAINT	mg / cm ^2	Final	WALL	PLASTER	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	NEGATIVE	0.7	0

TABLE 3.0 - LEAD XRF SA RESULTS
OUR LADY OF MT. LEBANON
333 SOUTH VICENTA BOULEVARD
LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
164	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.04
165	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.04
167	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.11
168	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	NEGATIVE	0.7	0
169	PAINT	mg / cm ^2	Final	WALL	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	NEGATIVE	0.7	0
170	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.02
171	PAINT	mg / cm ^2	Final	FLOOR	WOOD	D	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	106	CHURCH HOUSE	NEGATIVE	0.7	0
172	PAINT	mg / cm ^2	Final	FLOOR	WOOD	C	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.05
173	PAINT	mg / cm ^2	Final	TREAD	WOOD	CENTER	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.01
174	PAINT	mg / cm ^2	Final	RISER	WOOD	CENTER	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.09
175	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	CENTER	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.12
176	PAINT	mg / cm ^2	Final	WALL	PLASTER	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	NEGATIVE	0.7	0
177	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.02
179	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	B	INTACT	BROWN	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	NEGATIVE	0.7	0
180	PAINT	mg / cm ^2	Final	TUB	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	POSITIVE	0.7	5.3
181	PAINT	mg / cm ^2	Final	WALL	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.06
182	PAINT	mg / cm ^2	Final	SINK	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	POSITIVE	0.7	6.1
183	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.01
184	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	NEGATIVE	0.7	< LOD
185	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.06
187	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.04
188	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.15
189	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.02
190	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.23
191	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.08
192	PAINT	mg / cm ^2	Final	WALL	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.18
194	PAINT	mg / cm ^2	Final	CABINET	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.24
195	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
196	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	BROWN	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
197	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
198	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	LCP	0.7	0.05
200	PAINT	mg / cm ^2	Final	SINK	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	NEGATIVE	0.7	0
201	PAINT	mg / cm ^2	Final	TUB	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	POSITIVE	0.7	5.6
202	PAINT	mg / cm ^2	Final	WALL	CERAMIC	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	NEGATIVE	0.7	0
203	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	A	INTACT	GREEN	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	NEGATIVE	0.7	0
204	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	LCP	0.7	0.1
205	PAINT	mg / cm ^2	Final	WINDOW	METAL	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.05
206	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.08
207	PAINT	mg / cm ^2	Final	WALL	PLASTER	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	NEGATIVE	0.7	< LOD
208	PAINT	mg / cm ^2	Final	TUB	CERAMIC	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	POSITIVE	0.7	6
209	PAINT	mg / cm ^2	Final	SINK	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.01
210	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.01
212	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	D	INTACT	GREEN	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	NEGATIVE	0.7	0
213	PAINT	mg / cm ^2	Final	DOOR	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.12
214	PAINT	mg / cm ^2	Final	DOOR	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.12
215	PAINT	mg / cm ^2	Final	DOOR DUMB WAITER	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	201	CHURCH HOUSE	LCP	0.7	0.08
216	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	200	CHURCH HOUSE	LCP	0.7	0.03
217	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	200	CHURCH HOUSE	LCP	0.7	0.03

TABLE 3.0 - LEAD XRF SA RESULTS
 OUR LADY OF MT. LEBANON
 333 SOUTH VICENTA BOULEVARD
 LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
218	PAINT	mg / cm ^2	Final	TRIM	WOOD	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	POSITIVE	0.7	1.6
219	PAINT	mg / cm ^2	Final	TRIM	WOOD	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	POSITIVE	0.7	2.1
221	PAINT	mg / cm ^2	Final	CANOPY	PLASTER	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	LCP	0.7	0.07
222	PAINT	mg / cm ^2	Final	SHINGLES	CLAY	SE CORNER	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	LCP	0.7	0.03



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix G

Table 3.1 - Lead XRF Results - LBP (Positive)

TABLE 3.1 - LEAD XRF SA RESULTS
LEAD-BASED PAINTS (≥ 0.7 mg/cm²)
OUR LADY OF MT. LEBANON
333 SOUTH VICENTA BOULEVARD
LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
24	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	A	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	POSITIVE	0.7	3.6
25	PAINT	mg / cm ^2	Final	WALL	CERAMIC	B	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	POSITIVE	0.7	5.2
36	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	POSITIVE	0.7	6.4
37	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	POSITIVE	0.7	4.6
49	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	POSITIVE	0.7	6.7
60	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	YELLOW	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	POSITIVE	0.7	7
82	PAINT	mg / cm ^2	Final	WALL	CERAMIC	SE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	POSITIVE	0.7	3.6
126	PAINT	mg / cm ^2	Final	DOWN SPOUT	METAL	EAST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.2
127	PAINT	mg / cm ^2	Final	WINDOW	METAL	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.5
128	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	2.2
130	PAINT	mg / cm ^2	Final	SQUARE DOWN SPOUT	WOOD	SE	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	2.6
132	PAINT	mg / cm ^2	Final	BACK DOOR	WOOD	SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.8
133	PAINT	mg / cm ^2	Final	BACK DOOR JAM	WOOD	SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.5
142	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	POSITIVE	0.7	2.5
143	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.6
144	PAINT	mg / cm ^2	Final	DOOR	WOOD	NORTH DOOR	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	1.3
145	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	NORTH DOOR	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	POSITIVE	0.7	5.3
180	PAINT	mg / cm ^2	Final	TUB	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	POSITIVE	0.7	5.3
182	PAINT	mg / cm ^2	Final	SINK	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	POSITIVE	0.7	6.1
201	PAINT	mg / cm ^2	Final	TUB	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	POSITIVE	0.7	5.6
208	PAINT	mg / cm ^2	Final	TUB	CERAMIC	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	POSITIVE	0.7	6
218	PAINT	mg / cm ^2	Final	TRIM	WOOD	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	POSITIVE	0.7	1.6
219	PAINT	mg / cm ^2	Final	TRIM	WOOD	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	POSITIVE	0.7	2.1



CITADEL
ENVIRONMENTAL SERVICES, INC.

Appendix H

Table 3.2 - Lead XRF Results (LCP)

TABLE 3.2 - LEAD XRF SA RESULTS
 LEAD-CONTAINING PAINT ($\geq 0.01 \text{ mg/cm}^2$ and $\leq 0.7 \text{ mg/cm}^2$)
 OUR LADY OF MT. LEBANON
 333 SOUTH VICENTA BOULEVARD
 LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
6	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	NORTH	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.06
7	PAINT	mg / cm ^2	Final	WINDOW SILL	WOOD	EAST	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.01
9	PAINT	mg / cm ^2	Final	DOOR	WOOD	SW	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.03
11	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	SW	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	1	CHURCH HALL	LCP	0.7	0.04
18	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
20	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
26	PAINT	mg / cm ^2	Final	URINAL	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.15
27	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.01
28	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.1
29	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.03
30	PAINT	mg / cm ^2	Final	WINDOW SASH	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	10	CHURCH HALL	LCP	0.7	0.04
33	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.1
34	PAINT	mg / cm ^2	Final	DOOR	METAL	D	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.12
35	PAINT	mg / cm ^2	Final	WALL	PLASTER	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	9	CHURCH HALL	LCP	0.7	0.01
48	PAINT	mg / cm ^2	Final	WALL	PLASTER	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	LCP	0.7	0.03
50	PAINT	mg / cm ^2	Final	SHELF	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	4	CHURCH HALL	LCP	0.7	0.02
54	PAINT	mg / cm ^2	Final	WALL	METAL	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.29
55	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.07
56	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.01
57	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.27
59	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	7	CHURCH HALL	LCP	0.7	0.13
61	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.02
62	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.01
65	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.6
66	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.4
67	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	6	CHURCH HALL	LCP	0.7	0.4
71	PAINT	mg / cm ^2	Final	DOWN SPOUT	METAL	NW	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.09
76	PAINT	mg / cm ^2	Final	RAIL	METAL	MID NORTH	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.23
78	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	MID SOUTH	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.09
84	PAINT	mg / cm ^2	Final	BALLER	METAL	NE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HALL	LCP	0.7	0.18
110	PAINT	mg / cm ^2	Final	SINK	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 10	CHURCH OFFICE	LCP	0.7	0.01
111	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	ROOM 10	CHURCH OFFICE	LCP	0.7	0.01
124	PAINT	mg / cm ^2	Final	WALL	PLASTER	EAST	INTACT	TAN	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	LCP	0.7	0.19
129	PAINT	mg / cm ^2	Final	WINDOW CAGE	WOOD	EAST	INTACT	BLUE	OUR LADY OF MT. LEBANON	FIRST	OUTSIDE	CHURCH HOUSE	LCP	0.7	0.04
134	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.25
135	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.07
136	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.06
137	PAINT	mg / cm ^2	Final	DOOR FRAME	METAL	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.2
140	PAINT	mg / cm ^2	Final	WEST DOOR	WOOD	WEST SIDE TO GARAGE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.22
141	PAINT	mg / cm ^2	Final	WEST DOOR JAM	WOOD	WEST SIDE TO GARAGE	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	ROOM 109	CHURCH HOUSE	LCP	0.7	0.13
146	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	LCP	0.7	0.1
147	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	101	CHURCH HOUSE	LCP	0.7	0.17
152	PAINT	mg / cm ^2	Final	WALL	PLASTER	C	INTACT	BURGUNDY	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.04
153	PAINT	mg / cm ^2	Final	WALL	PLASTER	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.05
154	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	103	CHURCH HOUSE	LCP	0.7	0.03
156	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	LCP	0.7	0.04
157	PAINT	mg / cm ^2	Final	WINDOW	METAL	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	105	CHURCH HOUSE	LCP	0.7	0.01
164	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.04
165	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.04

TABLE 3.2 - LEAD XRF SA RESULTS
 LEAD-CONTAINING PAINT ($\geq 0.01 \text{ mg/cm}^2$ and $\leq 0.7 \text{ mg/cm}^2$)
 OUR LADY OF MT. LEBANON
 333 SOUTH VICENTA BOULEVARD
 LOS ANGELES, CALIFORNIA 90048

Reading No	Type	Units	Sequence	Component	Substrate	Side	Condition	Color	Site	Floor	Room	Misc 1	Results	Action Level	PbC
167	PAINT	mg / cm ^2	Final	DOOR FRAME	WOOD	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.11
170	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	B	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	108	CHURCH HOUSE	LCP	0.7	0.02
172	PAINT	mg / cm ^2	Final	FLOOR	WOOD	C	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.05
173	PAINT	mg / cm ^2	Final	TREAD	WOOD	CENTER	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.01
174	PAINT	mg / cm ^2	Final	RISER	WOOD	CENTER	INTACT	WHITE	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.09
175	PAINT	mg / cm ^2	Final	HAND RAIL	METAL	CENTER	INTACT	BROWN	OUR LADY OF MT. LEBANON	FIRST	104	CHURCH HOUSE	LCP	0.7	0.12
177	PAINT	mg / cm ^2	Final	BASEBOARD	CERAMIC	B	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.02
181	PAINT	mg / cm ^2	Final	WALL	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.06
183	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.01
185	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.06
187	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.04
188	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.15
189	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	213	CHURCH HOUSE	LCP	0.7	0.02
190	PAINT	mg / cm ^2	Final	DOOR JAM	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.23
191	PAINT	mg / cm ^2	Final	DOOR	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.08
192	PAINT	mg / cm ^2	Final	WALL	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.18
194	PAINT	mg / cm ^2	Final	CABINET	PLASTER	A	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	207	CHURCH HOUSE	LCP	0.7	0.24
195	PAINT	mg / cm ^2	Final	FLOOR	CERAMIC	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
196	PAINT	mg / cm ^2	Final	WALL	CERAMIC	C	INTACT	BROWN	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
197	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	208	CHURCH HOUSE	LCP	0.7	0.01
198	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	C	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	LCP	0.7	0.05
204	PAINT	mg / cm ^2	Final	WINDOW	METAL	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	206	CHURCH HOUSE	LCP	0.7	0.1
205	PAINT	mg / cm ^2	Final	WINDOW	METAL	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.05
206	PAINT	mg / cm ^2	Final	WINDOW FRAME	WOOD	D	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.08
209	PAINT	mg / cm ^2	Final	SINK	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.01
210	PAINT	mg / cm ^2	Final	TOILET	CERAMIC	D	INTACT	WHITE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.01
213	PAINT	mg / cm ^2	Final	DOOR	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.12
214	PAINT	mg / cm ^2	Final	DOOR	WOOD	C	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	202	CHURCH HOUSE	LCP	0.7	0.12
215	PAINT	mg / cm ^2	Final	DOOR DUMB WAITER	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	201	CHURCH HOUSE	LCP	0.7	0.08
216	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	200	CHURCH HOUSE	LCP	0.7	0.03
217	PAINT	mg / cm ^2	Final	BASEBOARD	WOOD	A	INTACT	BEIGE	OUR LADY OF MT. LEBANON	SECOND	200	CHURCH HOUSE	LCP	0.7	0.03
221	PAINT	mg / cm ^2	Final	CANOPY	PLASTER	SE CORNER	INTACT	BEIGE	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	LCP	0.7	0.07
222	PAINT	mg / cm ^2	Final	SHINGLES	CLAY	SE CORNER	INTACT	RED	OUR LADY OF MT. LEBANON	FIRST	OFFICE	CHURCH HOUSE	LCP	0.7	0.03