Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: WATER AND STORM WATER GROUP JOB 968

Lead Agency: City of San Diego

Contact Name: Jamie Kennedy

Email: JMKennedy@sandiego.gov Phone Number: 619-446-5445

Project Location: San Diego, San Diego
City *County*

Project Description (Proposed actions, location, and/or consequences).

A SITE DEVELOPMENT PERMIT (SDP) to replace, rehabilitate, construct, and abandon several existing water mains and replace a storm drain. Work includes the installation of about 7,839 linear feet of 8”, 12”, and 16” water mains, 193 linear feet of storm drain, as well as abandonment of 7,382 linear feet of 6”, 8”, and 12” water main. Appurtenances include cutoff walls, fire service connections and hydrants, and curb inlets. Cast iron and asbestos cement water main will be replaced with PVC pipe, and storm drain will be replaced with rolled concrete pipe. Abandonment will occur in place. The proposed project includes a total of eleven sites. Six of the sites are in urban areas primarily within developed right of way, in the communities of Old Town, North Park, City Heights, Encanto, and San Diego Airport Authority property. In addition, five sites in the communities of Peninsula, Mission Valley, and City Heights propose work adjacent to and within Environmentally Sensitive Lands. The project sites are located within City Council Districts 2, 3, 4, 7, and 9.

Identify the project’s significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The City of San Diego conducted an Initial Study which determined that the proposed project could have a significant environmental effect in the following areas(s): Biological Resources, Cultural Resources (Archaeology), and Tribal Cultural Resources. Biological resource impacts would be mitigated through .121 acre compensatory habitat mitigation at Canyon View, an existing Public Utilities mitigation site. A biological monitor shall monitor construction as needed. If California Gnatcatcher are present, construction would avoid the nesting season or noise protection measures would be implemented. Based on one site on Kellogg Dr (Site 2) being in an archaeologically sensitive area, proposed new trenching in undisturbed soil for new water service and new water main will require archaeological and Native American Monitoring.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None known

Provide a list of the responsible or trustee agencies for the project.

None