



## Sunset + Wilcox Project

Environmental Case: ENV-2020-1930-EIR  
State Clearinghouse No. 2020120005

**Project Location:** 1440, 1420, 1424, 1426, 1428, 1432, 1432½, 1434, 1436, 1438, 1450, 1452, and 1454 North Wilcox Avenue; 6450, 6460, and 6462 West Sunset Boulevard; 1413, 1417, 1419, 1425, 1427, 1433, 1435, 1439, 1441, 1443, 1445, and 1447 North Cole Place; and, 6503 De Longpre Avenue, Los Angeles, California 90028.

**Community Plan Area:** Hollywood

**Council District:** 13—O'Farrell

**Project Description:** The Project is a new commercial development containing office and restaurant uses proposed on an approximately 73,903-square-foot (1.70-acre) site comprised of 10 contiguous lots along North Wilcox Avenue, West Sunset Boulevard, North Cole Place, and De Longpre Avenue (Project Site) in the Hollywood Community Plan Area of the City of Los Angeles (City). The Project Site is currently occupied with approximately 26,261 square feet of office and retail uses and associated surface parking. The Project includes the development of a 15-story commercial building with a total floor area of 443,418 square feet consisting of 431,032 square feet of office space and 12,386 square feet of ground floor restaurant space. However, for conservative environmental analysis purposes, this Draft EIR assumes the outdoor eating area adjacent to the ground floor restaurant space would count as floor area, resulting in a total floor area of 445,218 square feet, including 431,032 square feet of office space and 14,186 square feet of restaurant space. The Project also includes a Los Angeles Department of Water and Power (LADWP) equipment area that would include electrical distribution equipment and emergency generators within the Cole Place and De Longpre Avenue portion of the Project Site (De Longpre Lot). Specifically, on the north side of the De Longpre Lot an approximately 18-foot-tall, 3,550-square-foot enclosure would be constructed to house new electrical equipment, building life safety generator, tenant back-up generators, and switchgear with adjacent exterior LADWP transformer yard surrounded by a protective 8-foot high fence with landscaped enhancements. The area proposed for this use would not constitute floor area as defined by Los Angeles Municipal Code (LAMC) Section 12.03. As part of the Project, the existing office and retail uses and associated surface parking would be demolished. Upon completion, the Project would result in a floor area ratio (FAR) of 6:1. The Project would include 1,291 vehicular parking spaces, including five vehicular parking spaces provided within a small surface parking area adjacent to the LADWP equipment area. The Project would provide 61,449 square feet of private open space, of which 12,290 square feet would be landscaped.

**PREPARED FOR:**

The City of Los Angeles  
Department of City Planning

**PREPARED BY:**

Eyestone Environmental, LLC

**APPLICANT:**

6450 Sunset Owner, LLC

June 2022

# Table of Contents

---

	<u>Page</u>
<b>I. EXECUTIVE SUMMARY .....</b>	<b>I-1</b>
<b>II. PROJECT DESCRIPTION .....</b>	<b>II-1</b>
<b>III. ENVIRONMENTAL SETTING .....</b>	<b>III-1</b>
A. Overview of Environmental Setting .....	III-1
B. Related Projects .....	III-4
<b>IV. ENVIRONMENTAL IMPACT ANALYSIS .....</b>	<b>IV.A-1</b>
A. Air Quality .....	IV.A-1
B. Cultural Resources .....	IV.B-1
C. Energy .....	IV.C-1
D. Greenhouse Gas Emissions .....	IV.D-1
E. Land Use and Planning .....	IV.E-1
F. Noise .....	IV.F-1
G.1 Public Services—Fire Protection .....	IV.G.1-1
G.2 Public Services—Police Protection.....	IV.G.2-1
G.3 Public Services—Libraries.....	IV.G.3-1
H. Transportation .....	IV.H-1
I. Tribal Cultural Resources .....	IV.I-1
J.1 Utilities and Service Systems—Water Supply and Infrastructure .....	IV.J.1-1
J.2 Utilities and Service Systems—Wastewater .....	IV.J.2-1
J.3 Utilities and Service Systems—Energy Infrastructure .....	IV.J.3-1
<b>V. ALTERNATIVES.....</b>	<b>V-1</b>
A. Alternative 1: No Project.....	V-15
B. Alternative 2: Existing Zoning Compliant Alternative .....	V-25
C. Alternative 3: Reduced Excavation Alternative.....	V-47
D. Alternative 4: Development in Accordance with Community Plan Update Alternative .....	V-68
E. Alternative 5: Residential Alternative .....	V-90
F. Environmentally Superior Alternative.....	V-114
<b>VI. OTHER CEQA CONSIDERATIONS .....</b>	<b>VI-1</b>

	<b><u>Page</u></b>
<b>VII. REFERENCES.....</b>	<b>VII-1</b>
<b>VIII. ACRONYMS AND ABBREVIATIONS .....</b>	<b>VIII-1</b>
<b>IX. LIST OF PREPARERS .....</b>	<b>IX-1</b>

# List of Appendices

---

Appendix A Initial Study, NOP (Notice of Preparation), and NOP Comment Letters

Appendix A.1 Initial Study

Appendix A.2 Notice of Preparation (NOP)

Appendix A.3 NOP Comment Letters

Appendix B Air Quality and Greenhouse Gas Emissions

Appendix B.1 Air Quality and Greenhouse Gas Emissions Methodology

Appendix B.2 Air Quality Worksheet and Modeling Output Files

Appendix B.3 Greenhouse Gas Worksheets and Modeling Output Files

Appendix C Historical Resources Technical Report

Appendix D Energy Calculations

Appendix E Land Use Plans Consistency Analysis Tables

Appendix F Noise Calculation Worksheets

Appendix G Los Angeles Fire Department Response Letter

Appendix H Los Angeles Police Department Response Letter

Appendix I Los Angeles Public Library Response Letter

Appendix J Transportation

Appendix J.1 Los Angeles Department of Transportation Assessment Letter

Appendix J.2 Transportation Assessment

Appendix K Tribal Cultural Resources

Appendix K.1 Tribal Cultural Resources Report

Appendix K.2 AB 52 Notification Letter and Delivery Confirmations

Appendix L Water Supply Assessment

Appendix M Utility Infrastructure Technical Report: Water and Energy

Appendix N Utility Infrastructure Technical Report: Wastewater

Appendix O VMT Runs for Alternatives

# List of Figures

---

<u>Figure</u>	<u>Page</u>
II-1	Project Location Map ..... II-3
II-2	Aerial View of the Project Site and Vicinity ..... II-4
II-3	Existing Site Plan ..... II-5
II-4	Conceptual Site Plan ..... II-9
II-5	Conceptual Rendering Looking Southeast ..... II-11
II-6	Conceptual Rendering Looking Northeast ..... II-12
II-7	Conceptual Landscape/Open Space Plan ..... II-13
II-8	Conceptual Ground-Level Circulation Plan ..... II-15
III-1	Location of Related Projects ..... III-11
IV.A-1	Ozone Trends ..... IV.A-22
IV.A-2	SCAQMD SRAs ..... IV.A-25
IV.A-3	MATES V Total Cancer Risk for Project Area ..... IV.A-28
IV.A-4	Air Quality Sensitive Receptors Locations ..... IV.A-29
IV.B-1	Project Site ..... IV.B-20
IV.B-2	Map of the Study Area ..... IV.B-23
IV.E-1	Land Use Designations on the Project Site ..... IV.E-14
IV.E-2	Zoning Designations on the Project Site ..... IV.E-15
IV.F-1	Decibel Scale and Common Noise Sources ..... IV.F-3
IV.F-2	Guidelines for Noise Compatible Use ..... IV.F-14
IV.F-3	Noise Measurement Locations ..... IV.F-20
IV.G.1-1	Fire Stations in the Vicinity of the Project Site ..... IV.G.1-14
IV.G.2-1	Police Station Serving the Project Site ..... IV.G.2-9
IV.G.3-1	Libraries Serving the Project Vicinity ..... IV.G.3-6
IV.H-1	Existing Street System and Transit Network ..... IV.H-13

<b><u>Figure</u></b>		<b><u>Page</u></b>
V-1	Alternative 2 Conceptual Site Plan .....	V-26
V-2	Alternative 3 Conceptual Site Plan .....	V-48
V-3	Alternative 4 Conceptual Site Plan .....	V-69
V-4	Alternative 5 Conceptual Site Plan .....	V-91

# List of Tables

---

<u>Table</u>	<u>Page</u>
I-1	Summary of Impacts Under the Project ..... I-8
III-1	Related Projects ..... III-7
IV.A-1	Ambient Air Quality Standards ..... IV.A-3
IV.A-2	Summary of Ambient Air Quality in the Project Vicinity ..... IV.A-26
IV.A-3	Estimated Daily Regional Operational Criteria Pollutant Emissions—Baseline ..... IV.A-31
IV.A-4	SCAQMD Air Quality Significance Thresholds ..... IV.A-35
IV.A-5	Project Consistency with City of Los Angeles General Plan (Air Quality Element) ..... IV.A-54
IV.A-6	Estimate of Maximum Regional Project Daily Construction Emissions (pounds per day) ..... IV.A-59
IV.A-7	Estimate of Maximum Regional Project Daily Operational Emissions—At Project Buildout ..... IV.A-60
IV.A-8	Estimate of Maximum Localized Daily Project Construction Emissions (pounds per day) ..... IV.A-61
IV.A-9	Estimate of Maximum Mitigated Regional Project Daily Construction Emissions (pounds per day) ..... IV.A-63
IV.A-10	Estimate of Maximum Localized Project Daily Operational Emissions—At Project Buildout (2026) (pounds per day) ..... IV.A-65
IV.A-11	Estimate of Maximum Mitigated Localized Daily Project Construction Emissions (pounds per day) ..... IV.A-68
IV.C-1	Summary of Energy Use During Project Construction ..... IV.C-23
IV.C-2	Summary of Annual Energy Use During Project Operation ..... IV.C-26
IV.D-1	Description of Identified GHGs ..... IV.D-5
IV.D-2	Atmospheric Lifetimes and Global Warming Potentials ..... IV.D-6
IV.D-3	Estimated Statewide Greenhouse Gas Emissions Reductions Required by HSC Division 25.5 ..... IV.D-20



<b><u>Table</u></b>	<b><u>Page</u></b>
IV.D-4 California GHG Inventory (million metric tons CO <sub>2</sub> e) .....	IV.D-36
IV.D-5 Existing Project Site Annual GHG Emissions Summary .....	IV.D-38
IV.D-6 Regulatory Compliance Measures within the 2008 Climate Change Scoping Plan and Subsequent Updates .....	IV.D-53
IV.D-7 Consistency Analysis—2008 Climate Change Scoping Plan and Subsequent Updates .....	IV.D-55
IV.D-8 Consistency with Applicable GHG Emissions Goals and Actions of the City’s Green New Deal.....	IV.D-66
IV.D-9 Project Consistency with 2045 Carbon Neutrality Goals.....	IV.D-72
IV.D-10 Construction-Related Emissions (MTCO <sub>2</sub> e).....	IV.D-75
IV.D-11 Annual Project GHG Emissions Summary (Buildout Year) (metric tons of carbon dioxide equivalent [MTCO <sub>2</sub> e]) .....	IV.D-76
IV.F-1 FTA Construction Vibration Impact Criteria for Building Damage .....	IV.F-12
IV.F-2 FTA Vibration Impact Criteria for Human Annoyance .....	IV.F-12
IV.F-3 City of Los Angeles Presumed Ambient Noise Levels .....	IV.F-16
IV.F-4 City of Los Angeles Guidelines for Noise Compatible Land Use .....	IV.F-17
IV.F-5 Description of Noise Measurement Locations.....	IV.F-21
IV.F-6 Existing Ambient Noise Levels.....	IV.F-22
IV.F-7 Existing Roadway Traffic Noise Levels .....	IV.F-24
IV.F-8 Vehicle Mix for Traffic Noise Model .....	IV.F-25
IV.F-9 Construction Equipment Noise Levels .....	IV.F-33
IV.F-10 Construction Noise Impacts .....	IV.F-34
IV.F-11 Off-Site Construction Truck Noise Levels .....	IV.F-36
IV.F-12 Estimated Noise Levels from Mechanical Equipment .....	IV.F-39
IV.F-13 Outdoor Use Analysis Assumptions.....	IV.F-39
IV.F-14 Estimated Noise Levels from Outdoor Uses .....	IV.F-41
IV.F-15 Estimated Noise Levels from Parking Facilities .....	IV.F-41
IV.F-16 Estimated Noise Levels from Loading Area .....	IV.F-43
IV.F-17 Roadway Traffic Noise Impacts—Future Plus Project .....	IV.F-44
IV.F-18 Roadway Traffic Noise Impacts—Existing Plus Project .....	IV.F-45

<b><u>Table</u></b>	<b><u>Page</u></b>
IV.F-19 Composite Noise Impacts .....	IV.F-47
IV.F-20 Construction Noise Impacts With Mitigation Measures .....	IV.F-49
IV.F-21 Construction Vibration Impacts—Building Damage .....	IV.F-52
IV.F-22 Construction Vibration Impacts—Human Annoyance .....	IV.F-53
IV.F-23 Cumulative Roadway Traffic Noise Impacts .....	IV.F-66
IV.G.1-1 Relevant General Plan Fire Protection Goals, Objectives, and Policies: Framework Element—Chapter 9, Infrastructure and Public Services .....	IV.G.1-7
IV.G.1-2 Relevant General Plan Fire Protection Goals, Objectives, and Policies: Framework Element—Safety Element.....	IV.G.1-9
IV.G.1-3 LAFD Stations Located in the Vicinity of the Project Site.....	IV.G.1-16
IV.G.1-4 Average Emergency Medical Service and Structure Fire Response Times.....	IV.G.1-16
IV.G.2-2 Estimated Service Population from Related Projects within Hollywood Area.....	IV.G.2-18
IV.G.3-1 LAPL Branch Facilities Plan—Library Building Size Standards .....	IV.G.3-3
IV.G.3-2 Related Projects with Cumulative Library Impacts.....	IV.G.3-12
IV.H-1 Project Consistency With Mobility Plan 2035.....	IV.H-29
IV.H-2 Project Consistency With Plan for a Healthy Los Angeles .....	IV.H-39
IV.J.1-1 Applicable General Plan Utilities and Service Systems Goals, Objectives, and Policies: Framework Element--Chapter 9 Infrastructure and Public Services .....	IV.J.1-14
IV.J.1-2 LADWP Water Supply .....	IV.J.1-17
IV.J.1-3 Local Groundwater Basin Supply.....	IV.J.1-19
IV.J.1-4 City of Los Angeles Water Demand Projections (thousand AFY) .....	IV.J.1-27
IV.J.1-5 Project Water Demand .....	IV.J.1-37
IV.J.1-6 Cumulative Water Demand.....	IV.J.1-40
IV.J.2-1 Estimated Existing Project Site Wastewater Generation .....	IV.J.2-7
IV.J.2-2 Existing Capacity of Hyperion Sanitary Sewer System.....	IV.J.2-9
IV.J.2-3 Estimated Wastewater Generation .....	IV.J.2-14

<b><u>Table</u></b>	<b><u>Page</u></b>
IV.J.2-4 Cumulative Wastewater Generation .....	IV.J.2-19
V-1 Summary Comparison of Development Proposed under Alternatives to the Project.....	V-5
V-2 Comparison of Impacts Associated with the Alternatives .....	V-12