Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Irwin Road Tank and Transmission Main Project

Lead Agency: State Water Resources Control Board

Contact Name: Wendy Pierce

Email: Wendy.Pierce@waterboards.ca.gov Phone Number: (916) 449-5178

Project Location: Barstow (*City*) San Bernardino County (*County*)

Project Decription (Proposed actions, location, and/or consequences).

The Project includes the construction, operation, and maintenance of a proposed 1.5 million gallon welded steel water reservoir and approximately 5,816 linear feet (1.1 miles) of 12-inch diameter ductile iron water transmission pipeline along the east side of Irwin Road that would connect to existing pipeline located at the intersection of Irwin Road and Gabilan Street. Approximately 4,000 linear feet (0.75 miles) of the Project is located within land owned by the County of San Bernardino and 1,800 linear feet (0.34 miles) of the Project lies within Bureau of Land Management (BLM)-lands. The reservoir would be constructed on a 1.03-acre site that would require permanent right-of-way from BLM.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Biological Resources: BIO-1 Pre-Construction Survey for Cactus and Succulents, BIO-2 Desert Tortoise Protection, BIO-3 Pre-construction Survey for Burrowing Owl, BIO-4 Mohave Ground Squirrel Protection, BIO-5 Pre-construction Nesting Bird Survey, BIO-6 Vegetation Protection and Restoration

Geology: GEO-1 Discovery of Paleontological Resources

Hydrology and Water Quality: HYD-1: A construction inspector will be employed in the field during construction, HYD-2: Temporary erosion/sediment control devices, HYD-3: Project-related ground disturbance will be limited to the minimum necessary, HYD-4: Project-related construction, clean up, and reclamation, HYD-5: Stockpile of erosion control materials, HYD-6: All construction personnel, vehicles, and equipment shall be confined to designated areas

Noise: NOI-1: During Project construction, stationary noise-generating equipment shall be located as far as is practicable from any existing structure designed for human occupancy. NOI-2: construction activities shall be limited to between the hours of 7:00 a.m. and 5:00 p.m., Monday through Saturday. Construction during other periods, including Sundays and holidays, shall be limited to emergencies NOI-3: All construction equipment shall be operated with mandated noise control equipment

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Wildlife
San Bernardino County Department of Public Works
Mojave Desert Air Quality Management District