Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Oregon Street Improvements Project

Lead Agency: City of Redding

Contact Name: Amber Kelley

Email: akelley@cityofredding.org Phone Number: 530-225-4046

Project Location: Redding, Shasta County
City *County*

Project Description (Proposed actions, location, and/or consequences).

The City of Redding (City) is proposing the Oregon Street Improvements Project (project). The project area includes two discontinuous segments along Oregon Street: The first area is located between Yuba Street and Butte Street, and the second area is located between Tehama Street and Shasta Street. The purpose of this project is to improve pedestrian access and safety. The project is needed because these two roadway sections do not currently have a sidewalk, which forces pedestrians to walk on the edge of the pavement next to an open channel or walk in the travel way. Under existing conditions, some disabled pedestrians do not have a choice and must traverse the travel way. The proposed project would provide approximately 460 linear feet of 10-foot sidewalk for pedestrians, as well as Americans with Disabilities Act (ADA) compliant curb ramps. In order to construct the project, approximately 460 feet of new 5-foot by 8-foot box culvert would be installed within the two open channel segments of Calaboose Creek along Oregon Street. The new sidewalk, curb, and gutter would be constructed over the subsurface box culvert. The project includes pavement grinding and a pavement overlay; however, the project will not increase vehicle capacity.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The following mitigation measures will be incorporated into the project to minimize potential effects on biological resources:

MM-1. Construction activities within Calaboose Creek shall be limited to a work window of June 1 to October 31.

MM-2. If vegetation removal or construction activities will occur during the nesting season for migratory birds or raptors (February 1 through August 31), a qualified biologist shall conduct a preconstruction survey 7 days before construction activities begin. If nesting birds or raptors are found, CDFW will be notified and consulted. An appropriate buffer, as determined by CDFW and the qualified biologist, will be placed around the nest until the young have fledged. If construction activities cease for a period greater than 7 days, additional preconstruction surveys will be required.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

No known issues.

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Wildlife - Region 1
Central Valley Regional Water Quality Control Board - Region 5, Redding