Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Parkfield Fire Station

Lead Agency: California Department of Forestry and Fire Protection

Contact Name: Christina Snow

Email: christina.snow@fire.ca.gov Phone Number: 916-995-6044

Project Location: _____
City *County*

Project Description (Proposed actions, location, and/or consequences).

This Project includes construction of a 1-engine fire station single building with 8-bed barracks and 2-bay apparatus (6067 sf); a generator/pump building (648 sf) with backup generator and transfer switch; a storage building (494 sf), and a vehicle wash building (1008 sf).

The Project also includes new underground utilities and/or connections (water, drainage, sewer, electric, gas, telephone/radio); fuel facility (storage tanks/dispensing system, canopy); a hose wash rack; grading, paving, walkways, drainage structures and landscaping; propane system; new septic system, new potable water well, water treatment system, and potable and fire water storage tanks; security fencing and lighting, and associated appurtenances.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The visual aspect of the property will change from agriculture to an active fire station. Appropriate landscaping to soften hardscape will be implemented.

The area is sensitive with regard to cultural resources. Monitoring is proposed by local tribes to ensure potential impacts are mitigated through consultation if necessary.

The project is located in an area known for earthquake activity. Several recommendations from geotechnical studies will be implemented to mitigate any potential safety concerns.

The noise from the public address system could be problematic if the system is not kept at a level that would not disturb nearby rural residents. The noise levels are limited to 85 A-weighted decibels (dBA) at a distance of 50 feet (ft) or below for daytime nonemergency purposes.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

Provide a list of the responsible or trustee agencies for the project.