

May 28, 2021 File No. 33348-08

The Cove at El Niguel c/o Laguna Niguel Properties, Inc. 27422 Portola Parkway, Suite 300 Foothill Ranch, CA 92610

Attention: Ms. Deborah Hon

Mr. Brian Diaz / Recupero and Associates, Inc.

Subject: ADDENDUM REPORT – ADDING GEOLOGY TO CURRENT SITE PLAN

The Cove at El Niguel - Tentative Tract No. 17721

30667 Crown Valley Parkway Laguna Niguel, California

References: **TENTATIVE TRACT MAP NO. 17721**

By: Hunsaker & Associates Irvine, Inc.

Dated: May 27, 2021

RESPONSE TO CITY OF LAGUNA NIGUEL GEOTECHNICAL REVIEW SHEET DATED FEBRUARY 15, 2021 AND NOTICE OF INCOMPLETENESS DATED FEBRUARY 23, 2021

By: American Geotechnical, Inc. (File No. 33348-08)

Dated: April 2, 2021

GEOTECHNICAL REVIEW OF TENTATIVE TRACT MAP

By: American Geotechnical, Inc. (File No. 33348-08)

Dated: January 8, 2021

Dear Ms. Hon:

The project civil engineer, Mr. Robert Glessner of Hunsaker and Associates Irvine, Inc. (Hunsaker), forwarded us a copy of the revised Tentative Tract Map No. 17721 (TTM) dated May 27, 2021 for the proposed redevelopment project, The Cove at El Niguel, located in Laguna Niguel, California. Mr. Glessner indicated that he had a conference call last week with the City's geotechnical reviewer, GMU Geotechnical, Inc. (GMU) to discuss if a conventional retaining wall could be used on the north side of Playa Blanca and along Crown Valley Parkway. GMU requested that a letter from the project geotechnical engineer, American Geotechnical, Inc. (AGI) be provided for their review and the letter should state that based on AGI's review, the current site plan would comply with the recommendations presented in the referenced report dated January 8, 2021 and to confirm that the minor changes of the site plan would not affect site geology or recommendations for the proposed retaining walls.

File No. 33348-08 May 28, 2021 Page **2** of **3**



GEOTECHNICAL REVIEW OF TENTATIVE TRACT MAP DATED MAY 27, 2021

We conducted a geotechnical review of the revised Tentative Tract Map No. 17721 (TTM) dated May 27, 2021 prepared by Hunsaker and Associates Irvine, Inc. (Hunsaker). Prior to our review, we updated Plate 1 – Preliminary Geotechnical/Geologic Map shown in our January 8, 2021 report by adding a site geologic map to the current site plan as shown in the revised TTM dated May 27, 2021. A copy of the updated **Plate 1** is attached in this addendum report. Our review revealed that the revised stie plan has only minor changes in the retaining walls on the north side of Playa Blanca and along Crown Valley Parkway.

The current site plan shows a conventional retaining wall proposed on the north side of Playa Blanca. The height of this wall varies from 5 to 6.6 feet maximum. On top of this wall, another shorter-lengthed conventional retaining wall is also proposed. This wall height varies from 0 to 6 feet maximum.

The current site plan shows either a MSE or conventional retaining wall is proposed on top of the slope along Crown Valley Parkway. This wall varies from 2 to 3.4 feet maximum in height. There is another MSE or conventional retaining wall proposed below the top-of-the slope retaining wall. This lower retaining wall is 2.5 to 3-feet high and is terminated then joined at the top-of-slope retaining wall at the south side of Lot 3.

CONCLUSIONS AND DISCUSSIONS

Based on our review of the current site plan shown in the revised Tentative Tract Map No. 17221 (TTM) dated May 27, 2021, it is our opinion that from a geotechnical standpoint, the proposed minor changes of the retaining walls on the north side of Playa Blanca and along Crown Valley Parkway have no significant changes from the previous site plan. As such, it is our opinion that the recommendations for a conventional retaining wall and MSE wall presented in the referenced January 8, 2021 report are still valid and applicable to the proposed minor changes of the retaining walls discussed above. Additionally, it is our opinion that the proposed minor changes of the retaining walls would not affect the site geology and would not have any significant impact to the stability of the slopes provided the recommendations presented in our January 8, 2021 report are followed in the retaining wall design and during construction.

File No. 33348-08 May 28, 2021 Page **3** of **3**



We appreciate the opportunity to be of service. Should you have any questions regarding the information provided herein, please do not hesitate to contact this office. When additional plans become available, they should be forwarded to this office for review and comment.

Respectfully Submitted,

AMERICAN GEOTECHNICAL, INC.

Pei-chiu (Jerry) Huang, Ph.D.

Principal Engineer G.E. 2601

Douglas S. Santo

Chief Engineering Geologist

C.E.G. 1866

Enclosure: Updated Preliminary Geotechnical/Geologic Map (Plate 1)

Distribution: 5 – Addressee (Regular Mail and Email: Deborah.hon@hondev.com)

Mr. Brian Diaz (Email: bdiaz@recupero.net)

SP/33348-08 Addendum JH GWA DS 5-28-21 DL

Gregory W. Axten President/CEO

G.E. 103

