Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Getty Center Parking Improvement Project

Lead Agency: City of Los Angeles

Contact Name: Esther Serrato, City Planner

Email: esther.serrato@lacity.org Phone Number: (213) 978-1211

Project Location: Los Angeles, Los Angeles County
City *County*

Project Decription (Proposed actions, location, and/or consequences).

The Getty Center Parking Improvement Project proposes two new landscaped surface parking areas providing up to 217 vehicle parking spaces and a new 250 square-foot restroom station. The Project Site is located on two existing, previously-graded pads adjacent to the I-405 Freeway and north of the Getty Center Drive entrance. The Project Site will be improved with water conveyance infrastructure, fire hydrants, drought tolerant landscaping, and security lighting. Approximately 3,500 cubic yards of earthwork consisting of 1,400 cubic yards of soil export and 2,100 cubic yards of soil import are proposed. No protected trees are located on the Project Site. The project requests Public Benefit Project Approval with alternative compliance measures.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The Project will have a potential impacts related to Biological Resources. To address biological resource impacts, the Project shall comply with the following mitigation measures:

MM-BIO-1: The Project Area shall be demarcated with visible fencing in order to ensure the construction activities remain within the Project Site.

MM-BIO-2: General wildlife surveys shall be completed no more than 48 hours prior to commencement of construction activities to assess the presence of special status wildlife in the Project Site. If wildlife is found, individuals would be allowed to leave the site on their own.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Game