

Standard Conditions of Approval Applicable to Project

Air Quality-Related

1. **Air Quality and Dust Control.** The following measures shall be shown on grading and building plans and shall be adhered to throughout grading, hauling, and construction activities:
 - a. During construction, use water trucks or sprinkler systems to keep all areas of vehicle movement damp enough to prevent dust from leaving the site. At a minimum, this should include wetting down such areas in the late morning and after work is completed for the day. Increased watering frequency should be required whenever the wind speed exceeds 15 mph. Reclaimed water should be used whenever possible. However, reclaimed water should not be used in or around crops for human consumption.
 - b. Minimize amount of disturbed area and reduce on site vehicle speeds to 15 miles per hour or less.
 - c. If importation, exportation and stockpiling of fill material is involved, soil stockpiled for more than two days shall be covered, kept moist, or treated with soil binders to prevent dust generation. Trucks transporting fill material to and from the site shall be tarped from the point of origin.
 - d. Gravel pads shall be installed at all access points to prevent tracking of mud onto public roads.
 - e. After clearing, grading, earth moving or excavation is completed, treat the disturbed area by watering, or revegetating, or by spreading soil binders until the area is paved or otherwise developed so that dust generation will not occur.
 - f. The contractor or builder shall designate a person or persons to monitor the dust control program and to order increased watering, as necessary, to prevent transport of dust offsite. Their duties shall include holiday and weekend periods when work may not be in progress. The name and telephone number of such persons shall be provided to the Air Pollution Control District prior to land use clearance for map recordation and land use clearance for finish grading of the structure.
 - g. All portable diesel-powered construction equipment shall be registered with the state's portable equipment registration program OR shall obtain an APCD permit.
 - h. Fleet owners of mobile construction equipment are subject to the California Air Resources Board (CARB) Regulation for In-use Off-road Diesel Vehicles (Title 13 California Code of Regulations, Chapter 9, § 2449), the purpose of which is to reduce diesel particulate matter (PM) and criteria pollutant emissions from in-use (existing) off-road diesel-fueled vehicles. For more information, please refer to the CARB website at www.arb.ca.gov/msprog/ordiesel/ordiesel.htm.
 - i. All commercial diesel vehicles are subject to Title 13, § 2485 of the California Code of Regulations, limiting engine idling time. Idling of heavy-duty diesel construction equipment and trucks during loading and unloading shall be limited to five minutes; electric auxiliary power units should be used whenever possible.

- j. Diesel construction equipment meeting the California Air Resources Board (CARB) Tier 1 emission standards for off-road heavy-duty diesel engines shall be used. Equipment meeting CARB Tier 2 or higher emission standards should be used to the maximum extent feasible.
- k. Diesel powered equipment should be replaced by electric equipment whenever feasible.
- l. If feasible, diesel construction equipment shall be equipped with selective catalytic reduction systems, diesel oxidation catalysts and diesel particulate filters as certified and/or verified by EPA or California.
- m. Catalytic converters shall be installed on gasoline-powered equipment, if feasible.
- n. All construction equipment shall be maintained in tune per the manufacturer's specifications.
- o. The engine size of construction equipment shall be the minimum practical size.
- p. The number of construction equipment operating simultaneously shall be minimized through efficient management practices to ensure that the smallest practical number is operating at any one time. Construction worker trips should be minimized by requiring carpooling and by providing for lunch onsite.

Cultural Resources-Related

1. **Unanticipated Archaeological Resources Contractor Notification.** Standard discovery measures shall be implemented per the City master Environmental Assessment throughout grading and construction: Prior to the start of any vegetation or paving removal, demolition, trenching or grading, contractors and construction personnel shall be alerted to the possibility of uncovering unanticipated subsurface archaeological features or artifacts. If such archaeological resources are encountered or suspected, work shall be halted immediately, the City Environmental Analyst shall be notified and the Owner shall retain an archaeologist from the most current City Qualified Archaeologists List. The latter shall be employed to assess the nature, extent and significance of any discoveries and to develop appropriate management recommendations for archaeological resource treatment, which may potentially include, but are not limited to, redirection of grading and/or excavation activities, consultation and/or monitoring with a Barbareño Chumash representative from the most current City qualified Barbareño Chumash Site Monitors List, testing, documentation, collection, and curation of resources, etc. Measures will be implemented to ensure no significant impact involving important resources will result.

If the discovery consists of possible human remains, the Santa Barbara County Coroner shall be contacted immediately. If the Coroner determines that the remains are Native American, the Coroner shall contact the California Native American Heritage Commission. A Barbareño Chumash representative from the most current City Qualified Barbareño Chumash Site Monitors List shall be retained to monitor all further subsurface disturbance in the area of the find. Work in the area may only proceed after the Environmental Analyst grants authorization.

If the discovery consists of possible prehistoric or Native American artifacts or materials, a Barbareño Chumash representative from the most current City Qualified Barbareño Chumash Site Monitors List shall be retained to monitor all further subsurface disturbance in the area of the find. Work in the area may only proceed after the Environmental Analyst grants authorization.

A final report on the results of the archaeological monitoring shall be submitted by the City-approved archaeologist to the Environmental Analyst within 180 days of completion of the monitoring and prior to any certificate of occupancy for the project.

Construction-Related

1. **Haul Routes Require Separate Permit.** Apply for a Public Works Permit to establish the haul route(s) for all construction-related trucks with a gross vehicle weight rating of three tons or more, entering or exiting the site. The Haul Routes shall be approved by the Transportation Engineer.
2. **Construction-Related Truck Trips.** Construction-related truck trips for trucks with a gross vehicle weight rating of three tons or more shall not be scheduled during peak hours (7:00 a.m. to 9:00 a.m. and 4:00 p.m. to 6:00 p.m.) in order to help reduce truck traffic on adjacent streets and roadways.
3. **Construction Parking.** During construction, free parking spaces for construction workers shall be provided on-site or off-site in a location subject to the approval of the Transportation Manager.
4. **Construction Storage/Staging.** Construction vehicle/ equipment/ materials storage and staging shall be done on-site. No parking or storage shall be permitted within the public right-of-way, unless specifically permitted by the Transportation Manager with a Public Works permit.

Noise-Related

1. **Neighborhood Notification Prior to Construction.** At least twenty (20) days prior to commencement of construction, the contractor shall provide written notice to all property owners, businesses, and residents within 300 feet of the project area. The notice shall contain a description of the project, the construction schedule, including days and hours of construction, the name and phone number of the Project Environmental Coordinator (PEC) and Contractor(s), site rules and Conditions of Approval pertaining to construction activities, and any additional information that will assist Building Inspectors, Police Officers and the public in addressing problems that may arise during construction.
2. **Construction Hours.** Construction (including preparation for construction work) shall only be permitted Monday through Friday between the hours of 7:00 a.m. and 5:00 p.m. and Saturdays between the hours of 9:00 a.m. and 4:00 p.m., excluding the following holidays:

New Year's Day	January 1st*
Martin Luther King, Jr. Day	3rd Monday in January
Presidents' Day	3rd Monday in February
Memorial Day	Last Monday in May
Independence Day	July 4th*
Labor Day	1st Monday in September
Thanksgiving Day	4th Thursday in November
Following Thanksgiving Day	Friday following Thanksgiving Day
Christmas Day	December 25th*

*When a holiday falls on a Saturday or Sunday, the preceding Friday or following Monday, respectively, shall be observed as a legal holiday.

When, based on required construction type or other appropriate reasons, it is necessary to do work outside the allowed construction hours, contractor shall contact the City to request a waiver from the above construction hours, using the procedure outlined in Santa Barbara Municipal Code §9.16.040 Construction Work at Night. Contractor shall notify all residents within 300 feet

of the parcel of intent to carry out said construction a minimum of 48 hours prior to said construction. Said notification shall include what the work includes, the reason for the work, the duration of the proposed work and a contact number.

Water Quality-Related

1. **Storm Water Pollution Control and Drainage Systems Maintenance.** Owner shall maintain the drainage system and storm water pollution control devices in a functioning state and in accordance with the Storm Water BMP Guidance Manual and Operations and Maintenance Procedure Plan approved by the Creeks Division. Should any of the project's surface or subsurface drainage structures or storm water pollution control methods fail to capture, infiltrate, and/or treat water, or result in increased erosion, the Owner shall be responsible for any necessary repairs to the system and restoration of the eroded area. Should repairs or restoration become necessary, prior to the commencement of such repair or restoration work, the Owner shall submit a repair and restoration plan to the Community Development Director to determine if an amendment or a new Building Permit is required to authorize such work. The Owner is responsible for the adequacy of any project-related drainage facilities and for the continued maintenance thereof in a manner that will preclude any hazard to life, health, or damage to the Real Property or any adjoining property.
2. **Drainage and Water Quality.** The project is required to comply with Tier 3 of the Storm Water BMP Guidance Manual, pursuant to Santa Barbara Municipal Code Chapter 22.87 treatment, rate and volume. The Owner shall submit a hydrology report prepared by a registered civil engineer or licensed architect demonstrating that the new development will comply with the City's Storm Water BMP Guidance Manual. Project plans for grading, drainage, stormwater facilities and treatment methods, and project development, shall be subject to review and approval by the City Building Division and Public Works Department. Sufficient engineered design and adequate measures shall be employed to ensure that no unpermitted construction-related or long-term effects from increased runoff, erosion and sedimentation, urban water pollutants (including, but not limited to trash, hydrocarbons, fertilizers, bacteria, etc.), or groundwater pollutants would result from the project.

For any proprietary treatment devices that are proposed as part of the project's final Storm Water Management Plan, the Owner shall provide an Operations and Maintenance Procedure Plan consistent with the manufacturer's specifications (describing schedules and estimated annual maintenance costs for pollution absorbing filter media replacement, sediment removal, etc.). The Plan shall be reviewed and approved by the Creeks Division for consistency with the Storm Water BMP Guidance Manual and the manufacturer's specifications.

After certificate of occupancy is granted, any proprietary treatment devices installed will be subject to water quality testing by City Staff to ensure they are performing as designed and are operating in compliance with the City's Storm Water MS4 Permit.