

---

# PRELIMINARY HYDROLOGY REPORT

for

## PALMDALE INDUSTRIAL PARK

South of East Avenue P  
Between Sierra Highway and 8<sup>th</sup> Street East  
City of Palmdale, CA 93550

*Prepared For:*

**Covington Development Partners, LLC**  
**3 Corporate Plaza, Suite 230**  
**Newport Beach, CA 92660**

*Prepared By:*

**Langan Engineering and Environmental Services, Inc.**  
**515 South Flower Street, Suite 1060**  
**Los Angeles, CA 90071**

---

**Michael Golias**  
**Professional Engineer License No. 91029**

**Prepared: March 2023**  
**Langan Project No. 722010601**

# **LANGAN**

## TABLE OF CONTENTS

<b>1.0</b>	<b>INTRODUCTION.....</b>	<b>1</b>
<b>2.0</b>	<b>PROJECT DESCRIPTION.....</b>	<b>1</b>
	<b>2.1 Existing Site Description.....</b>	<b>1</b>
	<b>2.2 Proposed Site Description .....</b>	<b>1</b>
<b>3.0</b>	<b>PROJECT ANALYSIS .....</b>	<b>2</b>
	<b>3.1 Methodology .....</b>	<b>2</b>
	<b>3.2 Hydrology Results &amp; Analysis .....</b>	<b>2</b>
	<b>3.3 Chamber Analysis.....</b>	<b>3</b>
	<b>3.4 Hydraulic Analysis .....</b>	<b>5</b>
<b>4.0</b>	<b>CONCLUSION .....</b>	<b>5</b>
<b>5.0</b>	<b>REFERENCES .....</b>	<b>5</b>

## FIGURES

<b>Figure 1</b>	<b>Site Vicinity Map</b>
<b>Figure 2</b>	<b>Proposed Site Plan</b>
<b>Figure 3</b>	<b>Pre-Development Drainage Map</b>
<b>Figure 4</b>	<b>Post-Development Drainage Map</b>

## APPENDICES

<b>Appendix A</b>	<b>LA County Hydrology Map – 50-Year, 24-Hour Storm</b>
<b>Appendix B</b>	<b>LA County Hydrology Map – Soils 2004</b>
<b>Appendix C</b>	<b>FEMA Flood Insurance Rate Map</b>
<b>Appendix D</b>	<b>Pre-Development HydroCalc Calculations</b>
<b>Appendix E</b>	<b>Post-Development HydroCalc Calculations</b>
<b>Appendix F</b>	<b>Infiltration Chamber Calculations and Details</b>
<b>Appendix G</b>	<b>Infiltration Report</b>

## **1.0 INTRODUCTION**

The purpose of this hydrology report is to analyze the existing and proposed surface-water hydrology and identify the impacts that are associated with the proposed development. This report provides analysis for designing the proposed on-site drainage systems and on-site proposed below grade infiltration chambers.

According to the analysis, the proposed development will not create and additional impacts to the downstream storm drain infrastructure. Furthermore, the proposed development will be protected against flooding in a 25-year, 24-hour storm event.

## **2.0 PROJECT DESCRIPTION**

### **2.1 Existing Site Description**

The project site is approximately 18.11 acres and is located within the City of Palmdale, Los Angeles County in the State of California. The site is located south of East Avenue P, and is bounded by an existing railroad to the north, Sierra Highway to the west, 8<sup>th</sup> Street to the east and an existing drainage channel to the south. The site is currently undeveloped the site has been previously cleared and graded. See Figure 1 for the site vicinity map.

The site is generally flat, flowing from the western edge towards several low points along the eastern boundary. The existing drainage channel running along the southern boundary captures off-site runoff from the west and flows through the site towards the east where it discharges to an existing channel across 8<sup>th</sup> Street. No groundwater wells exist on site. Per the Geotechnical Report provided, groundwater was not found within 25' of existing grade. See Figure 3 for the Pre-Development Hydrology Map.

### **2.2 Proposed Site Description**

The proposed development consists of a 380,000 square foot industrial warehouse facility with loading docks, trailer and car parking, and landscaped areas. See Figure 2 for the proposed site plan. On-site stormwater will be captured through a series of catch basins and storm drains which are routed to various underground infiltration chambers located along the northern and southern areas of the Site. The captured stormwater will be pre-treated through a hydrodynamic separator prior to entering the chambers. During significant rain events, stormwater will by-pass the hydrodynamic separator and flow directly into the chambers. The underground infiltration chambers will discharge directly into the proposed culverts beneath 8<sup>th</sup> Street.

The existing drainage channel running along the southern border of the site will be reconstructed to an earthen channel per the Palmdale MDP. It will maintain its existing flow path, which flows from west to east. The earthen channel will collect off-site flows from the west and flow through the site where it will discharge into the proposed culverts. The earthen channel will have stabilized side slopes to prevent erosion. The proposed culverts will discharge on the east side of East 8<sup>th</sup> Street and a headwall and rip rap will be installed to decrease the velocity of the flows and reduce the potential for significant erosion downstream of the improvements.

### 3.0 PROJECT ANALYSIS

#### 3.1 Methodology

The Los Angeles County Hydrology Manual for the 25-year storm was used as a basis for the hydrologic analysis. The Modified Rational (MODRAT) method was utilized to calculate the quantity and rate of stormwater runoff for the pre- and post-development conditions. The HydroCalc software provided by LA County was then used to compute the calculations for the MODRAT method. As required by City guidelines, the pre- and post-development peak flows and volumes were also calculated for the 0.75-inch, 2-year, 10-year, and 50-year storms, and are provided in Appendices D & E. The following parameters were required as inputs for the HydroCalc calculations.

- 0.75-inch, 24-hour Depth
- 50-Year Rainfall Depth = 3.5 inches (See Appendix A - LA County Hydrology Map)
- Soil Classification = 134 (See Appendix B – LA County Hydrology Map Soils 2004)

#### 3.2 Hydrology Results & Analysis

The existing conditions at the Site were analyzed to determine drainage areas and flow patterns. Based on existing flow patterns, the Site was subdivided into 6 drainage areas (Areas A-F), and flow lengths and slopes within each area were determined (see Figure 3). The Site is currently undeveloped and the runoff generally flowed from the western property line towards the east. The pre-development condition analyzed for the 25-year storm generates a total flow of 1.54 cubic feet/second, and a volume of 21,638 cubic feet. The table below summarizes the drainage areas and their respective flows and volumes.

**Table 3.2.1 Pre-Development Flows for 25-Year Storm**

AREA ID	AREA (SF)	AREA (AC)	IMPERVIOUS RATIO	Q25 (CFS)	V25 (CF)
A	260,328	5.98	0	0.51	7,145
B	201,574	4.63	0	0.39	5,532
C	131,776	3.03	0	0.26	3,620
D	62,407	1.43	0	0.12	1,709
E	72,686	1.67	0	0.14	1,995
F	59,891	1.37	0	0.12	1,637
<b>TOTAL</b>	784,965	18.11	-	1.54	21,638

The same process was performed for the post-development condition and is summarized in the table below (see Figure 4). Drainage Areas A and B were considered as areas that would contribute to runoff on-site. The runoff from Areas A and B will be captured through the onsite storm drain system, pre-treated through a hydrodynamic separator, and then routed to the proposed underground infiltration chambers. Area C, which is predominantly landscaped area (pervious) sheet flows offsite to 8<sup>th</sup> Street. Area D covers the area where the existing channel will be reconstructed to an earthen channel. The earthen channel will convey offsite flows from the west along with runoff generated within its extents, to the proposed culverts that will run under 8<sup>th</sup> Street and drain to the existing channel northeast of the site. When analyzed for the 25-year storm, the proposed development generates a total flow of 13.77 cubic feet/second and a volume of 144,585 cubic feet.

**Table 3.2.2 Post-Development Flows for 25-Year Storm**

AREA ID	AREA (SF)	AREA (AC)	IMPERVIOUS RATIO	Q25 (CFS)	V25 (CF)
A1	180,022	4.13	0.83	2.83	34,907
A2	38,776	0.89	0.84	1.03	7,606
A3	15,946	0.37	0.51	0.33	2,087
A4	214,613	4.93	1.00	4.58	49,086
B1	52,363	1.20	0.93	1.07	11,204
B2	7,885	0.18	0.98	0.29	1,761
B3	165,823	3.81	1	3.64	37,934
<b>TOTAL</b>	675,411	15.51	-	13.77	144,585
AREA ID	AREA (SF)	AREA (AC)	IMPERVIOUS RATIO	Q25 (CFS)	V25 (CF)
C	68,708	1.58	0.00	0.13	1,888
D	44,593	1.02	0.14	0.24	2,392
<b>TOTAL</b>	113,301	2.60	-	0.37	4,280

The table below shows a comparison of the total flows and volumes generated on-site between the pre- and post-development. The proposed development increases flows to 13.77 cubic feet/second and generates a total of 144,585 cubic feet of runoff. The total flow and volume quantities will be utilized to design the proposed storm drain system and underground infiltration chambers to ensure stormwater is captured, stored and conveyed appropriately.

**Table 3.2.3 Pre and Post-Development Flows for 25-Year Storm**

CONDITION	Q25 (CFS)	V25 (CF)
PRE-DEVELOPMENT	1.54	21,638
POST DEVELOPMENT	13.77	144,585
DIFFERENCE	12.23	122,947

### 3.3 Chamber Analysis

The infiltration report prepared by Southern California Geotechnical, dated on March 9<sup>th</sup>, 2022, recorded two design infiltration rates of 0.2 inches/hour and 0.4 inches/hour. The 0.2 inches/hour and 0.4 inches/hour rates were located in the southeastern and northeastern area of the site, respectively (see Appendix G). Because the minimum feasible infiltration rate per LA County is 0.3 inches/hour, additional tests should be explored to confirm rates and explore other areas where infiltration may be feasible.

Two underground infiltration chambers (Chambers A and B) were proposed and designed to fully retain the 25-year storm volumes from each of their respective drainage areas. The stormwater will be treated to remove partial sediments, trash and debris prior to entering the chambers. The chambers were designed taking into account a drawdown of 96 hours. Chamber A was designed with the infiltration rate of 0.4 inches/hour, and Chamber B was based on the rate of 0.2 inches/hour.

The total 25-year storm volume resulted in 144,585 cubic feet. Areas A1-A4 generated approximately 93,685 cubic feet of runoff and is stored in Chamber A, which has a capacity of 94,960 cubic feet. Chamber B holds a capacity of 52,017 cubic feet, which sufficiently stores the 50,899 cubic feet of runoff from their respective drainage areas. All chambers provide storage to retain the 25-year storm event, and also provide storage for water quality before outflowing to the proposed culverts. The total outflow from the chambers, Areas C and D resulted in a flow of 1.25 cubic feet/second. The total does not exceed 1.31 cubic feet/second, which is 85% of the pre-development flows from the 25-year storm. Refer to the tables below and Appendix F for calculations and details.

**Table 3.3.1 Chamber Analysis Summary**

AREA ID	DRAINAGE AREA (AC)	IMPERVIOUS RATIO	Q25 (CFS)	V25 (CF)	BASIN DEPTH (FT)	BASIN VOLUME PROVIDED (CF)	CHAMBER DESIGNATION
A1	4.13	0.83	2.83	34906.91	5	94,960	A
A2	0.89	0.84	1.03	7605.50			A
A3	0.37	0.51	0.33	2087.19			A
A4	4.93	1.00	4.58	49085.80			A
B1	1.20	0.93	1.07	11204.44	10	52,017	B
B2	0.18	0.98	0.29	1760.57			B
B3	3.81	1	3.64	37934.46			B
C	1.58	0.00	0.13	1887.78	-	-	OFFSITE
D	1.02	0.14	0.24	2392.23	-	-	OFFSITE

**Table 3.3.2 Chamber A Drawdown/Outlet Summary**

DRAWDOWN/OUTLET VOLUME CALCULATIONS	
DESIGN INFILTRATION RATE (IN/HR)	0.4
DRAWDOWN TIME (HR)	96
DRAWDOWN IN 96 HRS (FT)	1.6
CMP TOTAL FOOTPRINT (SF)	37,500
DRAWDOWN VOLUME IN 96 HR	120,000
VOLUME TO OUTLET (CF)	0
AVERAGE DISCHARGE PER ELEVATION (CFS)	0.30
AVERAGE DISCHARGE PER ELEVATION (CF/HR)	1,076
DESIGN OUTLET VOLUME (CF IN 24 HR)	25,816
OUTLET PIPE CENTROID ELEVATION	1.17
PIPE DIAMETER (IN)	3
PEAK OUTFLOW (CFS)	0.43

**Table 3.3.3 Chamber B Drawdown/Outlet Summary**

<b>DRAWDOWN/OUTLET VOLUME CALCULATIONS</b>	
DESIGN INFILTRATION RATE (IN/HR)	0.2
DRAWDOWN TIME (HR)	96
DRAWDOWN IN 96 HRS (FT)	1.6
CMP TOTAL FOOTPRINT (SF)	8568
DRAWDOWN VOLUME IN 96 HR	13709
VOLUME TO OUTLET (CF)	38127
AVERAGE DISCHARGE PER ELEVATION (CFS)	0.31
AVERAGE DISCHARGE PER ELEVATION (CF/HR)	1104
DESIGN OUTLET VOLUME (CF IN 24 HR)	26497
OUTLET PIPE CENTROID ELEVATION	2.5
PIPE DIAMETER (IN)	3
PEAK OUTFLOW (CFS)	0.45

### 3.4 Hydraulic Analysis

Preliminary hydraulic calculations will be performed with the Hydraflow Express in Autodesk Civil 3D. Inlet and storm drain sizing were analyzed to determine if the proposed sizes would be adequate to support flows resulting from the 25-year storm event. The preliminary storm pipes were sized to assuming full capacity with a minimum slope of 0.50%. A roughness coefficient of 0.012 was assumed for HDPE pipes.

### 4.0 CONCLUSION

Based on the preliminary hydrology and hydraulic analyses performed for the proposed development, the following points have been concluded:


- The proposed storm drain system will adequately capture and convey flows during the 25-year storm.
- The proposed underground chambers will provide sufficient storage capacity for the 25-year storm.
- The total outflow from the site does not exceed 85% of the pre-development flows from the 25-year storm.

### 5.0 REFERENCES

1. Los Angeles County Department of Public Works Hydrology Manual, January 2006.
2. Los Angeles County Flood Control Design Manual, 1982.
3. City of Palmdale Contents of Preliminary Hydrology and Hydraulic Study.
4. City of Palmdale Master Plan of Drainage Update, August 1996.
5. City of Palmdale Master Plan of Drainage Anaverde Watershed Facility Map.

## **Figure 1 Site Vicinity Map**






LA County | County of Los Angeles, Bureau of Land Management, Esri, HERE, Garmin, INCREMENT P, USGS, METI/NASA, ...

<p>LANGAN Langan Engineering and Environmental Services, Inc. 11801 Pierce Street Riverside, CA 92505 T: 951.710.3000      www.langan.com</p>	<p>Project</p> <p><b>PALMDALE INDUSTRIAL PARK 8TH ST</b></p> <p>CITY OF PALMDALE LOS ANGELES COUNTY CALIFORNIA</p>	<p>Drawing Title</p> <p><b>SITE VICINITY MAP</b></p>	<p>Project No.</p> <p><b>722010601</b></p>	<p>FIGURE</p> <p><b>1</b></p>
	<p>Date</p> <p><b>03/24/2023</b></p> <p>Drawn By</p> <p><b>DB</b></p> <p>Checked By</p> <p><b>KKMG</b></p>			

## **Figure 2 Proposed Site Plan**



Date	Description	No.
Revisions		

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_  
 MICHAEL GOLIAS  
 PROFESSIONAL ENGINEER CA LICENSE NO. C91029

**LANGAN**  
 Langan Engineering and  
 Environmental Services, Inc.  
 11801 Pierce Street  
 Riverside, CA 92505  
 T: 951.710.3000 www.langan.com


Project  
**PALMDALE  
 INDUSTRIAL PARK  
 8TH ST**  
 CITY OF PALMDALE  
 LOS ANGELES COUNTY CALIFORNIA

Drawing Title  
**PROPOSED  
 SITE PLAN**

Project No.  
**722010601**  
 Date  
**03/28/2023**  
 Drawn By  
**DB**  
 Checked By  
**KK/MG**

Figure No.  
**2**

## **Figure 3 Pre-Development Drainage Map**



**LEGEND**

- PROJECT DRAINAGE BOUNDARY
- - - - SUB-AREA BOUNDARY
- - - - FLOW PATH
- X SUB-DRAINAGE AREA ID
- X / X SUB-DRAINAGE AREA IDENTIFIER
- XXX SUB-DRAINAGE SURFACE AREA (ACRE)
- XXX SURFACE FLOW NODE
- APPROXIMATE EXISTING GROUND ELEVATION

**PROJECT SUMMARY**

SITE AREA (GROSS):	18.11 ACRES
SITE AREA (NET):	17.90 ACRES
IMPERVIOUS COVERAGE:	0% (PRE-DEVELOPMENT)
SOIL GROUP:	134
ISOHYETALS:	3.5-INCHES (50-YEAR, 24-HOUR)
FREQUENCY:	25-YEAR (FOR STORM DRAIN ANALYSIS)
METHOD:	LOS ANGELES COUNTY HYDROLOGY MANUAL

- GENERAL NOTES:**
- SEE PRELIMINARY LID REPORT PREPARED BY LANGAN ENGINEERING FOR THE COMPLETE POST DEVELOPMENT LID CALCULATIONS.
  - CALCULATIONS WERE BASED ON THE REQUIREMENTS OF THE LOS ANGELES COUNTY LID MANUAL FOR THE 0.75-INCH, 24-HOUR RAINFALL DEPTH.
  - PROPOSED ON-SITE DRAINAGE SYSTEM LAYOUT IS PRELIMINARY.
  - ALL EXISTING ELEVATIONS ARE APPROXIMATE.

**ABBREVIATIONS:**

EG - EXISTING GRADE  
L - LENGTH OF FLOW



Date	Description	No.
Revisions		

SIGNATURE: MICHAEL GOLIAS  
PROFESSIONAL ENGINEER CA LICENSE NO. C91029

DATE: \_\_\_\_\_

**LANGAN**  
Langan Engineering and Environmental Services, Inc.  
11801 Pierce Street  
Riverside, CA 92505  
T: 951.710.3000  
www.langan.com


Project  
**PALMDALE INDUSTRIAL PARK 8TH ST**  
CITY OF PALMDALE  
LOS ANGELES COUNTY CALIFORNIA

Drawing Title  
**PRE-DEVELOPMENT DRAINAGE MAP**

Project No. <b>722010601</b>	Figure No. <b>3</b>
Date <b>03/28/2023</b>	
Drawn By <b>DB</b>	
Checked By <b>KK/MG</b>	

## **Figure 4**

# **Post-Development Drainage Map**



**LEGEND**

- PROJECT DRAINAGE BOUNDARY
- - - - SUB-AREA BOUNDARY
- - - -> FLOW PATH
- X SUB-DRAINAGE AREA ID
- X SUB-DRAINAGE AREA IDENTIFIER
- XXX SUB-DRAINAGE SURFACE AREA (ACRE)
- XXX SURFACE FLOW NODE
- 100.00 APPROXIMATE EXISTING GROUND ELEVATION

**PROJECT SUMMARY**

SITE AREA (GROSS): 18.11 ACRES  
 SITE AREA (NET): 17.90 ACRES

IMPERVIOUS COVERAGE: 80% (POST-DEVELOPMENT)

SOIL GROUP: 134

ISOHYETALS: 3.5-INCHES (50-YEAR, 24-HOUR)

FREQUENCY: 25-YEAR (FOR STORM DRAIN ANALYSIS)


METHOD: LOS ANGELES COUNTY HYDROLOGY MANUAL

**GENERAL NOTES:**

- SEE PRELIMINARY HYDROLOGY REPORT PREPARED BY LANGAN ENGINEERING FOR THE COMPLETE POST DEVELOPMENT HYDROLOGY CALCULATIONS.
- CALCULATIONS WERE BASED ON THE CITY AND COUNTY REQUIREMENTS FOR THE 25-YEAR STORM.
- PROPOSED ON-SITE DRAINAGE SYSTEM LAYOUT IS PRELIMINARY.
- ALL EXISTING ELEVATIONS ARE APPROXIMATE.

**ABBREVIATIONS:**

EG - EXISTING GRADE  
 FS - FINISHED SURFACE  
 L - LENGTH OF FLOW



Date	Description	No.
Revisions		

Signature	Date
-----------	------

**LANGAN**  
 Langan Engineering and Environmental Services, Inc.  
 11801 Pierce Street  
 Riverside, CA 92505  
 T: 951.710.3000  
 www.langan.com

Project  
**PALMDALE INDUSTRIAL PARK**  
**8TH ST**  
 CITY OF PALMDALE  
 LOS ANGELES COUNTY CALIFORNIA

Drawing Title  
**POST-DEVELOPMENT DRAINAGE MAP**

Project No. <b>722010601</b>	Figure No. <b>4</b>
Date <b>03/28/2023</b>	
Drawn By <b>DB</b>	
Checked By <b>KK/MG</b>	

## **Appendix A**

### **LA County Hydrology Map – 50-Year, 24-Hour Storm**



# LA County Hydrology Map

636 E Rancho Vista Blvd X




About



Legend



Layers



## Layers

- Hydrology GIS
- 50yr Two Tenths (Rainfall)
- DPA Zones
- Soils 2004
- Final 85th Percentile, 24-hr Rainfall
- 1-year, 1-hour Rainfall Intensity
- Final 95th Percentile, 24-hr Rainfall
- LA County Parcels

## **Appendix B**

### **LA County Hydrology Map – 2004 Soils Map**

# LA County Hydrology Map



About




Legend



Layers

## Layers

- Hydrology GIS
  - 50yr Two Tenths (Rainfall)
  - DPA Zones
  - Soils 2004
  - Final 85th Percentile, 24-hr Rainfall
  - 1-year, 1-hour Rainfall Intensity
  - Final 95th Percentile, 24-hr Rainfall
- LA County Parcels



Topographic

SITE LOCATION  
SOIL 134


## **Appendix C**

### **FEMA Flood Insurance Map**

# National Flood Hazard Layer FIRMette



118°7'25"W 34°36'10"N



## Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

- |                                    |  |   |
|------------------------------------|--|---|
| <b>SPECIAL FLOOD HAZARD AREAS</b>  |  | Without Base Flood Elevation (BFE)<br>Zone A, V, A99  |
|                                    |  | With BFE or Depth Zone AE, AO, AH, VE, AR   |
|                                    |  | Regulatory Floodway   |
| <b>OTHER AREAS OF FLOOD HAZARD</b> |  | 0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X |
|                                    |  | Future Conditions 1% Annual Chance Flood Hazard Zone X  |
|                                    |  | Area with Reduced Flood Risk due to Levee. See Notes. Zone X  |
|                                    |  | Area with Flood Risk due to Levee Zone D  |
| <b>OTHER AREAS</b>                 |  | NO SCREEN Area of Minimal Flood Hazard Zone X   |
|                                    |  | Effective LOMRs   |
|                                    |  | Area of Undetermined Flood Hazard Zone D  |
| <b>GENERAL STRUCTURES</b>          |  | Channel, Culvert, or Storm Sewer  |
|                                    |  | Levee, Dike, or Floodwall   |
| <b>OTHER FEATURES</b>              |  | 20.2 Cross Sections with 1% Annual Chance Water Surface Elevation   |
|                                    |  | 8 Coastal Transect  |
|                                    |  | Base Flood Elevation Line (BFE)   |
|                                    |  | Limit of Study  |
|                                    |  | Jurisdiction Boundary   |
|                                    |  | Coastal Transect Baseline   |
|                                    |  | Profile Baseline  |
|                                    |  | Hydrographic Feature  |
| <b>MAP PANELS</b>                  |  | Digital Data Available  |
|                                    |  | No Digital Data Available   |
|                                    |  | Unmapped  |
- The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 12/20/2022 at 6:33 PM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

0 250 500 1,000 1,500 2,000 Feet  
Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020  
118°6'47"W 34°35'40"N

 Langan Engineering and Environmental Services, Inc. 11801 Pierce Street Riverside, CA 92505 T: 951.710.3000 www.langan.com	Project	Drawing Title	Project No.	Figure No.	
	PALMDALE INDUSTRIAL PARK 8TH ST CITY OF PALMDALE LOS ANGELES COUNTY CALIFORNIA	FEMA FLOOD INSURANCE RATE MAP	722010601	D	
			Date		03/28/2023
			Drawn By		DB
			Checked By	KK/MG	

**Appendix D**  
**Pre-Development HydroCalc Calculations**  
**0.75-Inch, 24-Hour, 2-Year, 10-Year, 25-Year and 50-Year**

## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Pre-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A
Area (ac)	5.98
Flow Path Length (ft)	1062.56
Flow Path Slope (vft/hft)	0.0082
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.0781
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	205.0
Clear Peak Flow Rate (cfs)	0.0505
Burned Peak Flow Rate (cfs)	0.0505
24-Hr Clear Runoff Volume (ac-ft)	0.0401
24-Hr Clear Runoff Volume (cu-ft)	1744.8233













## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Pre-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	F
Area (ac)	1.37
Flow Path Length (ft)	786.5
Flow Path Slope (vft/hft)	0.0109
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.0878
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	160.0
Clear Peak Flow Rate (cfs)	0.013
Burned Peak Flow Rate (cfs)	0.013
24-Hr Clear Runoff Volume (ac-ft)	0.0092
24-Hr Clear Runoff Volume (cu-ft)	399.6345



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A
Area (ac)	5.98
Flow Path Length (ft)	1062.56
Flow Path Slope (vft/hft)	0.0082
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.2248
Burned Peak Flow Rate (cfs)	0.2248
24-Hr Clear Runoff Volume (ac-ft)	0.0723
24-Hr Clear Runoff Volume (cu-ft)	3149.2812



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B
Area (ac)	4.63
Flow Path Length (ft)	668.43
Flow Path Slope (vft/hft)	0.0141
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1741
Burned Peak Flow Rate (cfs)	0.1741
24-Hr Clear Runoff Volume (ac-ft)	0.056
24-Hr Clear Runoff Volume (cu-ft)	2438.323



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	3.03
Flow Path Length (ft)	760.03
Flow Path Slope (vft/hft)	0.0142
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1139
Burned Peak Flow Rate (cfs)	0.1139
24-Hr Clear Runoff Volume (ac-ft)	0.0366
24-Hr Clear Runoff Volume (cu-ft)	1595.706



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.43
Flow Path Length (ft)	1105.54
Flow Path Slope (vft/hft)	0.0091
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.0538
Burned Peak Flow Rate (cfs)	0.0538
24-Hr Clear Runoff Volume (ac-ft)	0.0173
24-Hr Clear Runoff Volume (cu-ft)	753.089





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	E
Area (ac)	1.67
Flow Path Length (ft)	1059.41
Flow Path Slope (vft/hft)	0.0009
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.0628
Burned Peak Flow Rate (cfs)	0.0628
24-Hr Clear Runoff Volume (ac-ft)	0.0202
24-Hr Clear Runoff Volume (cu-ft)	879.4815



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 2-Y  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	F
Area (ac)	1.37
Flow Path Length (ft)	786.5
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.0515
Burned Peak Flow Rate (cfs)	0.0515
24-Hr Clear Runoff Volume (ac-ft)	0.0166
24-Hr Clear Runoff Volume (cu-ft)	721.4908



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A
Area (ac)	5.98
Flow Path Length (ft)	1062.56
Flow Path Slope (vft/hft)	0.0082
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

## Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.4148
Burned Peak Flow Rate (cfs)	0.4148
24-Hr Clear Runoff Volume (ac-ft)	0.1334
24-Hr Clear Runoff Volume (cu-ft)	5810.3017



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B
Area (ac)	4.63
Flow Path Length (ft)	668.43
Flow Path Slope (vft/hft)	0.0141
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.3212
Burned Peak Flow Rate (cfs)	0.3212
24-Hr Clear Runoff Volume (ac-ft)	0.1033
24-Hr Clear Runoff Volume (cu-ft)	4498.6115



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	3.03
Flow Path Length (ft)	760.03
Flow Path Slope (vft/hft)	0.0142
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.2102
Burned Peak Flow Rate (cfs)	0.2102
24-Hr Clear Runoff Volume (ac-ft)	0.0676
24-Hr Clear Runoff Volume (cu-ft)	2944.0157



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.43
Flow Path Length (ft)	1105.54
Flow Path Slope (vft/hft)	0.0091
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.0992
Burned Peak Flow Rate (cfs)	0.0992
24-Hr Clear Runoff Volume (ac-ft)	0.0319
24-Hr Clear Runoff Volume (cu-ft)	1389.42



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	E
Area (ac)	1.67
Flow Path Length (ft)	1059.41
Flow Path Slope (vft/hft)	0.0009
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1158
Burned Peak Flow Rate (cfs)	0.1158
24-Hr Clear Runoff Volume (ac-ft)	0.0372
24-Hr Clear Runoff Volume (cu-ft)	1622.6093



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 10-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	F
Area (ac)	1.37
Flow Path Length (ft)	786.5
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.095
Burned Peak Flow Rate (cfs)	0.095
24-Hr Clear Runoff Volume (ac-ft)	0.0306
24-Hr Clear Runoff Volume (cu-ft)	1331.1226





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A
Area (ac)	5.98
Flow Path Length (ft)	1062.56
Flow Path Slope (vft/hft)	0.0082
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.5101
Burned Peak Flow Rate (cfs)	0.5101
24-Hr Clear Runoff Volume (ac-ft)	0.164
24-Hr Clear Runoff Volume (cu-ft)	7144.8808



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B
Area (ac)	4.63
Flow Path Length (ft)	668.43
Flow Path Slope (vft/hft)	0.0141
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.3949
Burned Peak Flow Rate (cfs)	0.3949
24-Hr Clear Runoff Volume (ac-ft)	0.127
24-Hr Clear Runoff Volume (cu-ft)	5531.906



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	3.03
Flow Path Length (ft)	760.03
Flow Path Slope (vft/hft)	0.0142
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.2585
Burned Peak Flow Rate (cfs)	0.2585
24-Hr Clear Runoff Volume (ac-ft)	0.0831
24-Hr Clear Runoff Volume (cu-ft)	3620.2322



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.43
Flow Path Length (ft)	1059.41
Flow Path Slope (vft/hft)	0.0091
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.122
Burned Peak Flow Rate (cfs)	0.122
24-Hr Clear Runoff Volume (ac-ft)	0.0392
24-Hr Clear Runoff Volume (cu-ft)	1708.5584



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	E
Area (ac)	1.67
Flow Path Length (ft)	1059.41
Flow Path Slope (vft/hft)	0.0009
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1425
Burned Peak Flow Rate (cfs)	0.1425
24-Hr Clear Runoff Volume (ac-ft)	0.0458
24-Hr Clear Runoff Volume (cu-ft)	1995.3095



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 25-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	F
Area (ac)	1.37
Flow Path Length (ft)	786.5
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1169
Burned Peak Flow Rate (cfs)	0.1169
24-Hr Clear Runoff Volume (ac-ft)	0.0376
24-Hr Clear Runoff Volume (cu-ft)	1636.8707



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A
Area (ac)	5.98
Flow Path Length (ft)	1062.56
Flow Path Slope (vft/hft)	0.0082
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.581
Burned Peak Flow Rate (cfs)	0.581
24-Hr Clear Runoff Volume (ac-ft)	0.1868
24-Hr Clear Runoff Volume (cu-ft)	8137.6774



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B
Area (ac)	4.63
Flow Path Length (ft)	668.43
Flow Path Slope (vft/hft)	0.0141
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.4498
Burned Peak Flow Rate (cfs)	0.4498
24-Hr Clear Runoff Volume (ac-ft)	0.1446
24-Hr Clear Runoff Volume (cu-ft)	6300.5763





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	3.03
Flow Path Length (ft)	760.03
Flow Path Slope (vft/hft)	0.0142
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.2944
Burned Peak Flow Rate (cfs)	0.2944
24-Hr Clear Runoff Volume (ac-ft)	0.0947
24-Hr Clear Runoff Volume (cu-ft)	4123.2713



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.43
Flow Path Length (ft)	1105.54
Flow Path Slope (vft/hft)	0.0091
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1389
Burned Peak Flow Rate (cfs)	0.1389
24-Hr Clear Runoff Volume (ac-ft)	0.0447
24-Hr Clear Runoff Volume (cu-ft)	1945.9663



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	E
Area (ac)	1.67
Flow Path Length (ft)	1059.41
Flow Path Slope (vft/hft)	0.0009
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1622
Burned Peak Flow Rate (cfs)	0.1622
24-Hr Clear Runoff Volume (ac-ft)	0.0522
24-Hr Clear Runoff Volume (cu-ft)	2272.5621



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Pre-Development 50-  
Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	F
Area (ac)	1.37
Flow Path Length (ft)	786.5
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

## Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1331
Burned Peak Flow Rate (cfs)	0.1331
24-Hr Clear Runoff Volume (ac-ft)	0.0428
24-Hr Clear Runoff Volume (cu-ft)	1864.3174



**Appendix E**  
**Post-Development HydroCalc Calculations**  
**0.75-Inch, 24-Hour, 2-Year, 10-Year, 25-Year and 50-Year**



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A2
Area (ac)	0.89
Flow Path Length (ft)	293.67
Flow Path Slope (vft/hft)	0.0168
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.84
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.2279
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.772
Time of Concentration (min)	21.0
Clear Peak Flow Rate (cfs)	0.1566
Burned Peak Flow Rate (cfs)	0.1566
24-Hr Clear Runoff Volume (ac-ft)	0.0426
24-Hr Clear Runoff Volume (cu-ft)	1855.1264



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Develop  
Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A3
Area (ac)	0.37
Flow Path Length (ft)	150.86
Flow Path Slope (vft/hft)	0.0107
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.51
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

## Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.2389
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.508
Time of Concentration (min)	19.0
Clear Peak Flow Rate (cfs)	0.0449
Burned Peak Flow Rate (cfs)	0.0449
24-Hr Clear Runoff Volume (ac-ft)	0.0117
24-Hr Clear Runoff Volume (cu-ft)	507.4943







## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B1
Area (ac)	1.2
Flow Path Length (ft)	787.18
Flow Path Slope (vft/hft)	0.0075
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.93
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.1646
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.844
Time of Concentration (min)	42.0
Clear Peak Flow Rate (cfs)	0.1667
Burned Peak Flow Rate (cfs)	0.1667
24-Hr Clear Runoff Volume (ac-ft)	0.0628
24-Hr Clear Runoff Volume (cu-ft)	2734.622



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B2
Area (ac)	0.18
Flow Path Length (ft)	170.1
Flow Path Slope (vft/hft)	0.0109
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.98
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.2758
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.884
Time of Concentration (min)	14.0
Clear Peak Flow Rate (cfs)	0.0439
Burned Peak Flow Rate (cfs)	0.0439
24-Hr Clear Runoff Volume (ac-ft)	0.0099
24-Hr Clear Runoff Volume (cu-ft)	429.6251



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B3
Area (ac)	3.81
Flow Path Length (ft)	849.93
Flow Path Slope (vft/hft)	0.0075
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.1646
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	42.0
Clear Peak Flow Rate (cfs)	0.5643
Burned Peak Flow Rate (cfs)	0.5643
24-Hr Clear Runoff Volume (ac-ft)	0.2125
24-Hr Clear Runoff Volume (cu-ft)	9258.51



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	1.58
Flow Path Length (ft)	881.01
Flow Path Slope (vft/hft)	0.0068
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.0814
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	188.0
Clear Peak Flow Rate (cfs)	0.0139
Burned Peak Flow Rate (cfs)	0.0139
24-Hr Clear Runoff Volume (ac-ft)	0.0106
24-Hr Clear Runoff Volume (cu-ft)	460.9596



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/2023-07-27/2023-07-27 10:00 AM/01-Hydrograph (PALMDALE INDUSTRIAL PARK: D).htm  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.02
Flow Path Length (ft)	181.13
Flow Path Slope (vft/hft)	0.0136
0.75-inch Rainfall Depth (in)	0.75
Percent Impervious	0.14
Soil Type	134
Design Storm Frequency	0.75 inch storm
Fire Factor	0
LID	True

### Output Results

Modeled (0.75 inch storm) Rainfall Depth (in)	0.75
Peak Intensity (in/hr)	0.1725
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.212
Time of Concentration (min)	38.0
Clear Peak Flow Rate (cfs)	0.0373
Burned Peak Flow Rate (cfs)	0.0373
24-Hr Clear Runoff Volume (ac-ft)	0.0134
24-Hr Clear Runoff Volume (cu-ft)	583.8588





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A2
Area (ac)	0.89
Flow Path Length (ft)	293.67
Flow Path Slope (vft/hft)	0.0168
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.84
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.4981
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.772
Time of Concentration (min)	14.0
Clear Peak Flow Rate (cfs)	0.3422
Burned Peak Flow Rate (cfs)	0.3422
24-Hr Clear Runoff Volume (ac-ft)	0.0769
24-Hr Clear Runoff Volume (cu-ft)	3350.3478





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A3
Area (ac)	0.37
Flow Path Length (ft)	150.86
Flow Path Slope (vft/hft)	0.0107
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.51
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.5158
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.508
Time of Concentration (min)	13.0
Clear Peak Flow Rate (cfs)	0.0969
Burned Peak Flow Rate (cfs)	0.0969
24-Hr Clear Runoff Volume (ac-ft)	0.021
24-Hr Clear Runoff Volume (cu-ft)	916.5325



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A4
Area (ac)	4.93
Flow Path Length (ft)	857.05
Flow Path Slope (vft/hft)	0.005
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	1.5447
Burned Peak Flow Rate (cfs)	1.5447
24-Hr Clear Runoff Volume (ac-ft)	0.4967
24-Hr Clear Runoff Volume (cu-ft)	21635.9478



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B1
Area (ac)	1.2
Flow Path Length (ft)	787.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.93
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3596
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.844
Time of Concentration (min)	28.0
Clear Peak Flow Rate (cfs)	0.3642
Burned Peak Flow Rate (cfs)	0.3642
24-Hr Clear Runoff Volume (ac-ft)	0.1134
24-Hr Clear Runoff Volume (cu-ft)	4938.6647



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B2
Area (ac)	0.18
Flow Path Length (ft)	170.1
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.98
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.6131
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.884
Time of Concentration (min)	9.0
Clear Peak Flow Rate (cfs)	0.0976
Burned Peak Flow Rate (cfs)	0.0976
24-Hr Clear Runoff Volume (ac-ft)	0.0178
24-Hr Clear Runoff Volume (cu-ft)	775.9017





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	1.58
Flow Path Length (ft)	881.01
Flow Path Slope (vft/hft)	0.0068
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3481
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.0594
Burned Peak Flow Rate (cfs)	0.0594
24-Hr Clear Runoff Volume (ac-ft)	0.0191
24-Hr Clear Runoff Volume (cu-ft)	832.0843



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 2-  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.02
Flow Path Length (ft)	181.13
Flow Path Slope (vft/hft)	0.0136
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.14
Soil Type	134
Design Storm Frequency	2-yr
Fire Factor	0
LID	False

### Output Results

Modeled (2-yr) Rainfall Depth (in)	1.3545
Peak Intensity (in/hr)	0.3793
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.212
Time of Concentration (min)	25.0
Clear Peak Flow Rate (cfs)	0.082
Burned Peak Flow Rate (cfs)	0.082
24-Hr Clear Runoff Volume (ac-ft)	0.0242
24-Hr Clear Runoff Volume (cu-ft)	1054.4379



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A1
Area (ac)	4.13
Flow Path Length (ft)	1226.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.83
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.687
Undeveloped Runoff Coefficient ( $C_u$ )	0.1
Developed Runoff Coefficient ( $C_d$ )	0.764
Time of Concentration (min)	26.0
Clear Peak Flow Rate (cfs)	2.1677
Burned Peak Flow Rate (cfs)	2.1677
24-Hr Clear Runoff Volume (ac-ft)	0.6517
24-Hr Clear Runoff Volume (cu-ft)	28386.765





# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A2
Area (ac)	0.89
Flow Path Length (ft)	293.67
Flow Path Slope (vft/hft)	0.0168
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.84
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

## Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	1.1311
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.772
Time of Concentration (min)	9.0
Clear Peak Flow Rate (cfs)	0.7771
Burned Peak Flow Rate (cfs)	0.7771
24-Hr Clear Runoff Volume (ac-ft)	0.1419
24-Hr Clear Runoff Volume (cu-ft)	6181.2528



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A3
Area (ac)	0.37
Flow Path Length (ft)	150.86
Flow Path Slope (vft/hft)	0.0107
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.51
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	1.1955
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.508
Time of Concentration (min)	8.0
Clear Peak Flow Rate (cfs)	0.2247
Burned Peak Flow Rate (cfs)	0.2247
24-Hr Clear Runoff Volume (ac-ft)	0.0388
24-Hr Clear Runoff Volume (cu-ft)	1690.9647



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A4
Area (ac)	4.93
Flow Path Length (ft)	857.05
Flow Path Slope (vft/hft)	0.005
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.7771
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	20.0
Clear Peak Flow Rate (cfs)	3.4482
Burned Peak Flow Rate (cfs)	3.4482
24-Hr Clear Runoff Volume (ac-ft)	0.9164
24-Hr Clear Runoff Volume (cu-ft)	39917.2292



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B1
Area (ac)	1.2
Flow Path Length (ft)	787.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.93
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.8166
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.844
Time of Concentration (min)	18.0
Clear Peak Flow Rate (cfs)	0.827
Burned Peak Flow Rate (cfs)	0.827
24-Hr Clear Runoff Volume (ac-ft)	0.2092
24-Hr Clear Runoff Volume (cu-ft)	9111.5913



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B2
Area (ac)	0.18
Flow Path Length (ft)	170.1
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.98
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	1.3685
Undeveloped Runoff Coefficient (Cu)	0.1505
Developed Runoff Coefficient (Cd)	0.885
Time of Concentration (min)	6.0
Clear Peak Flow Rate (cfs)	0.218
Burned Peak Flow Rate (cfs)	0.218
24-Hr Clear Runoff Volume (ac-ft)	0.0329
24-Hr Clear Runoff Volume (cu-ft)	1431.55



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B3
Area (ac)	3.81
Flow Path Length (ft)	849.93
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

## Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.8166
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	18.0
Clear Peak Flow Rate (cfs)	2.8001
Burned Peak Flow Rate (cfs)	2.8001
24-Hr Clear Runoff Volume (ac-ft)	0.7082
24-Hr Clear Runoff Volume (cu-ft)	30848.7821



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	1.58
Flow Path Length (ft)	881.01
Flow Path Slope (vft/hft)	0.0068
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.6423
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1096
Burned Peak Flow Rate (cfs)	0.1096
24-Hr Clear Runoff Volume (ac-ft)	0.0352
24-Hr Clear Runoff Volume (cu-ft)	1535.1633



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 10  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.02
Flow Path Length (ft)	181.13
Flow Path Slope (vft/hft)	0.0136
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.14
Soil Type	134
Design Storm Frequency	10-yr
Fire Factor	0
LID	False

### Output Results

Modeled (10-yr) Rainfall Depth (in)	2.499
Peak Intensity (in/hr)	0.8388
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.212
Time of Concentration (min)	17.0
Clear Peak Flow Rate (cfs)	0.1814
Burned Peak Flow Rate (cfs)	0.1814
24-Hr Clear Runoff Volume (ac-ft)	0.0447
24-Hr Clear Runoff Volume (cu-ft)	1945.3886





# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A1
Area (ac)	4.13
Flow Path Length (ft)	1226.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.83
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

## Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.8949
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.764
Time of Concentration (min)	23.0
Clear Peak Flow Rate (cfs)	2.8237
Burned Peak Flow Rate (cfs)	2.8237
24-Hr Clear Runoff Volume (ac-ft)	0.8014
24-Hr Clear Runoff Volume (cu-ft)	34906.9086



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A2
Area (ac)	0.89
Flow Path Length (ft)	293.67
Flow Path Slope (vft/hft)	0.0168
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.84
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.47
Undeveloped Runoff Coefficient (Cu)	0.1809
Developed Runoff Coefficient (Cd)	0.785
Time of Concentration (min)	8.0
Clear Peak Flow Rate (cfs)	1.027
Burned Peak Flow Rate (cfs)	1.027
24-Hr Clear Runoff Volume (ac-ft)	0.1746
24-Hr Clear Runoff Volume (cu-ft)	7605.504



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A3
Area (ac)	0.37
Flow Path Length (ft)	150.86
Flow Path Slope (vft/hft)	0.0107
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.51
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.5653
Undeveloped Runoff Coefficient (Cu)	0.2095
Developed Runoff Coefficient (Cd)	0.5616
Time of Concentration (min)	7.0
Clear Peak Flow Rate (cfs)	0.3253
Burned Peak Flow Rate (cfs)	0.3253
24-Hr Clear Runoff Volume (ac-ft)	0.0479
24-Hr Clear Runoff Volume (cu-ft)	2087.1887





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B1
Area (ac)	1.2
Flow Path Length (ft)	787.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.93
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.0613
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.844
Time of Concentration (min)	16.0
Clear Peak Flow Rate (cfs)	1.0749
Burned Peak Flow Rate (cfs)	1.0749
24-Hr Clear Runoff Volume (ac-ft)	0.2572
24-Hr Clear Runoff Volume (cu-ft)	11204.4401



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B2
Area (ac)	0.18
Flow Path Length (ft)	170.1
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.98
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.8334
Undeveloped Runoff Coefficient (Cu)	0.2793
Developed Runoff Coefficient (Cd)	0.8876
Time of Concentration (min)	5.0
Clear Peak Flow Rate (cfs)	0.2929
Burned Peak Flow Rate (cfs)	0.2929
24-Hr Clear Runoff Volume (ac-ft)	0.0404
24-Hr Clear Runoff Volume (cu-ft)	1760.5677



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B3
Area (ac)	3.81
Flow Path Length (ft)	849.93
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.0613
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	16.0
Clear Peak Flow Rate (cfs)	3.6393
Burned Peak Flow Rate (cfs)	3.6393
24-Hr Clear Runoff Volume (ac-ft)	0.8709
24-Hr Clear Runoff Volume (cu-ft)	37934.464



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	1.58
Flow Path Length (ft)	881.01
Flow Path Slope (vft/hft)	0.0068
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

### Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	0.7898
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1348
Burned Peak Flow Rate (cfs)	0.1348
24-Hr Clear Runoff Volume (ac-ft)	0.0433
24-Hr Clear Runoff Volume (cu-ft)	1887.7779





# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 25  
Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.02
Flow Path Length (ft)	181.13
Flow Path Slope (vft/hft)	0.0136
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.14
Soil Type	134
Design Storm Frequency	25-yr
Fire Factor	0
LID	False

## Output Results

Modeled (25-yr) Rainfall Depth (in)	3.073
Peak Intensity (in/hr)	1.1301
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.212
Time of Concentration (min)	14.0
Clear Peak Flow Rate (cfs)	0.2444
Burned Peak Flow Rate (cfs)	0.2444
24-Hr Clear Runoff Volume (ac-ft)	0.0549
24-Hr Clear Runoff Volume (cu-ft)	2392.2258



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A1
Area (ac)	4.13
Flow Path Length (ft)	1226.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.83
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

## Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.0638
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.764
Time of Concentration (min)	21.0
Clear Peak Flow Rate (cfs)	3.3565
Burned Peak Flow Rate (cfs)	3.3565
24-Hr Clear Runoff Volume (ac-ft)	0.9127
24-Hr Clear Runoff Volume (cu-ft)	39757.2544



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A2
Area (ac)	0.89
Flow Path Length (ft)	293.67
Flow Path Slope (vft/hft)	0.0168
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.84
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.7828
Undeveloped Runoff Coefficient (Cu)	0.2705
Developed Runoff Coefficient (Cd)	0.7993
Time of Concentration (min)	7.0
Clear Peak Flow Rate (cfs)	1.2682
Burned Peak Flow Rate (cfs)	1.2682
24-Hr Clear Runoff Volume (ac-ft)	0.199
24-Hr Clear Runoff Volume (cu-ft)	8669.7655



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A3
Area (ac)	0.37
Flow Path Length (ft)	150.86
Flow Path Slope (vft/hft)	0.0107
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.51
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.9167
Undeveloped Runoff Coefficient (Cu)	0.2938
Developed Runoff Coefficient (Cd)	0.6029
Time of Concentration (min)	6.0
Clear Peak Flow Rate (cfs)	0.4276
Burned Peak Flow Rate (cfs)	0.4276
24-Hr Clear Runoff Volume (ac-ft)	0.0548
24-Hr Clear Runoff Volume (cu-ft)	2386.431



# Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development/Version: HydroCalc 1.0.3

## Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	A4
Area (ac)	4.93
Flow Path Length (ft)	857.05
Flow Path Slope (vft/hft)	0.005
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

## Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.2088
Undeveloped Runoff Coefficient (Cu)	0.1026
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	16.0
Clear Peak Flow Rate (cfs)	5.3634
Burned Peak Flow Rate (cfs)	5.3634
24-Hr Clear Runoff Volume (ac-ft)	1.2834
24-Hr Clear Runoff Volume (cu-ft)	55906.3809



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B1
Area (ac)	1.2
Flow Path Length (ft)	787.18
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.93
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.246
Undeveloped Runoff Coefficient (Cu)	0.1138
Developed Runoff Coefficient (Cd)	0.845
Time of Concentration (min)	15.0
Clear Peak Flow Rate (cfs)	1.2634
Burned Peak Flow Rate (cfs)	1.2634
24-Hr Clear Runoff Volume (ac-ft)	0.293
24-Hr Clear Runoff Volume (cu-ft)	12761.6808



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B2
Area (ac)	0.18
Flow Path Length (ft)	170.1
Flow Path Slope (vft/hft)	0.0109
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.98
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	2.0882
Undeveloped Runoff Coefficient (Cu)	0.3235
Developed Runoff Coefficient (Cd)	0.8885
Time of Concentration (min)	5.0
Clear Peak Flow Rate (cfs)	0.334
Burned Peak Flow Rate (cfs)	0.334
24-Hr Clear Runoff Volume (ac-ft)	0.046
24-Hr Clear Runoff Volume (cu-ft)	2005.3142



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits & Figures/Post-Development  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	B3
Area (ac)	3.81
Flow Path Length (ft)	849.93
Flow Path Slope (vft/hft)	0.0075
50-yr Rainfall Depth (in)	3.5
Percent Impervious	1.0
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.246
Undeveloped Runoff Coefficient (Cu)	0.1138
Developed Runoff Coefficient (Cd)	0.9
Time of Concentration (min)	15.0
Clear Peak Flow Rate (cfs)	4.2726
Burned Peak Flow Rate (cfs)	4.2726
24-Hr Clear Runoff Volume (ac-ft)	0.9919
24-Hr Clear Runoff Volume (cu-ft)	43205.5228





## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	C
Area (ac)	1.58
Flow Path Length (ft)	881.01
Flow Path Slope (vft/hft)	0.0068
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.01
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	0.8996
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.108
Time of Concentration (min)	30.0
Clear Peak Flow Rate (cfs)	0.1535
Burned Peak Flow Rate (cfs)	0.1535
24-Hr Clear Runoff Volume (ac-ft)	0.0494
24-Hr Clear Runoff Volume (cu-ft)	2150.0887



## Peak Flow Hydrologic Analysis


File location: //langan.com/data/IEM/data6/722010601/Project Data/\_Discipline/Site Civil/Reports/Prelim Hydrology Report/Exhibits/Post-Development 50  
Version: HydroCalc 1.0.3

### Input Parameters

Project Name	PALMDALE INDUSTRIAL PARK
Subarea ID	D
Area (ac)	1.02
Flow Path Length (ft)	181.13
Flow Path Slope (vft/hft)	0.0136
50-yr Rainfall Depth (in)	3.5
Percent Impervious	0.14
Soil Type	134
Design Storm Frequency	50-yr
Fire Factor	0
LID	False

### Output Results

Modeled (50-yr) Rainfall Depth (in)	3.5
Peak Intensity (in/hr)	1.4416
Undeveloped Runoff Coefficient (Cu)	0.1724
Developed Runoff Coefficient (Cd)	0.2743
Time of Concentration (min)	11.0
Clear Peak Flow Rate (cfs)	0.4033
Burned Peak Flow Rate (cfs)	0.4033
24-Hr Clear Runoff Volume (ac-ft)	0.0633
24-Hr Clear Runoff Volume (cu-ft)	2756.7005



## **Appendix F**

# **INFILTRATION CHAMBER CALCULATIONS AND DETAILS**

# CHAMBER A

CHAMBER A STORAGE			
ELEVATION (FT)	STORAGE (CF)	CUMULATIVE STORAGE (CF)	DISCHARGE PER ELEVATION (CFS)
0.00	0	0	0
0.17	2,500	2,500	0
0.33	2,500	5,000	0
0.50	2,500	7,500	0
0.67	3,263	10,763	0
0.83	3,857	14,619	0
1.00	4,203	18,823	0
1.17	4,451	23,274	0
1.33	4,636	27,910	0.10
1.50	4,772	32,682	0.15
1.67	4,870	37,552	0.18
1.83	4,933	42,485	0.21
2.00	4,963	47,448	0.23
2.17	4,963	52,411	0.26
2.33	4,933	57,344	0.28
2.50	4,870	62,214	0.30
2.67	4,772	66,986	0.31
2.83	4,636	71,622	0.33
3.00	4,451	76,073	0.35
3.17	4,203	80,277	0.36
3.33	3,857	84,133	0.38
3.50	3,263	87,396	0.39
3.67	2,500	89,896	0.40
3.83	2,500	92,396	0.42
4.00	2,500	94,896	0.43

DRAWDOWN/OUTLET VOLUME CALCULATIONS	
DESIGN INFILTRATION RATE (IN/HR)	0.4
DRAWDOWN TIME (HR)	96
DRAWDOWN IN 96 HRS (FT)	1.6
CMP TOTAL FOOTPRINT (SF)	37,500
DRAWDOWN VOLUME IN 96 HR	120,000
VOLUME TO OUTLET (CF)	0
AVERAGE DISCHARGE PER ELEVATION (CFS)	0.30
AVERAGE DISCHARGE PER ELEVATION (CF/HR)	1,076
DESIGN OUTLET VOLUME (CF IN 24 HR)	25,816
OUTLET PIPE CENTROID ELEVATION	1.17
PIPE DIAMETER (IN)	3
PEAK OUTFLOW (CFS)	0.43

# CHAMBER B

CHAMBER B STORAGE			
ELEVATION (FT)	STORAGE (CF)	CUMULATIVE STORAGE (CF)	DISCHARGE PER ELEVATION (CFS)
0.00	0	0	0.00
0.17	571	571	0
0.33	571	1,142	0
0.50	571	1,714	0
0.67	678	2,391	0
0.83	764	3,155	0
1.00	818	3,973	0
1.17	860	4,834	0
1.33	896	5,729	0
1.50	926	6,655	0
1.67	952	7,607	0
1.83	975	8,583	0
2.00	996	9,579	0
2.17	1,015	10,594	0
2.33	1,031	11,625	0
2.50	1,046	12,672	0
2.67	1,060	13,732	0.07
2.83	1,072	14,803	0.10
3.00	1,082	15,886	0.13
3.17	1,092	16,978	0.14
3.33	1,100	18,078	0.16
3.50	1,107	19,185	0.18
3.67	1,113	20,298	0.19
3.83	1,118	21,416	0.20
4.00	1,122	22,538	0.22
4.17	1,125	23,663	0.23
4.33	1,127	24,790	0.24
4.50	1,128	25,918	0.25
4.67	1,128	27,046	0.26
4.83	1,127	28,173	0.27
5.00	1,125	29,297	0.28
5.17	1,122	30,419	0.29
5.33	1,118	31,538	0.30
5.50	1,113	32,651	0.31
5.67	1,107	33,758	0.32
5.83	1,100	34,858	0.32
6.00	1,092	35,950	0.33
6.17	1,082	37,032	0.34
6.33	1,072	38,104	0.35
6.50	1,060	39,164	0.35
6.67	1,046	40,210	0.36
6.83	1,031	41,242	0.37
7.00	1,015	42,257	0.38
7.17	996	43,253	0.38
7.33	975	44,228	0.39
7.50	952	45,180	0.40
7.67	926	46,106	0.40
7.83	896	47,002	0.41
8.00	860	47,862	0.42
8.17	818	48,680	0.42
8.33	764	49,444	0.43
8.50	678	50,122	0.43
8.67	571	50,693	0.44
8.83	571	51,264	0.45
9.00	571	51,836	0.45

DRAWDOWN/OUTLET VOLUME CALCULATIONS	
DESIGN INFILTRATION RATE (IN/HR)	0.2
DRAWDOWN TIME (HR)	96
DRAWDOWN IN 96 HRS (FT)	1.6
CMP TOTAL FOOTPRINT (SF)	8568
DRAWDOWN VOLUME IN 96 HR	13709
VOLUME TO OUTLET (CF)	38127
AVERAGE DISCHARGE PER ELEVATION (CFS)	0.31
AVERAGE DISCHARGE PER ELEVATION (CF/HR)	1104
DESIGN OUTLET VOLUME (CF IN 24 HR)	26497
OUTLET PIPE CENTROID ELEVATION	2.5
PIPE DIAMETER (IN)	3
PEAK OUTFLOW (CFS)	0.45

# PROJECT SUMMARY

## CALCULATION DETAILS

- LOADING = HS20/HS25
- APPROX. LINEAR FOOTAGE = 8,243 LF

## STORAGE SUMMARY


- STORAGE VOLUME REQUIRED = 93,685 CF
- PIPE STORAGE VOLUME = 58,266 CF
- BACKFILL STORAGE VOLUME = 36,693 CF
- TOTAL STORAGE PROVIDED = 94,960 CF

## PIPE DETAILS

- DIAMETER = 36"
- CORRUGATION = 2 2/3x1/2
- GAGE = 16
- COATING = ALT2
- WALL TYPE = PERFORATED
- BARREL SPACING = 18"

## BACKFILL DETAILS

- WIDTH AT ENDS = 12"
- ABOVE PIPE = 6"
- WIDTH AT SIDES = 12"
- BELOW PIPE = 6"



## NOTES


- ALL RISER AND STUB DIMENSIONS ARE TO CENTERLINE. ALL ELEVATIONS, DIMENSIONS, AND LOCATIONS OF RISERS AND INLETS, SHALL BE VERIFIED BY THE ENGINEER OF RECORD PRIOR TO RELEASING FOR FABRICATION.
- ALL FITTINGS AND REINFORCEMENT COMPLY WITH ASTM A998.
- ALL RISERS AND STUBS ARE 2 2/3" x 1/2" CORRUGATION AND 16 GAGE UNLESS OTHERWISE NOTED.
- RISERS TO BE FIELD TRIMMED TO GRADE.
- QUANTITY OF PIPE SHOWN DOES NOT PROVIDE EXTRA PIPE FOR CONNECTING THE SYSTEM TO EXISTING PIPE OR DRAINAGE STRUCTURES. OUR SYSTEM AS DETAILED PROVIDES NOMINAL INLET AND/OR OUTLET PIPE STUB FOR CONNECTION TO EXISTING DRAINAGE FACILITIES. IF ADDITIONAL PIPE IS NEEDED IT IS THE RESPONSIBILITY OF THE CONTRACTOR.
- BAND TYPE TO BE DETERMINED UPON FINAL DESIGN.
- THE PROJECT SUMMARY IS REFLECTIVE OF THE DYODS DESIGN, QUANTITIES ARE APPROX. AND SHOULD BE VERIFIED UPON FINAL DESIGN AND APPROVAL. FOR EXAMPLE, TOTAL EXCAVATION DOES NOT CONSIDER ALL VARIABLES SUCH AS SHORING AND ONLY ACCOUNTS FOR MATERIAL WITHIN THE ESTIMATED EXCAVATION FOOTPRINT.
- THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.

**ASSEMBLY**  
SCALE: 1" = 70'

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM


<small>The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.</small>		
<small>If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.</small>		
DATE	REVISION DESCRIPTION	BY


  
**ENGINEERED SOLUTIONS LLC**  
[www.ContechES.com](http://www.ContechES.com)  
 9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
 800-338-1122 513-645-7000 513-645-7993 FAX

  
**CMP DETENTION SYSTEMS**  
 CONTECH  
**DYODS**  
 DRAWING


DY029422 Palmdale Basins  
 Chamber A  
 Palmdale, CA  
 DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29422	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		<b>1</b>




Infiltration Systems - CMP Infiltration & CMP Perforated Drainage Pipe			
Material Location	Description	Material Designation	Designation
8	Rigid or Flexible Pavement (if applicable)		
7	Road Base (if applicable)		
A	Geotextile Layer	Non-Woven Geotextile CONTECH C-40 or C-45	Engineer Decision for consideration to prevent soil migration into varying soil types. Wrap the trench only.
6	Backfill	Infiltration pipe systems have a pipe perforation sized of 3/8" diameter. An open graded, free draining stone, with a particle size of 1/2" - 2 1/2" diameter is recommended. AASHTO M 145-A-1 or AASHTO M 43 - 3, 4	Material shall be worked into the pipe haunches by means of shovel-slicing, rodding, air-tamper, vibratory rod, or other effective methods. Compaction of all placed fill material is necessary and shall be considered adequate when no further yielding of the material is observed under the compactor, or under foot, and the Project Engineer or his representative is satisfied with the level of compaction*
3	Bedding Stone	Well graded granular bedding material w/maximum particle size of 3" AASHTO M43 - 3,357,4,467, 5, 56, 57	For soil aggregates larger than 3/8" a dedicated bedding layer is not required for CMP. Pipe may be placed on the trench bottom comprised of native suitable well graded & granular material. For Arch pipes it is recommended to be shaped to a relatively flat bottom or fine-grade the foundation to a slight v-shape. Soil aggregates less than 3/8" and unsuitable material should be over-excavated and re-placed with a 4"-6" layer of well graded & granular stone per the material designation.
A	Geotextile Layer	None	Contech does not recommend geotextiles be placed under the invert of infiltration systems due to the propensity for geotextiles to clog over time.


\* Note: The listed AASHTO designations are for gradation only. The stone must also be angular and clean.



TYPICAL MANWAY DETAIL



TYPICAL RISER DETAIL



TYPICAL SECTION VIEW


NOTE: IF SALTING AGENTS FOR SNOW AND ICE REMOVAL ARE USED ON OR NEAR THE PROJECT, AN HDPE MEMBRANE LINER IS RECOMMENDED WITH THE SYSTEM. THE IMPERMEABLE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM A CHANGE IN THE SURROUNDING ENVIRONMENT OVER A PERIOD OF TIME. PLEASE REFER TO THE CORRUGATED METAL PIPE DETENTION DESIGN GUIDE FOR ADDITIONAL INFORMATION.

- 1 MINIMUM WIDTH DEPENDS ON SITE CONDITIONS AND ENGINEERING JUDGEMENT.
- 2 PRIOR TO PLACING THE BEDDING, THE FOUNDATION MUST BE CONSTRUCTED TO A UNIFORM AND STABLE GRADE. IN THE EVENT THAT UNSUITABLE FOUNDATION MATERIALS ARE ENCOUNTERED DURING EXCAVATION, THEY SHALL BE REMOVED AND BROUGHT BACK TO THE GRADE WITH A FILL MATERIAL AS APPROVED BY THE ENGINEER.
- 5 HAUNCH ZONE MATERIAL SHALL BE PLACED AND UNIFORMLY COMPACTED WITHOUT SOFT SPOTS.


**BACKFILL**  
MATERIAL SHALL BE PLACED IN 8"-10" MAXIMUM LIFTS. INADEQUATE COMPACTION CAN LEAD TO EXCESSIVE DEFLECTIONS WITHIN THE SYSTEM AND SETTLEMENT OF THE SOILS OVER THE SYSTEM. BACKFILL SHALL BE PLACED SUCH THAT THERE IS NO MORE THAN A TWO-LIFT DIFFERENTIAL BETWEEN THE SIDES OF ANY PIPE IN THE SYSTEM AT ALL TIMES DURING THE BACKFILL PROCESS. BACKFILL SHALL BE ADVANCED ALONG THE LENGTH OF THE SYSTEM AT THE SAME RATE TO AVOID DIFFERENTIAL LOADING ON ANY PIPES IN THE SYSTEM.

EQUIPMENT USED TO PLACE AND COMPACT THE BACKFILL SHALL BE OF A SIZE AND TYPE SO AS NOT TO DISTORT, DAMAGE, OR DISPLACE THE PIPE. ATTENTION MUST BE GIVEN TO PROVIDING ADEQUATE MINIMUM COVER FOR SUCH EQUIPMENT. MAINTAIN BALANCED LOADING ON ALL PIPES IN THE SYSTEM DURING ALL SUCH OPERATIONS.


OTHER ALTERNATE BACKFILL MATERIAL MAY BE ALLOWED DEPENDING ON SITE SPECIFIC CONDITIONS. REFER TO TYPICAL BACKFILL DETAIL FOR MATERIAL REQUIRED.



OPEN AREA = 3.76 SQ IN/SQ FT



OPEN AREA = 4.16 SQ IN/SQ FT



OPEN AREA = 3.33 SQ IN/SQ FT

- NOTES:
- PERFORATIONS MEET AASHTO AND ASTM SPECIFICATIONS.
  - PERFORATION OPEN AREA PER SQUARE FOOT OF PIPE IS BASED ON THE NOMINAL DIAMETER AND LENGTH OF PIPE.
  - ALL DIMENSIONS ARE SUBJECT TO MANUFACTURING TOLERANCES.
  - ALL HOLES  $\varnothing$ 3/8".

TYPICAL PERFORATION DETAIL

SCALE: N.T.S.

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.


DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
DYODS  
DRAWING

DYO29422 Palmdale Basins  
Chamber A  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29422	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1



**CONSTRUCTION LOADS**

FOR TEMPORARY CONSTRUCTION VEHICLE LOADS, AN EXTRA AMOUNT OF COMPACTED COVER MAY BE REQUIRED OVER THE TOP OF THE PIPE. THE HEIGHT-OF-COVER SHALL MEET THE MINIMUM REQUIREMENTS SHOWN IN THE TABLE BELOW. THE USE OF HEAVY CONSTRUCTION EQUIPMENT NECESSITATES GREATER PROTECTION FOR THE PIPE THAN FINISHED GRADE COVER MINIMUMS FOR NORMAL HIGHWAY TRAFFIC.

PIPE SPAN, INCHES	AXLE LOADS (kips)			
	18-50	50-75	75-110	110-150
	MINIMUM COVER (FT)			
12-42	2.0	2.5	3.0	3.0
48-72	3.0	3.0	3.5	4.0
78-120	3.0	3.5	4.0	4.0
126-144	3.5	4.0	4.5	4.5

\*MINIMUM COVER MAY VARY, DEPENDING ON LOCAL CONDITIONS. THE CONTRACTOR MUST PROVIDE THE ADDITIONAL COVER REQUIRED TO AVOID DAMAGE TO THE PIPE. MINIMUM COVER IS MEASURED FROM THE TOP OF THE PIPE TO THE TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE.

**CONSTRUCTION LOADING DIAGRAM**

SCALE: N.T.S.

**SPECIFICATION FOR DESIGNED DETENTION SYSTEM:**

**SCOPE**

THIS SPECIFICATION COVERS THE MANUFACTURE AND INSTALLATION OF THE DESIGNED DETENTION SYSTEM DETAILED IN THE PROJECT PLANS.

**MATERIAL**

THE MATERIAL SHALL CONFORM TO THE APPLICABLE REQUIREMENTS LISTED BELOW:

ALUMINIZED TYPE 2 STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-274 OR ASTM A-92.

THE GALVANIZED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-218 OR ASTM A-929.

THE POLYMER COATED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-246 OR ASTM A-742.

THE ALUMINUM COILS SHALL CONFORM TO THE APPLICABLE OF AASHTO M-197 OR ASTM B-744.

**CONSTRUCTION LOADS**

CONSTRUCTION LOADS MAY BE HIGHER THAN FINAL LOADS. FOLLOW THE MANUFACTURER'S OR NCSIPA GUIDELINES.

**PIPE**

THE PIPE SHALL BE MANUFACTURED IN ACCORDANCE TO THE APPLICABLE REQUIREMENTS LISTED BELOW:

ALUMINIZED TYPE 2: AASHTO M-36 OR ASTM A-760

GALVANIZED: AASHTO M-36 OR ASTM A-760

POLYMER COATED: AASHTO M-245 OR ASTM A-762

ALUMINUM: AASHTO M-196 OR ASTM B-745


**APPLICABLE HANDLING AND ASSEMBLY**

SHALL BE IN ACCORDANCE WITH NCSP'S (NATIONAL CORRUGATED STEEL ASSOCIATION) FOR ALUMINIZED TYPE 2, GALVANIZED OR POLYMER COATED STEEL. SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS FOR ALUMINUM PIPE.


**INSTALLATION**

SHALL BE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SECTION 26, DIVISION II DIVISION II OR ASTM A-798 (FOR ALUMINIZED TYPE 2, GALVANIZED OR POLYMER COATED STEEL) OR ASTM B-788 (FOR ALUMINUM PIPE) AND IN CONFORMANCE WITH THE PROJECT PLANS AND SPECIFICATIONS. IF THERE ARE ANY INCONSISTENCIES OR CONFLICTS THE CONTRACTOR SHOULD DISCUSS AND RESOLVE WITH THE SITE ENGINEER.


IT IS ALWAYS THE RESPONSIBILITY OF THE CONTRACTOR TO FOLLOW OSHA GUIDELINES FOR SAFE PRACTICES.



**SECTION VIEW**



**ROUND OPTION PLAN VIEW**



**SQUARE OPTION PLAN VIEW**

**NOTES:**

- DESIGN IN ACCORDANCE WITH AASHTO, 17th EDITION.
- DESIGN LOAD HS25.
- EARTH COVER = 1' MAX.
- CONCRETE STRENGTH = 3,500 psi
- REINFORCING STEEL = ASTM A615, GRADE 60.
- PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.
- TRIM OPENING WITH DIAGONAL #4 BARS, EXTEND BARS A MINIMUM OF 12" BEYOND OPENING, BEND BARS AS REQUIRED TO MAINTAIN BAR COVER.
- PROTECTION SLAB AND ALL MATERIALS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.
- DETAIL DESIGN BY DELTA ENGINEERING, BINGHAMTON, NY.

**MANHOLE CAP DETAIL**

SCALE: N.T.S.

Ø CMP RISER	A	Ø B	REINFORCING	**BEARING PRESSURE (PSF)
24"	Ø 4' 4'X4'	26"	#5 @ 12" OCEW #5 @ 12" OCEW	2,410 1,780
30"	Ø 4'-6" 4'-6" X 4'-6"	32"	#5 @ 12" OCEW #5 @ 12" OCEW	2,120 1,530
36"	Ø 5' X 5'	38"	#5 @ 10" OCEW #5 @ 10" OCEW	1,890 1,350
42"	Ø 5'-6" 5'-6" X 5'-6"	44"	#5 @ 10" OCEW #5 @ 9" OCEW	1,720 1,210
48"	Ø 6' X 6'	50"	#5 @ 9" OCEW #5 @ 8" OCEW	1,600 1,100

\*\* ASSUMED SOIL BEARING CAPACITY

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

**NOTE:**  
THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
DYODS  
DRAWING

DY029422 Palmdale Basins  
Chamber A  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29422	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1




## CMP DETENTION INSTALLATION GUIDE

PROPER INSTALLATION OF A FLEXIBLE UNDERGROUND DETENTION SYSTEM WILL ENSURE LONG-TERM PERFORMANCE. THE CONFIGURATION OF THESE SYSTEMS OFTEN REQUIRES SPECIAL CONSTRUCTION PRACTICES THAT DIFFER FROM CONVENTIONAL FLEXIBLE PIPE CONSTRUCTION. CONTECH ENGINEERED SOLUTIONS STRONGLY SUGGESTS SCHEDULING A PRE-CONSTRUCTION MEETING WITH YOUR LOCAL SALES ENGINEER TO DETERMINE IF ADDITIONAL MEASURES, NOT COVERED IN THIS GUIDE, ARE APPROPRIATE FOR YOUR SITE.

## FOUNDATION

CONSTRUCT A FOUNDATION THAT CAN SUPPORT THE DESIGN LOADING APPLIED BY THE PIPE AND ADJACENT BACKFILL WEIGHT AS WELL AS MAINTAIN ITS INTEGRITY DURING CONSTRUCTION.

IF SOFT OR UNSUITABLE SOILS ARE ENCOUNTERED, REMOVE THE POOR SOILS DOWN TO A SUITABLE DEPTH AND THEN BUILD UP TO THE APPROPRIATE ELEVATION WITH A COMPETENT BACKFILL MATERIAL. THE STRUCTURAL FILL MATERIAL GRADATION SHOULD NOT ALLOW THE MIGRATION OF FINES, WHICH CAN CAUSE SETTLEMENT OF THE DETENTION SYSTEM OR PAVEMENT ABOVE. IF THE STRUCTURAL FILL MATERIAL IS NOT COMPATIBLE WITH THE UNDERLYING SOILS AN ENGINEERING FABRIC SHOULD BE USED AS A SEPARATOR. IN SOME CASES, USING A STIFF REINFORCING GEOGRID REDUCES OVER EXCAVATION AND REPLACEMENT FILL QUANTITIES.




GRADE THE FOUNDATION SUBGRADE TO A UNIFORM OR SLIGHTLY SLOPING GRADE. IF THE SUBGRADE IS CLAY OR RELATIVELY NON-POROUS AND THE CONSTRUCTION SEQUENCE WILL LAST FOR AN EXTENDED PERIOD OF TIME, IT IS BEST TO SLOPE THE GRADE TO ONE END OF THE SYSTEM. THIS WILL ALLOW EXCESS WATER TO DRAIN QUICKLY, PREVENTING SATURATION OF THE SUBGRADE.

## GEOMEMBRANE BARRIER

A SITE'S RESISTIVITY MAY CHANGE OVER TIME WHEN VARIOUS TYPES OF SALTING AGENTS ARE USED, SUCH AS ROAD SALTS FOR DEICING AGENTS. IF SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE, A GEOMEMBRANE BARRIER IS RECOMMENDED WITH THE SYSTEM. THE GEOMEMBRANE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM THE USE OF SUCH AGENTS INCLUDING PREMATURE CORROSION AND REDUCED ACTUAL SERVICE LIFE.


THE PROJECT'S ENGINEER OF RECORD IS TO EVALUATE WHETHER SALTING AGENTS WILL BE USED ON OR NEAR THE PROJECT SITE, AND USE HIS/HER BEST JUDGEMENT TO DETERMINE IF ANY ADDITIONAL PROTECTIVE MEASURES ARE REQUIRED. BELOW IS A TYPICAL DETAIL SHOWING THE PLACEMENT OF A GEOMEMBRANE BARRIER FOR PROJECTS WHERE SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE.



## IN-SITU TRENCH WALL


IF EXCAVATION IS REQUIRED, THE TRENCH WALL NEEDS TO BE CAPABLE OF SUPPORTING THE LOAD THAT THE PIPE SHEDS AS THE SYSTEM IS LOADED. IF SOILS ARE NOT CAPABLE OF SUPPORTING THESE LOADS, THE PIPE CAN DEFLECT. PERFORM A SIMPLE SOIL PRESSURE CHECK USING THE APPLIED LOADS TO DETERMINE THE LIMITS OF EXCAVATION BEYOND THE SPRING LINE OF THE OUTER MOST PIPES.

IN MOST CASES THE REQUIREMENTS FOR A SAFE WORK ENVIRONMENT AND PROPER BACKFILL PLACEMENT AND COMPACTION TAKE CARE OF THIS CONCERN.




## BACKFILL PLACEMENT

MATERIAL SHALL BE WORKED INTO THE PIPE HAUNCHES BY MEANS OF SHOVEL-SLICING, RODDING, AIR TAMPER, VIBRATORY ROD, OR OTHER EFFECTIVE METHODS.




IF AASHTO T99 PROCEDURES ARE DETERMINED INFEASIBLE BY THE GEOTECHNICAL ENGINEER OF RECORD, COMPACTION IS CONSIDERED ADEQUATE WHEN NO FURTHER YIELDING OF THE MATERIAL IS OBSERVED UNDER THE COMPACTOR, OR UNDER FOOT, AND THE GEOTECHNICAL ENGINEER OF RECORD (OR REPRESENTATIVE THEREOF) IS SATISFIED WITH THE LEVEL OF COMPACTION.

FOR LARGE SYSTEMS, CONVEYOR SYSTEMS, BACKHOES WITH LONG REACHES OR DRAGLINES WITH STONE BUCKETS MAY BE USED TO PLACE BACKFILL. ONCE MINIMUM COVER FOR CONSTRUCTION LOADING ACROSS THE ENTIRE WIDTH OF THE SYSTEM IS REACHED, ADVANCE THE EQUIPMENT TO THE END OF THE RECENTLY PLACED FILL, AND BEGIN THE SEQUENCE AGAIN UNTIL THE SYSTEM IS COMPLETELY BACKFILLED. THIS TYPE OF CONSTRUCTION SEQUENCE PROVIDES ROOM FOR STOCKPILED BACKFILL DIRECTLY BEHIND THE BACKHOE, AS WELL AS THE MOVEMENT OF CONSTRUCTION TRAFFIC. MATERIAL STOCKPILES ON TOP OF THE BACKFILLED DETENTION SYSTEM SHOULD BE LIMITED TO 8- TO 10- FEET HIGH AND MUST PROVIDE BALANCED LOADING ACROSS ALL BARRELS. TO DETERMINE THE PROPER COVER OVER THE PIPES TO ALLOW THE MOVEMENT OF CONSTRUCTION EQUIPMENT SEE TABLE 1, OR CONTACT YOUR LOCAL CONTECH SALES ENGINEER.



WHEN FLOWABLE FILL IS USED, YOU MUST PREVENT PIPE FLOATATION. TYPICALLY, SMALL LIFTS ARE PLACED BETWEEN THE PIPES AND THEN ALLOWED TO SET-UP PRIOR TO THE PLACEMENT OF THE NEXT LIFT. THE ALLOWABLE THICKNESS OF THE CLSM LIFT IS A FUNCTION OF A PROPER BALANCE BETWEEN THE UPLIFT FORCE OF THE CLSM, THE OPPOSING WEIGHT OF THE PIPE, AND THE EFFECT OF OTHER RESTRAINING MEASURES. THE PIPE CAN CARRY LIMITED FLUID PRESSURE WITHOUT PIPE DISTORTION OR DISPLACEMENT, WHICH ALSO AFFECTS THE CLSM LIFT THICKNESS. YOUR LOCAL CONTECH SALES ENGINEER CAN HELP DETERMINE THE PROPER LIFT THICKNESS.




## CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.

## ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION; POTENTIALLY CAUSING FLOATATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.



## CMP DETENTION SYSTEM INSPECTION AND MAINTENANCE

UNDERGROUND STORMWATER DETENTION AND INFILTRATION SYSTEMS MUST BE INSPECTED AND MAINTAINED AT REGULAR INTERVALS FOR PURPOSES OF PERFORMANCE AND LONGEVITY.

### INSPECTION

INSPECTION IS THE KEY TO EFFECTIVE MAINTENANCE OF CMP DETENTION SYSTEMS AND IS EASILY PERFORMED. CONTECH RECOMMENDS ONGOING, ANNUAL INSPECTIONS. SITES WITH HIGH TRASH LOAD OR SMALL OUTLET CONTROL ORIFICES MAY NEED MORE FREQUENT INSPECTIONS. THE RATE AT WHICH THE SYSTEM COLLECTS POLLUTANTS WILL DEPEND MORE ON SITE SPECIFIC ACTIVITIES RATHER THAN THE SIZE OR CONFIGURATION OF THE SYSTEM.

INSPECTIONS SHOULD BE PERFORMED MORE OFTEN IN EQUIPMENT WASHDOWN AREAS, IN CLIMATES WHERE SANDING AND/OR SALTING OPERATIONS TAKE PLACE, AND IN OTHER VARIOUS INSTANCES IN WHICH ONE WOULD EXPECT HIGHER ACCUMULATIONS OF SEDIMENT OR ABRASIVE/ CORROSIVE CONDITIONS. A RECORD OF EACH INSPECTION IS TO BE MAINTAINED FOR THE LIFE OF THE SYSTEM

### MAINTENANCE

CMP DETENTION SYSTEMS SHOULD BE CLEANED WHEN AN INSPECTION REVEALS ACCUMULATED SEDIMENT OR TRASH IS CLOGGING THE DISCHARGE ORIFICE.

ACCUMULATED SEDIMENT AND TRASH CAN TYPICALLY BE EVACUATED THROUGH THE MANHOLE OVER THE OUTLET ORIFICE. IF MAINTENANCE IS NOT PERFORMED AS RECOMMENDED, SEDIMENT AND TRASH MAY ACCUMULATE IN FRONT OF THE OUTLET ORIFICE. MANHOLE COVERS SHOULD BE SECURELY SEATED FOLLOWING CLEANING ACTIVITIES. CONTECH SUGGESTS THAT ALL SYSTEMS BE DESIGNED WITH AN ACCESS/INSPECTION MANHOLE SITUATED AT OR NEAR THE INLET AND THE OUTLET ORIFICE. SHOULD IT BE NECESSARY TO GET INSIDE THE SYSTEM TO PERFORM MAINTENANCE ACTIVITIES, ALL APPROPRIATE PRECAUTIONS REGARDING CONFINED SPACE ENTRY AND OSHA REGULATIONS SHOULD BE FOLLOWED.

ANNUAL INSPECTIONS ARE BEST PRACTICE FOR ALL UNDERGROUND SYSTEMS. DURING THIS INSPECTION, IF EVIDENCE OF SALTING/DE-ICING AGENTS IS OBSERVED WITHIN THE SYSTEM, IT IS BEST PRACTICE FOR THE SYSTEM TO BE RINSED, INCLUDING ABOVE THE SPRING LINE SOON AFTER THE SPRING THAW AS PART OF THE MAINTENANCE PROGRAM FOR THE SYSTEM.

MAINTAINING AN UNDERGROUND DETENTION OR INFILTRATION SYSTEM IS EASIEST WHEN THERE IS NO FLOW ENTERING THE SYSTEM. FOR THIS REASON, IT IS A GOOD IDEA TO SCHEDULE THE CLEANOUT DURING DRY WEATHER.

THE FOREGOING INSPECTION AND MAINTENANCE EFFORTS HELP ENSURE UNDERGROUND PIPE SYSTEMS USED FOR STORMWATER STORAGE CONTINUE TO FUNCTION AS INTENDED BY IDENTIFYING RECOMMENDED REGULAR INSPECTION AND MAINTENANCE PRACTICES. INSPECTION AND MAINTENANCE RELATED TO THE STRUCTURAL INTEGRITY OF THE PIPE OR THE SOUNDNESS OF PIPE JOINT CONNECTIONS IS BEYOND THE SCOPE OF THIS GUIDE.

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
**DYODS**  
DRAWING

DYO29422 Palmdale Basins  
Chamber A  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29422	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1

# PROJECT SUMMARY

## CALCULATION DETAILS

- LOADING = HS20/HS25
- APPROX. LINEAR FOOTAGE = 702 LF

## STORAGE SUMMARY


- STORAGE VOLUME REQUIRED = 52,000 CF
- PIPE STORAGE VOLUME = 35,286 CF
- BACKFILL STORAGE VOLUME = 16,730 CF
- TOTAL STORAGE PROVIDED = 52,017 CF

## PIPE DETAILS

- DIAMETER = 96"
- CORRUGATION = 5x1
- GAGE = 16
- COATING = ALT2
- WALL TYPE = PERFORATED
- BARREL SPACING = 36"

## BACKFILL DETAILS

- WIDTH AT ENDS = 36"
- ABOVE PIPE = 6"
- WIDTH AT SIDES = 36"
- BELOW PIPE = 6"



## NOTES

- ALL RISER AND STUB DIMENSIONS ARE TO CENTERLINE. ALL ELEVATIONS, DIMENSIONS, AND LOCATIONS OF RISERS AND INLETS, SHALL BE VERIFIED BY THE ENGINEER OF RECORD PRIOR TO RELEASING FOR FABRICATION.
- ALL FITTINGS AND REINFORCEMENT COMPLY WITH ASTM A998.
- ALL RISERS AND STUBS ARE 2<sup>2</sup>/<sub>3</sub>" x 1<sup>1</sup>/<sub>2</sub>" CORRUGATION AND 16 GAGE UNLESS OTHERWISE NOTED.
- RISERS TO BE FIELD TRIMMED TO GRADE.
- QUANTITY OF PIPE SHOWN DOES NOT PROVIDE EXTRA PIPE FOR CONNECTING THE SYSTEM TO EXISTING PIPE OR DRAINAGE STRUCTURES. OUR SYSTEM AS DETAILED PROVIDES NOMINAL INLET AND/OR OUTLET PIPE STUB FOR CONNECTION TO EXISTING DRAINAGE FACILITIES. IF ADDITIONAL PIPE IS NEEDED IT IS THE RESPONSIBILITY OF THE CONTRACTOR.
- BAND TYPE TO BE DETERMINED UPON FINAL DESIGN.
- THE PROJECT SUMMARY IS REFLECTIVE OF THE DYODS DESIGN, QUANTITIES ARE APPROX. AND SHOULD BE VERIFIED UPON FINAL DESIGN AND APPROVAL. FOR EXAMPLE, TOTAL EXCAVATION DOES NOT CONSIDER ALL VARIABLES SUCH AS SHORING AND ONLY ACCOUNTS FOR MATERIAL WITHIN THE ESTIMATED EXCAVATION FOOTPRINT.
- THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.

**ASSEMBLY**  
SCALE: 1" = 30'

C:\EXPORT\TEMPLATES\CMP\_1\B.DWG 10/18/2019 10:02 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.		
If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.		
DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com


9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS

CONTECH  
**DYODS**  
DRAWING


DYO29430 Palmdale Basins  
Chamber B  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29430	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		<b>1</b>




Infiltration Systems - CMP Infiltration & CMP Perforated Drainage Pipe			
Material Location	Description	Material Designation	Designation
8	Rigid or Flexible Pavement (if applicable)		
7	Road Base (if applicable)		
A	Geotextile Layer	Non-Woven Geotextile CONTECH C-40 or C-45	Engineer Decision for consideration to prevent soil migration into varying soil types. Wrap the trench only.
6	Backfill	Infiltration pipe systems have a pipe perforation sized of 3/8" diameter. An open graded, free draining stone, with a particle size of 1/2" - 2 1/2" diameter is recommended. AASHTO M 145-A-1 or AASHTO M 43 - 3, 4	Material shall be worked into the pipe haunches by means of shovel-slicing, rodding, air-tamper, vibratory rod, or other effective methods. Compaction of all placed fill material is necessary and shall be considered adequate when no further yielding of the material is observed under the compactor, or under foot, and the Project Engineer or his representative is satisfied with the level of compaction*
3	Bedding Stone	Well graded granular bedding material w/maximum particle size of 3" AASHTO M43 - 3,357,4,467, 5, 56, 57	For soil aggregates larger than 3/8" a dedicated bedding layer is not required for CMP. Pipe may be placed on the trench bottom comprised of native suitable well graded & granular material. For Arch pipes it is recommended to be shaped to a relatively flat bottom or fine-grade the foundation to a slight v-shape. Soil aggregates less than 3/8" and unsuitable material should be over-excavated and re-placed with a 4"-6" layer of well graded & granular stone per the material designation.
A	Geotextile Layer	None	Contech does not recommend geotextiles be placed under the invert of infiltration systems due to the propensity for geotextiles to clog over time.

\* Note: The listed AASHTO designations are for gradation only. The stone must also be angular and clean.



TYPICAL MANWAY DETAIL

NOTE: MANWAY DETAIL APPLICABLE FOR CMP SYSTEMS WITH DIAMETERS 48" AND LARGER. MANWAYS MAY BE REQUIRED ON SMALLER SYSTEMS DEPENDING ON ACTUAL SITE SPECIFIC CONDITIONS.



TYPICAL RISER DETAIL




NOTE: LADDERS ARE OPTIONAL AND ARE NOT REQUIRED FOR ALL SYSTEMS.

- 1 MINIMUM WIDTH DEPENDS ON SITE CONDITIONS AND ENGINEERING JUDGEMENT.
- 2 PRIOR TO PLACING THE BEDDING, THE FOUNDATION MUST BE CONSTRUCTED TO A UNIFORM AND STABLE GRADE. IN THE EVENT THAT UNSUITABLE FOUNDATION MATERIALS ARE ENCOUNTERED DURING EXCAVATION, THEY SHALL BE REMOVED AND BROUGHT BACK TO THE GRADE WITH A FILL MATERIAL AS APPROVED BY THE ENGINEER.
- 5 HAUNCH ZONE MATERIAL SHALL BE PLACED AND UNIFORMLY COMPACTED WITHOUT SOFT SPOTS.

**BACKFILL**  
MATERIAL SHALL BE PLACED IN 8"-10" MAXIMUM LIFTS. INADEQUATE COMPACTION CAN LEAD TO EXCESSIVE DEFLECTIONS WITHIN THE SYSTEM AND SETTLEMENT OF THE SOILS OVER THE SYSTEM. BACKFILL SHALL BE PLACED SUCH THAT THERE IS NO MORE THAN A TWO-LIFT DIFFERENTIAL BETWEEN THE SIDES OF ANY PIPE IN THE SYSTEM AT ALL TIMES DURING THE BACKFILL PROCESS. BACKFILL SHALL BE ADVANCED ALONG THE LENGTH OF THE SYSTEM AT THE SAME RATE TO AVOID DIFFERENTIAL LOADING ON ANY PIPES IN THE SYSTEM.

EQUIPMENT USED TO PLACE AND COMPACT THE BACKFILL SHALL BE OF A SIZE AND TYPE SO AS NOT TO DISTORT, DAMAGE, OR DISPLACE THE PIPE. ATTENTION MUST BE GIVEN TO PROVIDING ADEQUATE MINIMUM COVER FOR SUCH EQUIPMENT. MAINTAIN BALANCED LOADING ON ALL PIPES IN THE SYSTEM DURING ALL SUCH OPERATIONS.


OTHER ALTERNATE BACKFILL MATERIAL MAY BE ALLOWED DEPENDING ON SITE SPECIFIC CONDITIONS. REFER TO TYPICAL BACKFILL DETAIL FOR MATERIAL REQUIRED.



- NOTES:
- PERFORATIONS MEET AASHTO AND ASTM SPECIFICATIONS.
  - PERFORATION OPEN AREA PER SQUARE FOOT OF PIPE IS BASED ON THE NOMINAL DIAMETER AND LENGTH OF PIPE.
  - ALL DIMENSIONS ARE SUBJECT TO MANUFACTURING TOLERANCES.
  - ALL HOLES  $\varnothing$ 3/8".

TYPICAL PERFORATION DETAIL

SCALE: N.T.S.



TYPICAL SECTION VIEW

NOTE: IF SALTING AGENTS FOR SNOW AND ICE REMOVAL ARE USED ON OR NEAR THE PROJECT, AN HDPE MEMBRANE LINER IS RECOMMENDED WITH THE SYSTEM. THE IMPERMEABLE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM A CHANGE IN THE SURROUNDING ENVIRONMENT OVER A PERIOD OF TIME. PLEASE REFER TO THE CORRUGATED METAL PIPE DETENTION DESIGN GUIDE FOR ADDITIONAL INFORMATION.

LINER OVER ROWS  
SCALE: N.T.S.

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.


DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
DYODS  
DRAWING

DYO29430 Palmdale Basins  
Chamber B  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29430	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	APPROVED: DYO
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1



**CONSTRUCTION LOADS**

FOR TEMPORARY CONSTRUCTION VEHICLE LOADS, AN EXTRA AMOUNT OF COMPACTED COVER MAY BE REQUIRED OVER THE TOP OF THE PIPE. THE HEIGHT-OF-COVER SHALL MEET THE MINIMUM REQUIREMENTS SHOWN IN THE TABLE BELOW. THE USE OF HEAVY CONSTRUCTION EQUIPMENT NECESSITATES GREATER PROTECTION FOR THE PIPE THAN FINISHED GRADE COVER MINIMUMS FOR NORMAL HIGHWAY TRAFFIC.

PIPE SPAN, INCHES	AXLE LOADS (kips)			
	18-50	50-75	75-110	110-150
	MINIMUM COVER (FT)			
12-42	2.0	2.5	3.0	3.0
48-72	3.0	3.0	3.5	4.0
78-120	3.0	3.5	4.0	4.0
126-144	3.5	4.0	4.5	4.5

\*MINIMUM COVER MAY VARY, DEPENDING ON LOCAL CONDITIONS. THE CONTRACTOR MUST PROVIDE THE ADDITIONAL COVER REQUIRED TO AVOID DAMAGE TO THE PIPE. MINIMUM COVER IS MEASURED FROM THE TOP OF THE PIPE TO THE TOP OF THE MAINTAINED CONSTRUCTION ROADWAY SURFACE.

**CONSTRUCTION LOADING DIAGRAM**

SCALE: N.T.S.

**SPECIFICATION FOR DESIGNED DETENTION SYSTEM:**

**SCOPE**

THIS SPECIFICATION COVERS THE MANUFACTURE AND INSTALLATION OF THE DESIGNED DETENTION SYSTEM DETAILED IN THE PROJECT PLANS.

**MATERIAL**

THE MATERIAL SHALL CONFORM TO THE APPLICABLE REQUIREMENTS LISTED BELOW:

ALUMINIZED TYPE 2 STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-274 OR ASTM A-92.

THE GALVANIZED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-218 OR ASTM A-929.

THE POLYMER COATED STEEL COILS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-246 OR ASTM A-742.

THE ALUMINUM COILS SHALL CONFORM TO THE APPLICABLE OF AASHTO M-197 OR ASTM B-744.

**CONSTRUCTION LOADS**

CONSTRUCTION LOADS MAY BE HIGHER THAN FINAL LOADS. FOLLOW THE MANUFACTURER'S OR NCSPA GUIDELINES.

**PIPE**

THE PIPE SHALL BE MANUFACTURED IN ACCORDANCE TO THE APPLICABLE REQUIREMENTS LISTED BELOW:

ALUMINIZED TYPE 2: AASHTO M-36 OR ASTM A-760

GALVANIZED: AASHTO M-36 OR ASTM A-760

POLYMER COATED: AASHTO M-245 OR ASTM A-762

ALUMINUM: AASHTO M-196 OR ASTM B-745


**APPLICABLE HANDLING AND ASSEMBLY**

SHALL BE IN ACCORDANCE WITH NCSP'S (NATIONAL CORRUGATED STEEL ASSOCIATION) FOR ALUMINIZED TYPE 2, GALVANIZED OR POLYMER COATED STEEL. SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS FOR ALUMINUM PIPE.


**INSTALLATION**

SHALL BE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, SECTION 26, DIVISION II DIVISION II OR ASTM A-798 (FOR ALUMINIZED TYPE 2, GALVANIZED OR POLYMER COATED STEEL) OR ASTM B-788 (FOR ALUMINUM PIPE) AND IN CONFORMANCE WITH THE PROJECT PLANS AND SPECIFICATIONS. IF THERE ARE ANY INCONSISTENCIES OR CONFLICTS THE CONTRACTOR SHOULD DISCUSS AND RESOLVE WITH THE SITE ENGINEER.


IT IS ALWAYS THE RESPONSIBILITY OF THE CONTRACTOR TO FOLLOW OSHA GUIDELINES FOR SAFE PRACTICES.



**SECTION VIEW**



**ROUND OPTION PLAN VIEW**



**SQUARE OPTION PLAN VIEW**

**NOTES:**

- DESIGN IN ACCORDANCE WITH AASHTO, 17th EDITION.
- DESIGN LOAD HS25.
- EARTH COVER = 1' MAX.
- CONCRETE STRENGTH = 3,500 psi
- REINFORCING STEEL = ASTM A615, GRADE 60.
- PROVIDE ADDITIONAL REINFORCING AROUND OPENINGS EQUAL TO THE BARS INTERRUPTED, HALF EACH SIDE. ADDITIONAL BARS TO BE IN THE SAME PLANE.
- TRIM OPENING WITH DIAGONAL #4 BARS, EXTEND BARS A MINIMUM OF 12" BEYOND OPENING, BEND BARS AS REQUIRED TO MAINTAIN BAR COVER.
- PROTECTION SLAB AND ALL MATERIALS TO BE PROVIDED AND INSTALLED BY CONTRACTOR.
- DETAIL DESIGN BY DELTA ENGINEERING, BINGHAMTON, NY.

**MANHOLE CAP DETAIL**

SCALE: N.T.S.

Ø CMP RISER	A	Ø B	REINFORCING	**BEARING PRESSURE (PSF)
24"	Ø 4' 4'X4'	26"	#5 @ 12" OCEW #5 @ 12" OCEW	2,410 1,780
30"	Ø 4'-6" 4'-6" X 4'-6"	32"	#5 @ 12" OCEW #5 @ 12" OCEW	2,120 1,530
36"	Ø 5' X 5'	38"	#5 @ 10" OCEW #5 @ 10" OCEW	1,890 1,350
42"	Ø 5'-6" 5'-6" X 5'-6"	44"	#5 @ 10" OCEW #5 @ 9" OCEW	1,720 1,210
48"	Ø 6' X 6'	50"	#5 @ 9" OCEW #5 @ 8" OCEW	1,600 1,100

\*\* ASSUMED SOIL BEARING CAPACITY

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

**NOTE:**  
THESE DRAWINGS ARE FOR CONCEPTUAL PURPOSES AND DO NOT REFLECT ANY LOCAL PREFERENCES OR REGULATIONS. PLEASE CONTACT YOUR LOCAL CONTECH REP FOR MODIFICATIONS.

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
DYODS  
DRAWING

DY029430 Palmdale Basins  
Chamber B  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29430	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1


## CMP DETENTION INSTALLATION GUIDE

PROPER INSTALLATION OF A FLEXIBLE UNDERGROUND DETENTION SYSTEM WILL ENSURE LONG-TERM PERFORMANCE. THE CONFIGURATION OF THESE SYSTEMS OFTEN REQUIRES SPECIAL CONSTRUCTION PRACTICES THAT DIFFER FROM CONVENTIONAL FLEXIBLE PIPE CONSTRUCTION. CONTECH ENGINEERED SOLUTIONS STRONGLY SUGGESTS SCHEDULING A PRE-CONSTRUCTION MEETING WITH YOUR LOCAL SALES ENGINEER TO DETERMINE IF ADDITIONAL MEASURES, NOT COVERED IN THIS GUIDE, ARE APPROPRIATE FOR YOUR SITE.

## FOUNDATION

CONSTRUCT A FOUNDATION THAT CAN SUPPORT THE DESIGN LOADING APPLIED BY THE PIPE AND ADJACENT BACKFILL WEIGHT AS WELL AS MAINTAIN ITS INTEGRITY DURING CONSTRUCTION.

IF SOFT OR UNSUITABLE SOILS ARE ENCOUNTERED, REMOVE THE POOR SOILS DOWN TO A SUITABLE DEPTH AND THEN BUILD UP TO THE APPROPRIATE ELEVATION WITH A COMPETENT BACKFILL MATERIAL. THE STRUCTURAL FILL MATERIAL GRADATION SHOULD NOT ALLOW THE MIGRATION OF FINES, WHICH CAN CAUSE SETTLEMENT OF THE DETENTION SYSTEM OR PAVEMENT ABOVE. IF THE STRUCTURAL FILL MATERIAL IS NOT COMPATIBLE WITH THE UNDERLYING SOILS AN ENGINEERING FABRIC SHOULD BE USED AS A SEPARATOR. IN SOME CASES, USING A STIFF REINFORCING GEOGRID REDUCES OVER EXCAVATION AND REPLACEMENT FILL QUANTITIES.




GRADE THE FOUNDATION SUBGRADE TO A UNIFORM OR SLIGHTLY SLOPING GRADE. IF THE SUBGRADE IS CLAY OR RELATIVELY NON-POROUS AND THE CONSTRUCTION SEQUENCE WILL LAST FOR AN EXTENDED PERIOD OF TIME, IT IS BEST TO SLOPE THE GRADE TO ONE END OF THE SYSTEM. THIS WILL ALLOW EXCESS WATER TO DRAIN QUICKLY, PREVENTING SATURATION OF THE SUBGRADE.

## GEOMEMBRANE BARRIER

A SITE'S RESISTIVITY MAY CHANGE OVER TIME WHEN VARIOUS TYPES OF SALTING AGENTS ARE USED, SUCH AS ROAD SALTS FOR DEICING AGENTS. IF SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE, A GEOMEMBRANE BARRIER IS RECOMMENDED WITH THE SYSTEM. THE GEOMEMBRANE LINER IS INTENDED TO HELP PROTECT THE SYSTEM FROM THE POTENTIAL ADVERSE EFFECTS THAT MAY RESULT FROM THE USE OF SUCH AGENTS INCLUDING PREMATURE CORROSION AND REDUCED ACTUAL SERVICE LIFE.


THE PROJECT'S ENGINEER OF RECORD IS TO EVALUATE WHETHER SALTING AGENTS WILL BE USED ON OR NEAR THE PROJECT SITE, AND USE HIS/HER BEST JUDGEMENT TO DETERMINE IF ANY ADDITIONAL PROTECTIVE MEASURES ARE REQUIRED. BELOW IS A TYPICAL DETAIL SHOWING THE PLACEMENT OF A GEOMEMBRANE BARRIER FOR PROJECTS WHERE SALTING AGENTS ARE USED ON OR NEAR THE PROJECT SITE.



## IN-SITU TRENCH WALL


IF EXCAVATION IS REQUIRED, THE TRENCH WALL NEEDS TO BE CAPABLE OF SUPPORTING THE LOAD THAT THE PIPE SHEDS AS THE SYSTEM IS LOADED. IF SOILS ARE NOT CAPABLE OF SUPPORTING THESE LOADS, THE PIPE CAN DEFLECT. PERFORM A SIMPLE SOIL PRESSURE CHECK USING THE APPLIED LOADS TO DETERMINE THE LIMITS OF EXCAVATION BEYOND THE SPRING LINE OF THE OUTER MOST PIPES.

IN MOST CASES THE REQUIREMENTS FOR A SAFE WORK ENVIRONMENT AND PROPER BACKFILL PLACEMENT AND COMPACTION TAKE CARE OF THIS CONCERN.




## BACKFILL PLACEMENT

MATERIAL SHALL BE WORKED INTO THE PIPE HAUNCHES BY MEANS OF SHOVEL-SLICING, RODDING, AIR TAMPER, VIBRATORY ROD, OR OTHER EFFECTIVE METHODS.




IF AASHTO T99 PROCEDURES ARE DETERMINED INFEASIBLE BY THE GEOTECHNICAL ENGINEER OF RECORD, COMPACTION IS CONSIDERED ADEQUATE WHEN NO FURTHER YIELDING OF THE MATERIAL IS OBSERVED UNDER THE COMPACTOR, OR UNDER FOOT, AND THE GEOTECHNICAL ENGINEER OF RECORD (OR REPRESENTATIVE THEREOF) IS SATISFIED WITH THE LEVEL OF COMPACTION.

FOR LARGE SYSTEMS, CONVEYOR SYSTEMS, BACKHOES WITH LONG REACHES OR DRAGLINES WITH STONE BUCKETS MAY BE USED TO PLACE BACKFILL. ONCE MINIMUM COVER FOR CONSTRUCTION LOADING ACROSS THE ENTIRE WIDTH OF THE SYSTEM IS REACHED, ADVANCE THE EQUIPMENT TO THE END OF THE RECENTLY PLACED FILL, AND BEGIN THE SEQUENCE AGAIN UNTIL THE SYSTEM IS COMPLETELY BACKFILLED. THIS TYPE OF CONSTRUCTION SEQUENCE PROVIDES ROOM FOR STOCKPILED BACKFILL DIRECTLY BEHIND THE BACKHOE, AS WELL AS THE MOVEMENT OF CONSTRUCTION TRAFFIC. MATERIAL STOCKPILES ON TOP OF THE BACKFILLED DETENTION SYSTEM SHOULD BE LIMITED TO 8- TO 10- FEET HIGH AND MUST PROVIDE BALANCED LOADING ACROSS ALL BARRELS. TO DETERMINE THE PROPER COVER OVER THE PIPES TO ALLOW THE MOVEMENT OF CONSTRUCTION EQUIPMENT SEE TABLE 1, OR CONTACT YOUR LOCAL CONTECH SALES ENGINEER.



WHEN FLOWABLE FILL IS USED, YOU MUST PREVENT PIPE FLOATATION. TYPICALLY, SMALL LIFTS ARE PLACED BETWEEN THE PIPES AND THEN ALLOWED TO SET-UP PRIOR TO THE PLACEMENT OF THE NEXT LIFT. THE ALLOWABLE THICKNESS OF THE CLSM LIFT IS A FUNCTION OF A PROPER BALANCE BETWEEN THE UPLIFT FORCE OF THE CLSM, THE OPPOSING WEIGHT OF THE PIPE, AND THE EFFECT OF OTHER RESTRAINING MEASURES. THE PIPE CAN CARRY LIMITED FLUID PRESSURE WITHOUT PIPE DISTORTION OR DISPLACEMENT, WHICH ALSO AFFECTS THE CLSM LIFT THICKNESS. YOUR LOCAL CONTECH SALES ENGINEER CAN HELP DETERMINE THE PROPER LIFT THICKNESS.




## CONSTRUCTION LOADING

TYPICALLY, THE MINIMUM COVER SPECIFIED FOR A PROJECT ASSUMES H-20 LIVE LOAD. BECAUSE CONSTRUCTION LOADS OFTEN EXCEED DESIGN LIVE LOADS, INCREASED TEMPORARY MINIMUM COVER REQUIREMENTS ARE NECESSARY. SINCE CONSTRUCTION EQUIPMENT VARIES FROM JOB TO JOB, IT IS BEST TO ADDRESS EQUIPMENT SPECIFIC MINIMUM COVER REQUIREMENTS WITH YOUR LOCAL CONTECH SALES ENGINEER DURING YOUR PRE-CONSTRUCTION MEETING.

## ADDITIONAL CONSIDERATIONS

BECAUSE MOST SYSTEMS ARE CONSTRUCTED BELOW-GRADE, RAINFALL CAN RAPIDLY FILL THE EXCAVATION; POTENTIALLY CAUSING FLOATATION AND MOVEMENT OF THE PREVIOUSLY PLACED PIPES. TO HELP MITIGATE POTENTIAL PROBLEMS, IT IS BEST TO START THE INSTALLATION AT THE DOWNSTREAM END WITH THE OUTLET ALREADY CONSTRUCTED TO ALLOW A ROUTE FOR THE WATER TO ESCAPE. TEMPORARY DIVERSION MEASURES MAY BE REQUIRED FOR HIGH FLOWS DUE TO THE RESTRICTED NATURE OF THE OUTLET PIPE.



## CMP DETENTION SYSTEM INSPECTION AND MAINTENANCE

UNDERGROUND STORMWATER DETENTION AND INFILTRATION SYSTEMS MUST BE INSPECTED AND MAINTAINED AT REGULAR INTERVALS FOR PURPOSES OF PERFORMANCE AND LONGEVITY.

### INSPECTION

INSPECTION IS THE KEY TO EFFECTIVE MAINTENANCE OF CMP DETENTION SYSTEMS AND IS EASILY PERFORMED. CONTECH RECOMMENDS ONGOING, ANNUAL INSPECTIONS. SITES WITH HIGH TRASH LOAD OR SMALL OUTLET CONTROL ORIFICES MAY NEED MORE FREQUENT INSPECTIONS. THE RATE AT WHICH THE SYSTEM COLLECTS POLLUTANTS WILL DEPEND MORE ON SITE SPECIFIC ACTIVITIES RATHER THAN THE SIZE OR CONFIGURATION OF THE SYSTEM.

INSPECTIONS SHOULD BE PERFORMED MORE OFTEN IN EQUIPMENT WASHDOWN AREAS, IN CLIMATES WHERE SANDING AND/OR SALTING OPERATIONS TAKE PLACE, AND IN OTHER VARIOUS INSTANCES IN WHICH ONE WOULD EXPECT HIGHER ACCUMULATIONS OF SEDIMENT OR ABRASIVE/ CORROSIVE CONDITIONS. A RECORD OF EACH INSPECTION IS TO BE MAINTAINED FOR THE LIFE OF THE SYSTEM

### MAINTENANCE

CMP DETENTION SYSTEMS SHOULD BE CLEANED WHEN AN INSPECTION REVEALS ACCUMULATED SEDIMENT OR TRASH IS CLOGGING THE DISCHARGE ORIFICE.

ACCUMULATED SEDIMENT AND TRASH CAN TYPICALLY BE EVACUATED THROUGH THE MANHOLE OVER THE OUTLET ORIFICE. IF MAINTENANCE IS NOT PERFORMED AS RECOMMENDED, SEDIMENT AND TRASH MAY ACCUMULATE IN FRONT OF THE OUTLET ORIFICE. MANHOLE COVERS SHOULD BE SECURELY SEATED FOLLOWING CLEANING ACTIVITIES. CONTECH SUGGESTS THAT ALL SYSTEMS BE DESIGNED WITH AN ACCESS/INSPECTION MANHOLE SITUATED AT OR NEAR THE INLET AND THE OUTLET ORIFICE. SHOULD IT BE NECESSARY TO GET INSIDE THE SYSTEM TO PERFORM MAINTENANCE ACTIVITIES, ALL APPROPRIATE PRECAUTIONS REGARDING CONFINED SPACE ENTRY AND OSHA REGULATIONS SHOULD BE FOLLOWED.

ANNUAL INSPECTIONS ARE BEST PRACTICE FOR ALL UNDERGROUND SYSTEMS. DURING THIS INSPECTION, IF EVIDENCE OF SALTING/DE-ICING AGENTS IS OBSERVED WITHIN THE SYSTEM, IT IS BEST PRACTICE FOR THE SYSTEM TO BE RINSED, INCLUDING ABOVE THE SPRING LINE SOON AFTER THE SPRING THAW AS PART OF THE MAINTENANCE PROGRAM FOR THE SYSTEM.

MAINTAINING AN UNDERGROUND DETENTION OR INFILTRATION SYSTEM IS EASIEST WHEN THERE IS NO FLOW ENTERING THE SYSTEM. FOR THIS REASON, IT IS A GOOD IDEA TO SCHEDULE THE CLEANOUT DURING DRY WEATHER.

THE FOREGOING INSPECTION AND MAINTENANCE EFFORTS HELP ENSURE UNDERGROUND PIPE SYSTEMS USED FOR STORMWATER STORAGE CONTINUE TO FUNCTION AS INTENDED BY IDENTIFYING RECOMMENDED REGULAR INSPECTION AND MAINTENANCE PRACTICES. INSPECTION AND MAINTENANCE RELATED TO THE STRUCTURAL INTEGRITY OF THE PIPE OR THE SOUNDNESS OF PIPE JOINT CONNECTIONS IS BEYOND THE SCOPE OF THIS GUIDE.

C:\EXPORT\TEMPLATES\CMP\_V8.DWG 10/18/2019 10:02 AM

The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part thereof, may be used, reproduced or modified in any manner without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech expressly disclaims any liability or responsibility for such use.

If discrepancies between the supplied information upon which the drawing is based and actual field conditions are encountered as site work progresses, these discrepancies must be reported to Contech immediately for re-evaluation of the design. Contech accepts no liability for designs based on missing, incomplete or inaccurate information supplied by others.

DATE	REVISION DESCRIPTION	BY

**CONTECH**  
ENGINEERED SOLUTIONS LLC  
www.ContechES.com  
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069  
800-338-1122 513-645-7000 513-645-7993 FAX

**CONTECH**  
CMP DETENTION SYSTEMS  
CONTECH  
DYODS  
DRAWING

DYO29430 Palmdale Basins  
Chamber B  
Palmdale, CA  
DETENTION SYSTEM

PROJECT No.: 19757	SEQ. No.: 29430	DATE: 3/29/2023
DESIGNED: DYO	DRAWN: DYO	
CHECKED: DYO	APPROVED: DYO	
SHEET NO.:		1

## **Appendix G Infiltration Report**

March 9, 2022

Covington Development Group, Inc.  
3 Corporate Plaza, Suite 230  
Newport Beach, California 92660



**SOUTHERN  
CALIFORNIA  
GEOTECHNICAL**  
*A California Corporation*

Attention: Mr. Mark S. Milakovich  
President

Project No.: **22G109-2**

Subject: **Results of Infiltration Testing**  
Proposed Warehouse  
8<sup>th</sup> Street, South of Rancho Vista Boulevard  
Palmdale, California

Reference: Geotechnical Investigation, Proposed Warehouse, 8<sup>th</sup> Street, South of Ranch Vista Boulevard, Palmdale, California, Prepared by Southern California Geotechnical, Inc. (SCG) for Covington Development Group, Inc., SCG Project No. 22G109-1R, dated March 7, 2022.

Mr. Milakovich:

In accordance with your request, we have conducted infiltration testing at the subject site. We are pleased to present this report summarizing the results of the infiltration testing and our design recommendations.

### **Scope of Services**

The scope of services performed for this project was in accordance with our Proposal No. 21P430, dated September 29, 2021. The scope of the infiltration testing consisted of site reconnaissance, subsurface exploration, field testing, and engineering analysis to determine the infiltration rates of the onsite soils. The infiltration testing was performed in general accordance with the guidelines published by the County of Los Angeles – Department of Public Works Geotechnical and Materials Engineering Division. These guidelines are dated June 30, 2021 and titled Guidelines for Design, Investigation, and Reporting Low Impact Development Stormwater Infiltration, GS200.1.

### **Site Description**

The subject site is located on the west side of 8<sup>th</sup> Street, approximately 800 feet south of the intersection of 8<sup>th</sup> Street and Rancho Vista Boulevard in Palmdale, California. The site is bounded to the north and west by a railroad easement, to the south by a vacant lot, and to the east by 8<sup>th</sup> Street. The general location of the site is illustrated on the Site Location Map, enclosed as Plate 1 of this report.

The subject site consists of a roughly rectangular-shaped parcel, 18± acres in size. The site is currently vacant and undeveloped. The ground surface cover for the site generally consists of exposed soil with sparse native grass and weed growth. Trash and debris are scattered

throughout the site. A drainage course is located along the southern property line trending east-west of the site.

Based on our review of readily available historical aerial photographs and Google Earth, most of the site appears to have been rough graded between the years of 2010 and 2011. It appears that a construction trailer along with rock and soil stockpiles were present at the site between the years of 2011 and 2013.

Detailed topographic information was not available at the time of this report. Based on elevations obtained from Google Earth, and visual observations made at the time of the subsurface investigation, the overall site topography gently slopes downward to the east at a gradient of approximately 1 percent. Areas located in the central and eastern regions of the site appear to have been cut 1 to 3± feet below existing site grades. The depths of the drainage course range from 1 to 9± feet lower than the surrounding elevations.

### **Proposed Development**

A conceptual site plan, identified as Scheme 1 and prepared by HPA, Inc., for the proposed development was provided to our office by the client. Based on this plan, the subject site will be developed with a 389,200± ft<sup>2</sup> warehouse, located in the central region of the site. Dock-high doors will be constructed along the northern and southern building walls. The proposed building is expected to be surrounded by AC pavements in the parking and drive areas, PCC pavements in the loading dock area, and concrete flatwork and landscaped planters throughout the site.

The proposed development will use on-site storm water infiltration. The infiltration system will consist of below-grade chambers located in the northeastern and southeastern regions of the site. The bottom of the infiltration chambers will be approximately 10± feet below the existing site grades.

### **Concurrent Study**

SCG conducted a geotechnical investigation at the subject site, referenced above. As a part of this study, five (5) borings advanced to depths of 20 to 25± feet below the existing site grades.

Artificial fill soils were encountered at the ground surface at Boring No. B-3. These fill soils extend to a depth of 3± feet below the existing site grades. The fill soils generally consist of medium dense fine sandy silts with a varying amount of clay. The fill soils possess a disturbed appearance and mottled appearance resulting in their classification as artificial fill. Native alluvium was encountered below the fill soils at Boring No. B-3 and at the ground surface of all of the remaining boring locations, extending to at least the maximum depth explored of 25± feet below existing site grades. The alluvium generally consists of medium dense to dense fine to coarse sands and silty fine sands with varying gravel content. Boring No. B-4 encountered a layer of very dense clayey fine sands to fine sandy clays at depths of 17 to 22± feet below the existing site grades.

### **Groundwater**

Free water was not encountered during the drilling of any of the borings. Based on the lack of any water within the borings and the moisture contents of the recovered soil samples, the static



groundwater is considered to have existed at a depth in excess of 25± feet at the time of the subsurface exploration.

As part of our research, we reviewed available groundwater data in order to determine the historic high groundwater level for the site. The primary reference used to determine the historic groundwater depths in this area is the California Geological Survey (CGS) Open File Report 105, the Seismic Hazard Zone Report for the Palmdale 7.5-Minute Quadrangle, which indicated that the historic high groundwater level for the site was greater than 40 feet below the ground surface.

Recent water level data was obtained from the California Department of Water Resources website, <http://www.water.ca.gov/waterdatalibrary/>. The nearest monitoring well is located approximately 0.3 miles northeast from the site. Water level readings within this monitoring well indicates a high groundwater level of 445 feet (April 1982) below the ground surface.

## **Subsurface Exploration**

### Scope of Exploration

The subsurface exploration for the infiltration testing consisted of two (2) infiltration test borings advanced to a depth of 10± feet below the existing site grades. The borings were logged during drilling by a member of our staff and were advanced using a truck-mounted drilling rig, equipped with 8-inch-diameter hollow stem augers. The approximate locations of the infiltration test borings (identified as I-1 to I-2) are indicated on the Infiltration Test Location Plan, enclosed as Plate 2 of this report.

Upon the completion of the infiltration borings, the bottom of each test boring was covered with 2± inches of clean ¾-inch gravel. A sufficient length of 3-inch-diameter perforated PVC casing was then placed into each test hole so that the PVC casing extended from the bottom of the test hole to the ground surface. Clean ¾-inch gravel was then installed in the annulus surrounding the PVC casing.

### Geotechnical Conditions

Native alluvium was encountered at all infiltration test locations, extending to the maximum explored depth of 10± feet below existing site grades. The alluvium generally consists of medium dense silty fine sands with varying sand and gravel content. Groundwater was not encountered at any of the infiltration borings. The Infiltration Test Logs, which illustrate the conditions encountered at each test location are included within this report.

## **Infiltration Testing**

We understand that the results of the testing will be used to prepare a preliminary design for the storm water infiltration systems that will be used at the subject site. As previously mentioned, the infiltration testing was performed in general accordance with Guidelines for Geotechnical Investigation and Reporting Low Impact Development Stormwater Infiltration (GS200.1) published by Los Angeles County Public Works – Geotechnical Engineering and Materials Division, dated June 30, 2021.

## Pre-soaking

The infiltration test boring was pre-soaked for at least 1 hour to ensure the sand around the annulus of the perforated pipe was fully saturated. The pre-soaking procedure consisted of filling each test boring with clean potable water to an elevation of at least 12± inches above the bottom of each test boring. In accordance with the Los Angeles County guidelines, since the water in the infiltration test boring did not completely infiltrate within a 30-minute time period after filling each boring, a falling head test was the appropriate test method.

## Infiltration Testing Procedure

After the completion of the pre-soaking process, SCG performed the infiltration testing. A sufficient amount of water was added to the test borings so that the water level was approximately 12± inches higher than the bottom of the borings and less than or equal to the water level used during the pre-soaking process. Readings were taken at 30-minute intervals for all infiltration tests. A stabilized rate of drop, where the highest and lowest readings from three consecutive readings are within 10 percent of each other, was obtained for each of the test borings. These water level readings are presented on the spreadsheets enclosed with this report. The infiltration rates for each of the timed intervals are also tabulated on the spreadsheets.

The infiltration rates for the tests are tabulated in inches per hour. In accordance with the typically accepted practice, it is recommended that the most conservative reading from the latter part of the infiltration tests be used for design. These rates are summarized below:

<u>Infiltration Test No.</u>	<u>Depth (feet)</u>	<u>Soil Description</u>	<u>Infiltration Rate (inches/hour)</u>
I-1	10	Silty fine to medium Sand, trace coarse Sand, trace fine Gravel	0.2
I-2	10	Silty fine to medium Sand, trace coarse Sand, trace fine Gravel	0.4

## Laboratory Testing

### Moisture Content

The moisture contents for the recovered soil samples within the borings were determined in accordance with ASTM D-2216 and are expressed as a percentage of the dry weight. These test results are presented on the Boring Logs.

### Grain Size Analysis

The grain size distribution of selected soils collected from the base of each infiltration test boring have been determined using a range of wire mesh screens. These tests were performed in general accordance with ASTM D-422 and/or ASTM D-1140. The weight of the portion of the sample retained on each screen is recorded and the percentage finer or coarser of the total weight is calculated. The results of these tests are presented on Plates C-1 to C-2 of this report.

## Design Recommendations

Two (2) infiltration tests were performed at the northeastern and southeastern region of the subject site. The measured infiltration rates at the infiltration test locations range from 0.6 to 1.2 inches per hour.

The Guidelines for Geotechnical Investigation and Reporting Low Impact Development Stormwater Infiltration, GS200.1 prepared by the County of Los Angeles, Department of Public Works, Geotechnical and Materials Division (GMED) on June 30, 2021 dictate that a reduction factor be utilized in the design infiltration rate. The following reduction factors are considered in the design infiltration rate (DIR):

<b>Reduction Factors</b>	
Small Diameter Boring	$RF_t = 1$
Site Variability, number of tests, and thoroughness of subsurface investigation	$RF_v = 1$
Long-term siltation plugging and maintenance	$RF_s = 1$
Total Reduction Factor, $RF = RF_t + RF_v + RF_s$	$RF = 3$
Design Infiltration Rate (DIR) = Measured Percolation Rate/RF	DIR = See below

Based on the results of the infiltration testing, the following infiltration rates should be used in the design of the infiltration systems in their respective locations and depths:

<u><b>Infiltration System</b></u>	<u><b>Design Infiltration Rate (inches/hour)</b></u>
Southeast	0.2
Northeast	0.4

The design of the proposed storm water infiltration system should be performed by the project civil engineer, in accordance with the City of Palmdale and/or County of Los Angeles guidelines. However, it is recommended that the system be constructed so as to facilitate removal of silt and clay, or other deleterious materials from any water that may enter the systems. The presence of such materials would decrease the effective infiltration rates. **It is recommended that the project civil engineer apply an appropriate factor of safety. The infiltration rate recommended above is based on the assumption that only clean water will be introduced to the subsurface profile. Any fines, debris, or organic materials could significantly impact the infiltration rate.** It should be noted that the recommended infiltration rate is based on infiltration testing at two (2) discrete locations and the overall infiltration rate of the storm water infiltration system could vary considerably.

## Infiltration Rate Considerations

The infiltration rates presented herein was determined in accordance with the Los Angeles County guidelines and are considered valid only for the time and place of the actual test. Varying subsurface conditions will exist in other areas of the site, which could alter the

recommended infiltration rates presented above. The infiltration rates will decline over time between maintenance cycles as silt or clay particles accumulate on the BMP surface. The infiltration rate is highly dependent upon a number of factors, including density, silt and clay content, grain size distribution throughout the range of particle sizes, and particle shape. Small changes in these factors can cause large changes in the infiltration rates.

Infiltration rates are based on unsaturated flow. As water is introduced into soils by infiltration, the soils become saturated and the wetting front advances from the unsaturated zone to the saturated zone. Once the soils become saturated, infiltration rates become zero, and water can only move through soils by hydraulic conductivity at a rate determined by pressure head and soil permeability. Changes in soil moisture content will affect the infiltration rate. Infiltration rates should be expected to decrease until the soils become saturated. Soil permeability values will then govern groundwater movement. Permeability values may be on the order of 10 to 20 times less than infiltration rates. The system designer should incorporate adequate factors of safety and allow for overflow design into appropriate traditional storm drain systems, which would transport storm water off-site.

### **Construction Considerations**

The infiltration rates presented in this report are specific to the tested locations and tested depths. Infiltration rates can be significantly reduced if the soils are exposed to excessive disturbance or compaction during construction. Compaction of the soils at the bottom of the infiltration system can significantly reduce the infiltration ability of the chambers. Therefore, the subgrade soils within proposed infiltration system areas should not be over-excavated, undercut or compacted in any significant manner. **It is recommended that a note to this effect be added to the project plans and/or specifications.**

We recommend that a representative from the geotechnical engineer be on-site during the construction of the proposed infiltration systems to identify the soil classification at the base of each system. It should be confirmed that the soils at the base of the proposed infiltration systems correspond with those presented in this report to ensure that the performance of the systems will be consistent with the rates reported herein.

We recommend that scrapers and other rubber-tired heavy equipment not be operated on the chamber bottom, or at levels lower than 2 feet above the bottom of the system, particularly within basins. As such, the bottom 24 inches of the infiltration systems should be excavated with non-rubber-tired equipment, such as excavators.

### **Chamber Maintenance**

The proposed project includes below-grade chamber systems. Water flowing into these systems will carry some level of sediment. Wind-blown sediments will also contribute to sediment deposition at the bottom of the chamber. This layer has the potential to significantly reduce the infiltration rate of the chamber subgrade soils. Therefore, a formal chamber maintenance program should be established to ensure that these silt and clay deposits are removed from the system on a regular basis.

## **Location of Infiltration Systems**

The use of on-site storm water infiltration systems carries a risk of creating adverse geotechnical conditions. Increasing the moisture content of the soil can cause the soil to lose internal shear strength and increase its compressibility, resulting in a change in the designed engineering properties. Overlying structures and pavements in the infiltration area could potentially be damaged due to saturation of the subgrade soils. **The proposed infiltration systems for this site should be located at least 25 feet away from any structures, including retaining walls.** Even with this provision of locating the infiltration system at least 25 feet from the building(s), it is possible that infiltrating water into the subsurface soils could have an adverse effect on the proposed or existing structures. It should also be noted that utility trenches which happen to collect storm water can also serve as conduits to transmit storm water toward the structure, depending on the slope of the utility trench. Therefore, consideration should also be given to the proposed locations of underground utilities which may pass near the proposed infiltration system.

The infiltration system designer should also give special consideration to the effect that the proposed infiltration systems may have on nearby subterranean structures, open excavations, or descending slopes. In particular, infiltration systems should not be located near the crest of descending slopes, particularly where the slopes are comprised of granular soils. Such systems will require specialized design and analysis to evaluate the potential for slope instability, piping failures and other phenomena that typically apply to earthen dam design. This type of analysis is beyond the scope of this infiltration test report, but these factors should be considered by the infiltration system designer when locating the infiltration systems.

## **General Comments**

This report has been prepared as an instrument of service for use by the client in order to aid in the evaluation of this property and to assist the architects and engineers in the design and preparation of the project plans and specifications. This report may be provided to the contractor(s) and other design consultants to disclose information relative to the project. However, this report is not intended to be utilized as a specification in and of itself, without appropriate interpretation by the project architect, structural engineer, and/or civil engineer. The design of the proposed storm water infiltration system is the responsibility of the civil engineer. The role of the geotechnical engineer is limited to determination of infiltration rate only. By using the design infiltration rate contained herein, the civil engineer agrees to indemnify, defend, and hold harmless the geotechnical engineer for all aspects of the design and performance of the proposed storm water infiltration system. The reproduction and distribution of this report must be authorized by the client and Southern California Geotechnical, Inc. Furthermore, any reliance on this report by an unauthorized third party is at such party's sole risk, and we accept no responsibility for damage or loss which may occur.

The analysis of this site was based on a subsurface profile interpolated from limited discrete soil samples. While the materials encountered in the project area are considered to be representative of the total area, some variations should be expected between boring locations and testing depths. If the conditions encountered during construction vary significantly from those detailed herein, we should be contacted immediately to determine if the conditions alter the recommendations contained herein.

This report has been based on assumed or provided characteristics of the proposed development. It is recommended that the owner, client, architect, structural engineer, and civil engineer carefully review these assumptions to ensure that they are consistent with the characteristics of the proposed development. If discrepancies exist, they should be brought to our attention to verify that they do not affect the conclusions and recommendations contained herein. We also recommend that the project plans and specifications be submitted to our office for review to verify that our recommendations have been correctly interpreted. The analysis, conclusions, and recommendations contained within this report have been promulgated in accordance with generally accepted professional geotechnical engineering practice. No other warranty is implied or expressed.

### **Closure**

We sincerely appreciate the opportunity to be of service on this project. We look forward to providing additional consulting services during the course of the project. If we may be of further assistance in any manner, please contact our office.

Respectfully Submitted,


**SOUTHERN CALIFORNIA GEOTECHNICAL, INC.**

Oscar Sandoval  
Staff Engineer

Robert G. Trazo, GE 2655  
Principal Engineer




- Enclosures:
- Plate 1 - Site Location Map
  - Plate 2 - Infiltration Test Location Plan
  - Boring Log Legend and Logs (4 Pages)
  - Infiltration Test Results Spreadsheets (2 Pages)
  - Grain Size Analysis Graphs (2 Pages)





SOURCE: USGS TOPOGRAPHIC MAP OF THE RITTER RIDGE & PALMDALE QUADRANGLES, LOS ANGELES, CALIFORNIA, 2018.



<b>SITE LOCATION MAP</b>	
<b>PROPOSED WAREHOUSE</b>	
<b>PALMDALE, CALIFORNIA</b>	
SCALE: 1" = 2000'	 <b>SOUTHERN CALIFORNIA GEOTECHNICAL</b>
DRAWN: MD	
CHKD: RGT	
SCG PROJECT 22G109-2	
<b>PLATE 1</b>	



**GEOTECHNICAL LEGEND**

-  APPROXIMATE INFILTRATION TEST LOCATION
-  APPROXIMATE BORING LOCATION



NOTE: CONCEPTUAL SITE PLAN (SCHEME 1) PREPARED BY HPA, INC.  
AERIAL PHOTOGRAPH OBTAINED FROM GOOGLE EARTH (2018)

**INFILTRATION TEST LOCATION PLAN**

PROPOSED WAREHOUSE

PALMDALE, CALIFORNIA

SCALE: 1" = 100'

DRAWN: OS  
CHKD: RGT

SCG PROJECT  
22G109-2









PLATE 2



**SOUTHERN CALIFORNIA GEOTECHNICAL**



# BORING LOG LEGEND

SAMPLE TYPE	GRAPHICAL SYMBOL	SAMPLE DESCRIPTION
AUGER		SAMPLE COLLECTED FROM AUGER CUTTINGS, NO FIELD MEASUREMENT OF SOIL STRENGTH. (DISTURBED)
CORE		ROCK CORE SAMPLE: TYPICALLY TAKEN WITH A DIAMOND-TIPPED CORE BARREL. TYPICALLY USED ONLY IN HIGHLY CONSOLIDATED BEDROCK.
GRAB		SOIL SAMPLE TAKEN WITH NO SPECIALIZED EQUIPMENT, SUCH AS FROM A STOCKPILE OR THE GROUND SURFACE. (DISTURBED)
CS		CALIFORNIA SAMPLER: 2-1/2 INCH I.D. SPLIT BARREL SAMPLER, LINED WITH 1-INCH HIGH BRASS RINGS. DRIVEN WITH SPT HAMMER. (RELATIVELY UNDISTURBED)
NSR		NO RECOVERY: THE SAMPLING ATTEMPT DID NOT RESULT IN RECOVERY OF ANY SIGNIFICANT SOIL OR ROCK MATERIAL.
SPT		STANDARD PENETRATION TEST: SAMPLER IS A 1.4 INCH INSIDE DIAMETER SPLIT BARREL, DRIVEN 18 INCHES WITH THE SPT HAMMER. (DISTURBED)
SH		SHELBY TUBE: TAKEN WITH A THIN WALL SAMPLE TUBE, PUSHED INTO THE SOIL AND THEN EXTRACTED. (UNDISTURBED)
VANE		VANE SHEAR TEST: SOIL STRENGTH OBTAINED USING A 4 BLADED SHEAR DEVICE. TYPICALLY USED IN SOFT CLAYS-NO SAMPLE RECOVERED.

## COLUMN DESCRIPTIONS

### DEPTH:

Distance in feet below the ground surface.

### SAMPLE:

Sample Type as depicted above.

### BLOW COUNT:

Number of blows required to advance the sampler 12 inches using a 140 lb hammer with a 30-inch drop. 50/3" indicates penetration refusal (>50 blows) at 3 inches. WH indicates that the weight of the hammer was sufficient to push the sampler 6 inches or more.

### POCKET PEN.:

Approximate shear strength of a cohesive soil sample as measured by pocket penetrometer.

### GRAPHIC LOG:

Graphic Soil Symbol as depicted on the following page.

### DRY DENSITY:

Dry density of an undisturbed or relatively undisturbed sample in lbs/ft<sup>3</sup>.

### MOISTURE CONTENT:

Moisture content of a soil sample, expressed as a percentage of the dry weight.

### LIQUID LIMIT:

The moisture content above which a soil behaves as a liquid.

### PLASTIC LIMIT:

The moisture content above which a soil behaves as a plastic.

### PASSING #200 SIEVE:

The percentage of the sample finer than the #200 standard sieve.

### UNCONFINED SHEAR:

The shear strength of a cohesive soil sample, as measured in the unconfined state.

# SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS	
			GRAPH	LETTER		
<p><b>COARSE GRAINED SOILS</b></p> <p>MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE</p>	<p><b>GRAVEL AND GRAVELLY SOILS</b></p>	<p>CLEAN GRAVELS</p> <p>(LITTLE OR NO FINES)</p>		<b>GW</b>	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES	
		<p>MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE</p>	<p>GRAVELS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>GP</b>	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES, LITTLE OR NO FINES
			<p>GRAVELS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>GM</b>	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
		<p>MORE THAN 50% OF COARSE FRACTION PASSING ON NO. 4 SIEVE</p>	<p>CLEAN SANDS</p> <p>(LITTLE OR NO FINES)</p>		<b>SW</b>	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
	<p>MORE THAN 50% OF COARSE FRACTION PASSING ON NO. 4 SIEVE</p>		<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>SP</b>	POORLY-GRADED SANDS, GRAVELLY SAND, LITTLE OR NO FINES
		<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>SM</b>	SILTY SANDS, SAND - SILT MIXTURES	
	<p>SANDS WITH FINES</p> <p>(APPRECIABLE AMOUNT OF FINES)</p>		<b>SC</b>	CLAYEY SANDS, SAND - CLAY MIXTURES		
	<p><b>FINE GRAINED SOILS</b></p> <p>MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE</p>	<p><b>SILTS AND CLAYS</b></p> <p>LIQUID LIMIT LESS THAN 50</p>		<b>ML</b>	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY	
				<b>CL</b>	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS	
				<b>OL</b>	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY	
<p><b>SILTS AND CLAYS</b></p> <p>LIQUID LIMIT GREATER THAN 50</p>			<b>MH</b>	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS		
			<b>CH</b>	INORGANIC CLAYS OF HIGH PLASTICITY		
			<b>OH</b>	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS		
<p><b>HIGHLY ORGANIC SOILS</b></p>				<b>PT</b>	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS	

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS



JOB NO.: 22G109-2	DRILLING DATE: 1/25/22	WATER DEPTH: Dry
PROJECT: Proposed Warehouse	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: ---
LOCATION: Palmdale, California	LOGGED BY: Oscar Sandoval	READING TAKEN: At Completion

FIELD RESULTS				DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)		GRAPHIC LOG	DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	
SURFACE ELEVATION: --- MSL											
5	X	27		[Symbol]	ALLUVIUM: Gray Brown Silty fine Sand, trace medium Sand, medium dense-damp		5				
10	X	28		[Symbol]	Light Brown Silty fine to medium Sand, trace coarse Sand, trace fine Gravel, medium dense-dry to damp		3		14		
Boring Terminated at 10'											

TBL\_22G109-2.GPJ\_SOCALGEO.GDT\_3/9/22



JOB NO.: 22G109-2	DRILLING DATE: 1/25/22	WATER DEPTH: Dry
PROJECT: Proposed Warehouse	DRILLING METHOD: Hollow Stem Auger	CAVE DEPTH: ---
LOCATION: Palmdale, California	LOGGED BY: Oscar Sandoval	READING TAKEN: At Completion

FIELD RESULTS				GRAPHIC LOG	DESCRIPTION	LABORATORY RESULTS						COMMENTS
DEPTH (FEET)	SAMPLE	BLOW COUNT	POCKET PEN. (TSF)			DRY DENSITY (PCF)	MOISTURE CONTENT (%)	LIQUID LIMIT	PLASTIC LIMIT	PASSING #200 SIEVE (%)	ORGANIC CONTENT (%)	
SURFACE ELEVATION: --- MSL												
5	X	11			<u>ALLUVIUM</u> : Light Brown to Brown Silty fine to medium Sand, trace coarse Sand, medium dense-dry to damp		3					
10	X	10			Light Brown Silty fine to medium Sand, little coarse Sand, trace fine Gravel, medium dense-dry		2		13			
Boring Terminated at 10'												

TBL 22G109-2.GPJ\_SOCALGEO.GDT 3/9/22

# INFILTRATION CALCULATIONS

Project Name	Proposed Warehouse
Project Location	Palmdale, CA
Project Number	22G109-2
Engineer	CB

Test Hole Radius	3.00 (in)
Test Depth	10.20 (ft)

Infiltration Test Hole: I-1

Start Time for Pre-Soak	8:40am	Water Remaining in Boring (Y/N)	Y
Start Time for Standard	9:10am	Time Interval Between Readings	30min

Interval Number		Time	Time Interval (min)	Water Depth (ft)	Change in Water Level (ft)	Average Head Height (ft)	Measured Infiltration Rate Q (in/hr)	Reduction Factor (RF)	Design Infiltration Rate Q (in/hr)
1	Initial	9:10 AM	30.0	7.20	0.55	2.7	0.6	3.0	0.2
	Final	9:40 AM		7.75					
2	Initial	9:40 AM	30.0	7.20	0.56	2.7	0.6	3.0	0.2
	Final	10:10 AM		7.76					
3	Initial	10:10 AM	30.0	7.20	0.55	2.7	0.6	3.0	0.2
	Final	10:40 AM		7.75					
4	Initial	10:40 AM	30.0	7.20	0.56	2.7	0.6	3.0	0.2
	Final	11:10 AM		7.76					
5	Initial	11:10 AM	30.0	7.20	0.55	2.7	0.6	3.0	0.2
	Final	11:40 AM		7.75					
6	Initial	11:40 AM	30.0	7.20	0.56	2.7	0.6	3.0	0.2
	Final	12:10 PM		7.76					

Design Infiltration Rate = (Measured Infiltration Rate)/(Reduction Factor)

Reduction Factor (RF) = RF<sub>t</sub>+RF<sub>v</sub>+RF<sub>s</sub>

Reduction Factors	
Double-ring Infiltrometer	RF <sub>t</sub> = 1 to 3
Shallow Test Pit	
Small Diameter Boring	
Large Diameter Boring	
High Flow-rate	RF <sub>t</sub> = 3
Grain Size Analysis Method	RF <sub>t</sub> = 2 to 3
Site variability, number of tests and thoroughness of subsurface investigation	RF <sub>v</sub> = 1 to 3
Long-term siltation, plugging, and maintenance	RF <sub>s</sub> = 1 to 3

$$Q = \frac{\Delta H(60r)}{\Delta t(r + 2H_{avg})}$$

- Where:
- Q = Measured Infiltration Rate (in inches per hour)
  - ΔH = Change in Height (Water Level) over the time interval
  - r = Test Hole (Borehole) Radius
  - Δt = Time Interval
  - H<sub>avg</sub> = Average Head Height over the time interval

## INFILTRATION CALCULATIONS

Project Name	Proposed Warehouse
Project Location	Palmdale, CA
Project Number	22G109-2
Engineer	CB

Test Hole Radius	3.00 (in)
Test Depth	10.20 (ft)

Infiltration Test Hole: I-2

Start Time for Pre-Soak	9:00am	Water Remaining in Boring (Y/N)	Y
Start Time for Standard	9:30am	Time Interval Between Readings	30min

Interval Number		Time	Time Interval (min)	Water Depth (ft)	Change in Water Level (ft)	Average Head Height (ft)	Measured Infiltration Rate Q (in/hr)	Reduction Factor (RF)	Design Infiltration Rate Q (in/hr)
1	Initial	9:30 AM	30.0	8.00	0.80	1.8	1.2	3.0	0.4
	Final	10:00 AM		8.80					
2	Initial	10:00 AM	30.0	8.00	0.81	1.8	1.3	3.0	0.4
	Final	10:30 AM		8.81					
3	Initial	10:30 AM	30.0	8.00	0.80	1.8	1.2	3.0	0.4
	Final	11:00 AM		8.80					
4	Initial	11:00 AM	30.0	8.00	0.81	1.8	1.3	3.0	0.4
	Final	11:30 AM		8.81					
5	Initial	11:30 AM	30.0	8.00	0.81	1.8	1.3	3.0	0.4
	Final	12:00 PM		8.81					
6	Initial	12:00 PM	30.0	8.00	0.80	1.8	1.2	3.0	0.4
	Final	12:30 PM		8.80					

Design Infiltration Rate = (Measured Infiltration Rate)/(Reduction Factor)


Reduction Factor (RF) =  $RF_t + RF_v + RF_s$

Reduction Factors	
Double-ring Infiltrometer	$RF_t = 1 \text{ to } 3$
Shallow Test Pit	
Small Diameter Boring	
Large Diameter Boring	
High Flow-rate	$RF_t = 3$
Grain Size Analysis Method	$RF_t = 2 \text{ to } 3$
Site variability, number of tests and thoroughness of subsurface investigation	$RF_v = 1 \text{ to } 3$
Long-term siltation, plugging, and maintenance	$RF_s = 1 \text{ to } 3$

$$Q = \frac{\Delta H(60r)}{\Delta t(r + 2H_{avg})}$$

Where: Q = Measured Infiltration Rate (in inches per hour)  
 ΔH = Change in Height (Water Level) over the time interval  
 r = Test Hole (Borehole) Radius  
 Δt = Time Interval  
 H<sub>avg</sub> = Average Head Height over the time interval

# Grain Size Distribution




Sample Description	I-1 @ 8½'
Soil Classification	Light Brown Silty fine to medium Sand, trace coarse Sand, trace fine Gravel

Proposed Warehouse  
 Palmdale, CA  
 Project No. 22G109-2  
**PLATE C- 1**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
A California Corporation

# Grain Size Distribution



Sample Description	I-2 @ 8½'
Soil Classification	Light Brown Silty fine to medium Sand, trace coarse Sand, trace fine Gravel

Proposed Warehouse  
 Palmdale, CA  
 Project No. 22G109-2  
**PLATE C- 2**



**SOUTHERN CALIFORNIA GEOTECHNICAL**  
*A California Corporation*