Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: 2023010087

Project Title: Tudor Flood Risk Reduction Project

Lead Agency: Sutter Butte Flood Control Agency

Contact Name: Michael Bessette

Email: m.bessette@sutterbutteflood.org Phone Number: 530-755-9859

Project Location: Nicolaus (*City*) Sutter (*County*)

Project Decription (Proposed actions, location, and/or consequences).

Planned levee remedial measures for the Project include construction of a cutoff wall, a berm tie-in to the HWY 99 embankment, pipe penetration improvements, and surficial geometry corrections. Improvement measures were developed based on the 100-year design water surface elevation (DWSE) provided in Design Water Surface Profiles for the Feather River West Levee Project, Addendum #2, dated December 2013 and prepared by Peterson Brustad, Inc. Fill material for the levee and clay core would be obtained from either an off-site borrow source(s) or from excess material obtained from Project excavations. The construction contractor will be required to obtain off-site borrow materials, which may be imported to the Project Area from local sources or existing permitted commercial sources. Borrow sources for earthen materials are anticipated to be in the vicinity of Sutter and Yuba Counties. Other materials, such as aggregate base, bentonite for the cutoff wall, pipe, concrete products, and materials needed to support construction, would be obtained from off-site commercial vendors and sources.

The Project incorporates construction areas along the land and water sides of the levee. These areas would be utilized by the contractor for access, hauling, spoiling of material, storage, fueling, and other construction related activities. Prior to and during construction of remedial measures, staging areas would be established to allow for efficient use and distribution of materials and equipment. Staging areas would be identified by the contractor during construction and would be located within the Project Area limits.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Aesthetics - Lighting, Implement a Community Outreach Program
Air Quality - CARB Tier 4 Certified Equipment
Biological Resources - Erosion Control, Floristic Preconstruction Surveys, Special Status Fish Avoidance, Northwestern Pond Turtle Preconstruction Surveys, Giant Garter Snake Preconstruction Surveys, Special-Status Bird Preconstruction Surveys, Bat Habitat Assessment, Section 1602 Streambed Alteration Agreement, Section 404 and Section 401 Permits
Cultural Resources - Archaeological Monitoring, Post-Review Discoveries,
Geology and Soils - Unanticipated Discovery of Paleontological Resources
Hazards and Hazardous Materials - Avoid Feather River
Noise - Haul Truck Hours
Transportation - Emergency Evacuations
Tribal Cultural Resources - Geoarchaeological Profiling, Develop a Burial Treatment Agreement, Cultural Sensitivity Training, Tribal Monitoring, Discoveries, Slow Degrade, Human Remains, Recovery, Treatment Storage and Reburial of Native American Cultural Items and Soils, Documentation of Finds, Mitigation

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None known.

Provide a list of the responsible or trustee agencies for the project.

Federal, state, and local agencies that would serve as either responsible or trustee agencies for the proposed Project include: Air Resources Board, California Emergency Management Agency, California Highway Patrol, Caltrans District 3, Department of Conservation, CDFW Region 2, Native American Heritage Commission, Office of Historic Preservation, Public Utilities Commission, RWQCB Region 5, State Lands Commission, SWRCB, Department of Toxic Substances Control, Department of Water Resources, U.S. Army Corps of Engineers, NOAA National Marine Fisheries Service (NMFS), U.S. Fish and Wildlife Service (USFWS).