

Appendix D Air Quality and Greenhouse Emissions Data

Appendices

This page intentionally left blank.

Air Quality and Greenhouse Gas Appendix

Emissions Worksheet

Regional Construction Emissions Worksheet:

Phase 1							
3.1. Phase 1 Building Demolition (2023)							
		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite		Summer					
	Off-Road Equipment	0.45	4.88	7.03	0.01	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.45	4.88	7.03	0.01	0.23	0.21
Offsite							
	Worker	0.06	0.07	1.02	0.00	0.16	0.04
	Vendor	0.01	0.32	0.16	0.01	0.07	0.02
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.39	1.18	0.01	0.23	0.06
TOTAL		0.52	5.27	8.21	0.02	0.46	0.27
Onsite		Winter					
	Off-Road Equipment	0.04	0.45	0.66	0.01	0.02	0.02
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.45	0.66	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.08	0.00	0.02	0.01
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.09	0.01	0.03	0.01
TOTAL		0.06	0.49	0.75	0.01	0.05	0.03
Onsite							
	Off-Road	0.45	4.88	7.03	0.01	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.45	4.88	7.03	0.01	0.23	0.21
Offsite							
	Worker	0.06	0.07	1.02	0.00	0.16	0.04
	Vendor	0.01	0.32	0.16	0.01	0.07	0.02
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.39	1.18	0.01	0.23	0.06
TOTAL		0.52	5.27	8.21	0.02	0.46	0.27
3.3. Building Demolition Debris Hauling (2023)							
		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.21	0.03
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.37	0.14	0.01	0.08	0.02
	Total	0.01	0.37	0.14	0.01	0.08	0.02
TOTAL		0.01	0.37	0.14	0.01	0.29	0.05
Onsite		Winter					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.02	0.01
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.04	0.01	0.01	0.01	0.01
	Total	0.01	0.04	0.01	0.01	0.01	0.01
TOTAL		0.01	0.04	0.01	0.01	0.03	0.01
Onsite							
	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.21	0.03
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.37	0.14	0.01	0.08	0.02
	Total	0.01	0.37	0.14	0.01	0.08	0.02
TOTAL		0.01	0.37	0.14	0.01	0.29	0.05

3.5. Phase 1 Asphalt Demolition (2023)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
		Summer					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
		Winter					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00

3.7. Phase 1 Asphalt Demolition Debris Haul (2023)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
		Summer					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.21	0.03
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.18	0.07	0.01	0.04	0.01
	Total	0.01	0.18	0.07	0.01	0.04	0.01
TOTAL		0.01	0.18	0.07	0.01	0.25	0.04
		Winter					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.02	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.02	0.01	0.01	0.01	0.01
	Total	0.01	0.02	0.01	0.01	0.01	0.01
TOTAL		0.01	0.02	0.01	0.01	0.03	0.01
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.21	0.03
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.18	0.07	0.01	0.04	0.01
	Total	0.01	0.18	0.07	0.01	0.04	0.01
TOTAL		0.01	0.18	0.07	0.01	0.25	0.04

3.9. Phase 1 Site Preparation (2023)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	0.65	6.03	8.67	0.01	0.29	0.27
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.65	6.03	8.67	0.01	0.29	0.27
Offsite							
	Worker	0.06	0.07	1.02	0.00	0.16	0.04
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.47	1.22	0.01	0.25	0.07
TOTAL		0.72	6.50	9.89	0.02	0.54	0.34
		Winter					
Onsite							
	Off-Road Equipment	0.01	0.07	0.10	0.01	0.01	0.01
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.07	0.10	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.02	0.01	0.01	0.01
TOTAL		0.02	0.08	0.12	0.01	0.02	0.02
		Summer					
Onsite							
	Off-Road	0.65	6.03	8.67	0.01	0.29	0.27
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.65	6.03	8.67	0.01	0.29	0.27
Offsite							
	Hauling	0.06	0.07	1.02	0.00	0.16	0.04
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.47	1.22	0.01	0.25	0.07
TOTAL		0.72	6.50	9.89	0.02	0.54	0.34

3.11. Phase 1 Rough Grading (2023)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	1.78	17.50	16.30	0.02	0.83	0.77
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.78	17.50	16.30	0.02	3.59	2.11
Offsite							
	Worker	0.05	0.05	0.82	0.00	0.13	0.03
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.45	1.02	0.01	0.22	0.06
TOTAL		1.84	17.95	17.32	0.03	3.81	2.17
		Winter					
Onsite							
	Off-Road Equipment	0.03	0.34	0.31	0.01	0.02	0.01
	Dust From Material Movement	0.00	0.00	0.00	0.00	0.05	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.34	0.31	0.01	0.07	0.04
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
TOTAL		0.04	0.36	0.33	0.01	0.08	0.05
		Summer					
Onsite							
	Off-Road Equipment	1.78	17.50	16.30	0.02	0.83	0.77
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.78	17.50	16.30	0.02	3.59	2.11
Offsite							
	Worker	0.05	0.05	0.82	0.00	0.13	0.03
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.45	1.02	0.01	0.22	0.06
TOTAL		1.84	17.95	17.32	0.03	3.81	2.17

3.13. Phase 1 Fine Grading (2023)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite	Summer						
	Off-Road Equipment	1.78	17.50	16.30	0.02	0.83	0.77
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.78	17.50	16.30	0.02	3.59	2.11
Offsite	Worker	0.05	0.05	0.82	0.00	0.13	0.03
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.45	1.02	0.01	0.22	0.06
	TOTAL	1.84	17.95	17.32	0.03	3.81	2.17
Onsite	Winter						
	Off-Road Equipment	0.03	0.29	0.27	0.01	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.00	0.00	0.05	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.29	0.27	0.01	0.06	0.03
Offsite	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
	TOTAL	0.04	0.31	0.29	0.01	0.07	0.04
Onsite	Summer						
	Off-Road Equipment	1.78	17.50	16.30	0.02	0.83	0.77
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.78	17.50	16.30	0.02	3.59	2.11
Offsite	Worker	0.05	0.05	0.82	0.00	0.13	0.03
	Vendor	0.01	0.40	0.20	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.45	1.02	0.01	0.22	0.06
	TOTAL	1.84	17.95	17.32	0.03	3.81	2.17

3.15. Phase 1 Building Construction (2023)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite	Summer						
	Off-Road Equipment	1.19	9.81	10.20	0.02	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.19	9.81	10.20	0.02	0.41	0.38
Offsite	Worker	0.05	0.05	0.84	0.00	0.13	0.03
	Vendor	0.01	0.16	0.08	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.21	0.92	0.01	0.17	0.04
	TOTAL	1.25	10.02	11.12	0.03	0.58	0.42
Onsite	Winter						
	Off-Road Equipment	1.19	9.81	10.20	0.02	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.19	9.81	10.20	0.02	0.41	0.38
Offsite	Worker	0.01	0.02	0.18	0.00	0.03	0.01
	Vendor	0.01	0.04	0.02	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.06	0.20	0.01	0.04	0.02
	TOTAL	1.21	9.87	10.40	0.03	0.45	0.40
Onsite	Summer						
	Off-Road Equipment	1.19	9.81	10.20	0.02	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.19	9.81	10.20	0.02	0.41	0.38
Offsite	Worker	0.05	0.05	0.84	0.00	0.13	0.03
	Vendor	0.01	0.16	0.08	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.21	0.92	0.01	0.17	0.04
	TOTAL	1.25	10.02	11.12	0.03	0.58	0.42

3.17. Phase 1 Building Construction (2024)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.13	9.44	10.10	0.02	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.13	9.44	10.10	0.02	0.37	0.34
Offsite							
	Worker	0.05	0.05	0.77	0.00	0.13	0.03
	Vendor	0.01	0.15	0.07	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.20	0.84	0.01	0.17	0.04
TOTAL		1.19	9.64	10.94	0.03	0.54	0.38
Onsite		Winter					
	Off-Road Equipment	1.13	9.44	10.10	0.02	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.13	9.44	10.10	0.02	0.37	0.34
Offsite							
	Worker	0.05	0.06	0.65	0.00	0.13	0.03
	Vendor	0.01	0.16	0.08	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.22	0.73	0.01	0.17	0.04
TOTAL		1.19	9.66	10.83	0.03	0.54	0.38
Onsite							
	Off-Road Equipment	1.13	9.44	10.10	0.02	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.13	9.44	10.10	0.02	0.37	0.34
Offsite							
	Worker	0.05	0.06	0.77	0.00	0.13	0.03
	Vendor	0.01	0.16	0.08	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.22	0.84	0.01	0.17	0.04
TOTAL		1.19	9.66	10.94	0.03	0.54	0.38

3.19. Phase 1 Paving (2024)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.38	3.32	4.84	0.01	0.15	0.14
	Paving	0.15	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.53	3.32	4.84	0.01	0.15	0.14
Offsite							
	Worker	0.03	0.04	0.48	0.00	0.10	0.02
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.04	0.48	0.00	0.10	0.02
TOTAL		0.56	3.36	5.32	0.01	0.25	0.16
Onsite							
	Off-Road Equipment	0.38	3.32	4.84	0.01	0.15	0.14
	Paving	0.15	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.53	3.32	4.84	0.01	0.15	0.14
Offsite							
	Worker	0.03	0.04	0.48	0.00	0.10	0.02
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.04	0.48	0.00	0.10	0.02
TOTAL		0.56	3.36	5.32	0.01	0.25	0.16

3.21. Phase 1 Architectural Coating (2024)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.20	1.60	1.05	0.01	0.07	0.06
	Architectural Coatings	7.79	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	7.99	1.60	1.05	0.01	0.07	0.06
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.00	0.01	0.01
TOTAL		8.00	1.61	1.06	0.01	0.08	0.07
Onsite							
	Off-Road Equipment	0.20	1.60	1.05	0.01	0.07	0.06
	Architectural Coatings	7.79	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	7.99	1.60	1.05	0.01	0.07	0.06
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.00	0.01	0.01
TOTAL		8.00	1.61	1.06	0.01	0.08	0.07

3.23. Phase 1 Utilities Trenching (2023)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.11	0.87	1.02	0.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.11	0.87	1.02	0.01	0.03	0.03
Offsite							
	Worker	0.01	0.01	0.20	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.20	0.00	0.03	0.01
TOTAL		0.12	0.88	1.22	0.01	0.06	0.04
Onsite		Winter					
	Off-Road Equipment	0.01	0.01	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.00	0.01	0.01
TOTAL		0.01	0.02	0.02	0.01	0.01	0.01
Onsite							
	Off-Road Equipment	0.11	0.87	1.02	0.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.11	0.87	1.02	0.01	0.03	0.03
Offsite							
	Worker	0.01	0.01	0.20	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.20	0.00	0.03	0.01
TOTAL		0.12	0.88	1.22	0.01	0.06	0.04

3.25. Phase 1 Finishing/Landscaping (2024)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.10	0.84	1.01	0.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.10	0.84	1.01	0.01	0.03	0.03
Offsite							
	Worker	0.01	0.01	0.16	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.16	0.00	0.03	0.01
TOTAL		0.11	0.85	1.17	0.01	0.06	0.04
Onsite							
	Off-Road Equipment	0.10	0.84	1.01	0.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.10	0.84	1.01	0.01	0.03	0.03
Offsite							
	Worker	0.01	0.01	0.16	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.16	0.00	0.03	0.01
TOTAL		0.11	0.85	1.17	0.01	0.06	0.04

Phase 2

3.2. Phase 2 Building Demolition (2025)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite		Summer					
	Off-Road Equipment	0.58	5.61	8.82	0.01	0.23	0.21
	Demolition					0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.58	5.61	8.82	0.01	0.23	0.21
Offsite							
	Worker	0.06	0.06	1.04	0.00	0.01	0.00
	Vendor	0.01	0.29	0.14	0.01	0.02	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.35	1.18	0.01	0.03	0.01
TOTAL		0.65	5.96	10.00	0.02	0.26	0.22
Onsite		Winter					
	Off-Road Equipment	0.05	0.46	0.73	0.01	0.02	0.02
	Demolition					0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.46	0.73	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.08	0.00	0.01	0.00
	Vendor	0.01	0.02	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.03	0.09	0.01	0.01	0.01
TOTAL		0.07	0.49	0.82	0.01	0.03	0.03
Onsite							
	Off-Road	0.58	5.61	8.82	0.01	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.58	5.61	8.82	0.01	0.23	0.21
Offsite							
	Worker	0.06	0.06	1.04	0.00	0.01	0.00
	Vendor	0.01	0.29	0.14	0.01	0.02	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.07	0.35	1.18	0.01	0.03	0.01
TOTAL		0.65	5.96	10.00	0.02	0.26	0.22

3.3. Building Demolition Debris Hauling (2025)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
		Summer					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition					0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.01	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.09	0.03	0.01	0.01	0.01
	Total	0.01	0.09	0.03	0.01	0.01	0.01
TOTAL		0.01	0.09	0.03	0.01	0.02	0.01
		Winter					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition					0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.01	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.01	0.01	0.01	0.01	0.01
	Total	0.01	0.01	0.01	0.01	0.01	0.01
TOTAL		0.01	0.01	0.01	0.01	0.01	0.01
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.01	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.09	0.03	0.01	0.01	0.01
	Total	0.01	0.09	0.03	0.01	0.01	0.01
TOTAL		0.01	0.09	0.03	0.01	0.02	0.01

3.5. Phase 2 Asphalt Demolition (2025)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
		Summer					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
		Winter					
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00

3.7. Phase 2 Asphalt Demolition Debris Haul (2025)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite	Summer						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition					0.50	0.08
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.50	0.08
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.34	0.13	0.01	0.02	0.01
	Total	0.01	0.34	0.13	0.01	0.02	0.01
TOTAL		0.01	0.34	0.13	0.01	0.52	0.09
Onsite	Winter						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition					0.04	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.04	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.03	0.01	0.01	0.01	0.01
	Total	0.01	0.03	0.01	0.01	0.01	0.01
TOTAL		0.01	0.03	0.01	0.01	0.05	0.02
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.50	0.08
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.50	0.08
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.34	0.13	0.01	0.02	0.01
	Total	0.01	0.34	0.13	0.01	0.02	0.01
TOTAL		0.01	0.34	0.13	0.01	0.52	0.09

3.9. Phase 2 Site Preparation (2025)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5 Total
Onsite	Summer						
	Off-Road Equipment	0.57	5.29	8.63	0.01	0.21	0.19
	Demolition					0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.57	5.29	8.63	0.01	0.21	0.19
Offsite	Worker	0.05	0.05	0.87	0.00	0.01	0.00
	Vendor	0.01	0.36	0.18	0.01	0.02	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.41	1.05	0.01	0.03	0.01
TOTAL		0.63	5.70	9.68	0.02	0.24	0.20
Onsite	Winter						
	Off-Road Equipment	0.01	0.07	0.12	0.01	0.01	0.01
	Demolition					0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.07	0.12	0.01	0.01	0.01
Offsite	Worker	0.01	0.01	0.01	0.00	0.01	0.00
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
TOTAL		0.02	0.09	0.14	0.01	0.02	0.01
Onsite	Off-Road	0.57	5.29	8.63	0.01	0.21	0.19
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.57	5.29	8.63	0.01	0.21	0.19
Offsite	Hauling	0.05	0.05	0.87	0.00	0.01	0.00
	Vendor	0.01	0.36	0.18	0.01	0.02	0.01
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.41	1.05	0.01	0.03	0.01
TOTAL		0.63	5.70	9.68	0.02	0.24	0.20

3.11. Phase 2 Rough Grading (2025)							
		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.51	14.10	14.50	0.02	0.64	0.59
	Onsite truck					2.76	1.34
	Total	1.51	14.10	14.50	0.02	3.40	1.93
Offsite	Worker	0.04	0.04	0.70	0.00	0.01	0.00
	Vendor	0.01	0.36	0.18	0.01	0.02	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.40	0.88	0.01	0.03	0.01
TOTAL		1.56	14.50	15.38	0.03	3.43	1.94
Onsite		Winter					
	Off-Road Equipment	0.04	0.35	0.36	0.01	0.02	0.01
	Onsite truck					0.07	0.03
	Total	0.04	0.35	0.36	0.01	0.09	0.04
Offsite	Worker	0.01	0.01	0.02	0.00	0.01	0.00
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.03	0.01	0.01	0.01
TOTAL		0.05	0.37	0.39	0.01	0.10	0.05
Onsite	Off-Road Equipment	1.51	14.10	14.50	0.02	0.64	0.59
	Onsite truck	0.00	0.00	0.00	0.00	2.76	1.34
	Total	1.51	14.10	14.50	0.02	3.40	1.93
	Offsite	Worker	0.04	0.04	0.70	0.00	0.01
Vendor		0.01	0.36	0.18	0.01	0.02	0.01
Hauling		0.00	0.00	0.00	0.00	0.00	0.00
Total		0.05	0.40	0.88	0.01	0.03	0.01
TOTAL		1.56	14.50	15.38	0.03	3.43	1.94

3.13. Phase 2 Fine Grading (2025)							
		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.51	14.10	14.50	0.02	0.64	0.59
	Onsite truck					2.76	1.34
	Total	1.51	14.10	14.50	0.02	3.40	1.93
Offsite	Worker	0.04	0.04	0.70	0.00	0.01	0.00
	Vendor	0.01	0.36	0.18	0.01	0.02	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.40	0.88	0.01	0.03	0.01
TOTAL		1.56	14.50	15.38	0.03	3.43	1.94
Onsite		Winter					
	Off-Road Equipment	0.03	0.31	0.32	0.01	0.01	0.01
	Onsite truck					0.06	0.03
	Total	0.03	0.31	0.32	0.01	0.07	0.04
Offsite	Worker	0.01	0.01	0.01	0.00	0.01	0.00
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
TOTAL		0.04	0.33	0.34	0.01	0.08	0.05
Onsite	Off-Road Equipment	1.51	14.10	14.50	0.02	0.64	0.59
	Onsite truck	0.00	0.00	0.00	0.00	2.76	1.34
	Total	1.51	14.10	14.50	0.02	3.40	1.93
	Offsite	Worker	0.04	0.04	0.70	0.00	0.01
Vendor		0.01	0.36	0.18	0.01	0.02	0.01
Hauling		0.00	0.00	0.00	0.00	0.00	0.00
Total		0.05	0.40	0.88	0.01	0.03	0.01
TOTAL		1.56	14.50	15.38	0.03	3.43	1.94

3.15. Phase 2 Building Construction (2025)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.24	10.60	11.90	0.02	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.24	10.60	11.90	0.02	0.40	0.37
Offsite							
	Worker	0.01	0.01	0.13	0.00	0.01	0.00
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.14	0.01	0.01	0.01
TOTAL		1.26	10.64	12.04	0.03	0.41	0.38
Onsite		Winter					
	Off-Road Equipment	1.24	10.60	11.90	0.02	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.24	10.60	11.90	0.02	0.40	0.37
Offsite							
	Worker	0.01	0.01	0.11	0.00	0.01	0.00
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.12	0.01	0.01	0.01
TOTAL		1.26	10.64	12.02	0.03	0.41	0.38
Onsite		Summer					
	Off-Road Equipment	1.24	10.60	11.90	0.02	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.24	10.60	11.90	0.02	0.40	0.37
Offsite							
	Worker	0.01	0.01	0.13	0.00	0.01	0.00
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.14	0.01	0.01	0.01
TOTAL		1.26	10.64	12.04	0.03	0.41	0.38

3.17. Phase 2 Building Construction (2026)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.18	10.10	11.80	0.02	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.18	10.10	11.80	0.02	0.36	0.33
Offsite							
	Worker	0.01	0.01	0.12	0.00	0.01	0.00
	Vendor	0.01	0.02	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.03	0.13	0.01	0.01	0.01
TOTAL		1.20	10.13	11.93	0.03	0.37	0.34
Onsite		Winter					
	Off-Road Equipment	1.18	10.10	11.80	0.02	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.18	10.10	11.80	0.02	0.36	0.33
Offsite							
	Worker	0.01	0.01	0.10	0.00	0.01	0.00
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.11	0.01	0.01	0.01
TOTAL		1.20	10.14	11.91	0.03	0.37	0.34
Onsite		Summer					
	Off-Road Equipment	1.18	10.10	11.80	0.02	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.18	10.10	11.80	0.02	0.36	0.33
Offsite							
	Worker	0.01	0.01	0.12	0.00	0.01	0.00
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.13	0.01	0.01	0.01
TOTAL		1.20	10.14	11.93	0.03	0.37	0.34

3.19. Phase 2 Paving (2026)							
		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.33	2.94	4.80	0.01	0.11	0.10
	Paving	0.01					
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.34	2.94	4.80	0.01	0.11	0.10
Offsite							
	Worker	0.03	0.03	0.41	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.03	0.41	0.00	0.01	0.00
TOTAL		0.37	2.97	5.21	0.01	0.12	0.10
Onsite							
	Off-Road Equipment	0.33	2.94	4.80	0.01	0.11	0.10
	Paving	0.01	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.34	2.94	4.80	0.01	0.11	0.10
Offsite							
	Worker	0.03	0.03	0.41	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.03	0.41	0.00	0.01	0.00
TOTAL		0.37	2.97	5.21	0.01	0.12	0.10

3.21. Phase 2 Architectural Coating (2026)							
		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.12	0.86	1.13	0.01	0.02	0.02
	Architectural Coatings	2.67					
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	2.79	0.86	1.13	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.06	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.06	0.00	0.01	0.00
TOTAL		2.80	0.87	1.19	0.01	0.03	0.02
Onsite							
	Off-Road Equipment	0.12	0.86	1.13	0.01	0.02	0.02
	Architectural Coatings	2.67	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	2.79	0.86	1.13	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.06	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.06	0.00	0.01	0.00
TOTAL		2.80	0.87	1.19	0.01	0.03	0.02

3.23. Phase 2 Utilities Trenching (2025)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.10	0.83	1.02	0.01	0.03	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.10	0.83	1.02	0.01	0.03	0.02
Offsite							
	Worker	0.01	0.01	0.17	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.17	0.00	0.01	0.00
TOTAL		0.11	0.84	1.19	0.01	0.04	0.02
Onsite		Winter					
	Off-Road Equipment	0.01	0.01	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.00	0.01	0.00
TOTAL		0.01	0.02	0.02	0.01	0.01	0.01
Onsite							
	Off-Road Equipment	0.10	0.83	1.02	0.01	0.03	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.10	0.83	1.02	0.01	0.03	0.02
Offsite							
	Worker	0.01	0.01	0.17	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.17	0.00	0.01	0.00
TOTAL		0.11	0.84	1.19	0.01	0.04	0.02

3.25. Phase 2 Finishing/Landscaping (2026)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.09	0.82	1.02	0.01	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.09	0.82	1.02	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.14	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.14	0.00	0.01	0.00
TOTAL		0.10	0.83	1.16	0.01	0.03	0.02
Onsite							
	Off-Road Equipment	0.09	0.82	1.02	0.01	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.09	0.82	1.02	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.14	0.00	0.01	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.14	0.00	0.01	0.00
TOTAL		0.10	0.83	1.16	0.01	0.03	0.02

Phase 3

3.1. Phase 3 Building Demolition (2028)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite	Summer						
	Off-Road Equipment	0.50	4.86	8.83	0.01	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.50	4.86	8.83	0.01	0.14	0.13
Offsite	Worker	0.05	0.05	0.85	0.00	0.20	0.05
	Vendor	0.01	0.25	0.12	0.01	0.07	0.02
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.30	0.97	0.01	0.27	0.07
TOTAL		0.56	5.16	9.80	0.02	0.41	0.20
Onsite	Winter						
	Off-Road Equipment	0.05	0.52	0.94	0.01	0.02	0.01
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.52	0.94	0.01	0.02	0.01
Offsite	Worker	0.01	0.01	0.08	0.00	0.02	0.01
	Vendor	0.01	0.03	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.04	0.09	0.01	0.03	0.01
TOTAL		0.07	0.56	1.03	0.01	0.05	0.02
Onsite	Summer						
	Off-Road	0.50	4.86	8.83	0.01	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.50	4.86	8.83	0.01	0.14	0.13
Offsite	Worker	0.05	0.05	0.85	0.00	0.20	0.05
	Vendor	0.01	0.25	0.12	0.01	0.07	0.02
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.06	0.30	0.97	0.01	0.27	0.07
TOTAL		0.56	5.16	9.80	0.02	0.41	0.20

3.3. Building Demolition Debris Hauling (2028)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite	Summer						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.59	0.09
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.59	0.09
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.15	0.06	0.01	0.04	0.01
	Total	0.01	0.15	0.06	0.01	0.04	0.01
TOTAL		0.01	0.15	0.06	0.01	0.63	0.10
Onsite	Winter						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.06	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.06	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.02	0.01	0.01	0.01	0.01
	Total	0.01	0.02	0.01	0.01	0.01	0.01
TOTAL		0.01	0.02	0.01	0.01	0.07	0.02
Onsite	Summer						
	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.59	0.09
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.59	0.09
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.15	0.06	0.01	0.04	0.01
	Total	0.01	0.15	0.06	0.01	0.04	0.01
TOTAL		0.01	0.15	0.06	0.01	0.63	0.10

3.5. Phase 3 Asphalt Demolition (2028)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite	Summer						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite	Winter						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00

3.7. Phase 3 Asphalt Demolition Debris Haul (2028)

		ROG	NOx	CO	SO ₂	PM10 Total	PM2.5Total
Onsite	Summer						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.15	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.15	0.02
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.15	0.06	0.01	0.04	0.01
	Total	0.01	0.15	0.06	0.01	0.04	0.01
TOTAL		0.01	0.15	0.06	0.01	0.19	0.03
Onsite	Winter						
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.02	0.01
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.02	0.01	0.01	0.01	0.01
	Total	0.01	0.02	0.01	0.01	0.01	0.01
TOTAL		0.01	0.02	0.01	0.01	0.03	0.01
Onsite	Off-Road	0.00	0.00	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00	0.15	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.15	0.02
Offsite	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.01	0.15	0.06	0.01	0.04	0.01
	Total	0.01	0.15	0.06	0.01	0.04	0.01
TOTAL		0.01	0.15	0.06	0.01	0.19	0.03

3.9. Phase 3 Site Preparation (2028)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	0.50	4.68	8.65	0.01	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.50	4.68	8.65	0.01	0.14	0.13
Offsite							
	Worker	0.04	0.04	0.71	0.00	0.16	0.04
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.35	0.86	0.01	0.25	0.07
TOTAL		0.55	5.03	9.51	0.02	0.39	0.20
		Winter					
Onsite							
	Off-Road Equipment	0.01	0.05	0.09	0.01	0.01	0.01
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.05	0.09	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.02	0.01	0.01	0.01
TOTAL		0.02	0.06	0.11	0.01	0.02	0.02
		Summer					
Onsite							
	Off-Road	0.50	4.68	8.65	0.01	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.50	4.68	8.65	0.01	0.14	0.13
Offsite							
	Hauling	0.04	0.04	0.71	0.00	0.16	0.04
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.35	0.86	0.01	0.25	0.07
TOTAL		0.55	5.03	9.51	0.02	0.39	0.20

3.11. Phase 3 Rough Grading (2028)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	1.35	11.80	13.90	0.02	0.52	0.47
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.35	11.80	13.90	0.02	3.28	1.81
Offsite							
	Worker	0.03	0.03	0.56	0.00	0.13	0.03
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.34	0.71	0.01	0.22	0.06
TOTAL		1.39	12.14	14.61	0.03	3.50	1.87
		Winter					
Onsite							
	Off-Road Equipment	0.03	0.26	0.30	0.01	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.00	0.00	0.06	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.26	0.30	0.01	0.07	0.04
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
TOTAL		0.04	0.28	0.32	0.01	0.08	0.05
		Summer					
Onsite							
	Off-Road Equipment	1.35	11.80	13.90	0.02	0.52	0.47
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.35	11.80	13.90	0.02	3.28	1.81
Offsite							
	Worker	0.03	0.03	0.56	0.00	0.13	0.03
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.34	0.71	0.01	0.22	0.06
TOTAL		1.39	12.14	14.61	0.03	3.50	1.87

3.13. Phase 3 Fine Grading (2028)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	1.35	11.80	13.90	0.02	0.52	0.47
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.35	11.80	13.90	0.02	3.28	1.81
Offsite							
	Worker	0.03	0.03	0.56	0.00	0.13	0.03
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.34	0.71	0.01	0.22	0.06
TOTAL		1.39	12.14	14.61	0.03	3.50	1.87
Onsite		Winter					
	Off-Road Equipment	0.03	0.23	0.27	0.01	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.00	0.00	0.05	0.03
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.03	0.23	0.27	0.01	0.06	0.04
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.01	0.01	0.01	0.01	0.01	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.02	0.02	0.01	0.01	0.01
TOTAL		0.04	0.25	0.29	0.01	0.07	0.05
Onsite		Summer					
	Off-Road Equipment	1.35	11.80	13.90	0.02	0.52	0.47
	Dust From Material Movement	0.00	0.00	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	1.35	11.80	13.90	0.02	3.28	1.81
Offsite							
	Worker	0.03	0.03	0.56	0.00	0.13	0.03
	Vendor	0.01	0.31	0.15	0.01	0.09	0.03
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.34	0.71	0.01	0.22	0.06
TOTAL		1.39	12.14	14.61	0.03	3.50	1.87

3.15. Phase 3 Building Construction (2028)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.93	7.89	9.88	0.02	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.93	7.89	9.88	0.02	0.23	0.21
Offsite							
	Worker	0.04	0.04	0.63	0.00	0.15	0.03
	Vendor	0.01	0.14	0.07	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.18	0.70	0.01	0.19	0.04
TOTAL		0.98	8.07	10.58	0.03	0.42	0.25
Onsite		Winter					
	Off-Road Equipment	0.93	7.89	9.88	0.02	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.93	7.89	9.88	0.02	0.23	0.21
Offsite							
	Worker	0.04	0.04	0.53	0.00	0.15	0.03
	Vendor	0.01	0.14	0.07	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.18	0.60	0.01	0.19	0.04
TOTAL		0.98	8.07	10.48	0.03	0.42	0.25
Onsite		Summer					
	Off-Road Equipment	0.93	7.89	9.88	0.02	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.93	7.89	9.88	0.02	0.23	0.21
Offsite							
	Worker	0.04	0.04	0.63	0.00	0.15	0.03
	Vendor	0.01	0.14	0.07	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.18	0.70	0.01	0.19	0.04
TOTAL		0.98	8.07	10.58	0.03	0.42	0.25

3.17. Phase 3 Building Construction (2029)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.89	7.62	9.82	0.02	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.89	7.62	9.82	0.02	0.21	0.19
Offsite							
	Worker	0.04	0.03	0.59	0.00	0.15	0.03
	Vendor	0.01	0.13	0.06	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.16	0.65	0.01	0.19	0.04
TOTAL		0.94	7.78	10.47	0.03	0.40	0.23
Onsite		Winter					
	Off-Road Equipment	0.89	7.62	9.82	0.02	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.89	7.62	9.82	0.02	0.21	0.19
Offsite							
	Worker	0.04	0.04	0.50	0.00	0.15	0.03
	Vendor	0.01	0.14	0.06	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.18	0.56	0.01	0.19	0.04
TOTAL		0.94	7.80	10.38	0.03	0.40	0.23
Onsite							
	Off-Road Equipment	0.89	7.62	9.82	0.02	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.89	7.62	9.82	0.02	0.21	0.19
Offsite							
	Worker	0.04	0.04	0.59	0.00	0.15	0.03
	Vendor	0.01	0.14	0.06	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.05	0.18	0.65	0.01	0.19	0.04
TOTAL		0.94	7.80	10.47	0.03	0.40	0.23

3.19. Phase 3 Building Construction (2030)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.87	7.48	9.79	0.02	0.20	0.18
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.87	7.48	9.79	0.02	0.20	0.18
Offsite							
	Worker	0.03	0.03	0.46	0.00	0.15	0.03
	Vendor	0.01	0.13	0.06	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.16	0.52	0.01	0.19	0.04
TOTAL		0.91	7.64	10.31	0.03	0.39	0.22
Onsite							
	Off-Road Equipment	0.87	7.48	9.79	0.02	0.20	0.18
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.87	7.48	9.79	0.02	0.20	0.18
Offsite							
	Worker	0.03	0.03	0.46	0.00	0.15	0.03
	Vendor	0.01	0.13	0.06	0.01	0.04	0.01
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.04	0.16	0.52	0.01	0.19	0.04
TOTAL		0.91	7.64	10.31	0.03	0.39	0.22

3.21. Phase 3 Paving (2030)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
		Winter					
Onsite							
	Off-Road Equipment	0.30	2.67	4.82	0.01	0.07	0.07
	Paving	0.08	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.38	2.67	4.82	0.01	0.07	0.07
Offsite							
	Worker	0.02	0.02	0.31	0.00	0.10	0.02
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.02	0.31	0.00	0.10	0.02
TOTAL		0.40	2.69	5.13	0.01	0.17	0.09
Onsite							
	Off-Road Equipment	0.30	2.67	4.82	0.01	0.07	0.07
	Paving	0.08	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.38	2.67	4.82	0.01	0.07	0.07
Offsite							
	Worker	0.02	0.02	0.31	0.00	0.10	0.02
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.02	0.02	0.31	0.00	0.10	0.02
TOTAL		0.40	2.69	5.13	0.01	0.17	0.09

3.23. Phase 3 Architectural Coating (2030)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
		Summer					
Onsite							
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
		Winter					
Onsite							
	Off-Road Equipment	0.10	0.78	1.11	0.01	0.01	0.01
	Architectural Coatings	6.65	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	6.75	0.78	1.11	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.09	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.09	0.00	0.03	0.01
TOTAL		6.76	0.79	1.20	0.01	0.04	0.02
Onsite							
	Off-Road Equipment	0.10	0.78	1.11	0.01	0.01	0.01
	Architectural Coatings	6.65	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	6.75	0.78	1.11	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.09	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.09	0.00	0.03	0.01
TOTAL		6.76	0.79	1.20	0.01	0.04	0.02

3.25. Phase 3 Utilities Trenching (2028)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.09	0.81	1.02	0.01	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.09	0.81	1.02	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.14	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.14	0.00	0.03	0.01
TOTAL		0.10	0.82	1.16	0.01	0.05	0.03
Onsite		Winter					
	Off-Road Equipment	0.01	0.01	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01	0.01	0.01
Offsite							
	Worker	0.01	0.01	0.01	0.00	0.01	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.00	0.01	0.01
TOTAL		0.01	0.02	0.02	0.01	0.01	0.01
Onsite							
	Off-Road Equipment	0.09	0.81	1.02	0.01	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.09	0.81	1.02	0.01	0.02	0.02
Offsite							
	Worker	0.01	0.01	0.14	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.14	0.00	0.03	0.01
TOTAL		0.10	0.82	1.16	0.01	0.05	0.03

3.25. Phase 3 Finishing/Landscaping (2030)

		ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
Onsite		Summer					
	Off-Road Equipment	0.00	0.00	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
Offsite							
	Worker	0.00	0.00	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00	0.00	0.00
Onsite		Winter					
	Off-Road Equipment	0.08	0.80	1.01	0.01	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.08	0.80	1.01	0.01	0.02	0.01
Offsite							
	Worker	0.01	0.01	0.10	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.10	0.00	0.03	0.01
TOTAL		0.09	0.81	1.11	0.01	0.05	0.02
Onsite							
	Off-Road Equipment	0.08	0.80	1.01	0.01	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.08	0.80	1.01	0.01	0.02	0.01
Offsite							
	Worker	0.01	0.01	0.10	0.00	0.03	0.01
	Vendor	0.00	0.00	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.10	0.00	0.03	0.01
TOTAL		0.09	0.81	1.11	0.01	0.05	0.02

Phase 1 Construction

	ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
<i>Phase 1 Building and Asphalt Demolition and Debris Haul</i>	1	6	8	0	1	0
<i>Phase 1 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	1	12	18	0	2	1
<i>Phase 1 Site Preparation</i>	1	7	10	0	1	0
<i>Phase 1 Site Preparation and Rough Grading</i>	3	24	27	0	4	3
<i>Phase 1 Rough Grading</i>	2	18	17	0	4	2
<i>Phase 1 Fine Grading</i>	2	18	17	0	4	2
<i>Phase 1 Fine Grading and Utilities Trenching</i>	2	19	19	0	4	2
<i>Phase 1 Utilities Trenching</i>	0	1	1	0	0	0
<i>Phase 1 Utilities Trenching and Building Construction (2023)</i>	1	11	12	0	1	0
<i>Phase 1 Building Construction (2023)</i>	1	10	11	0	1	0
<i>Phase 1 Building Construction (2024)</i>	1	10	11	0	1	0
<i>Phase 1 Building Construction (2024), Paving, and Architectural Coating</i>	10	15	17	0	1	1
<i>Phase 1 Building Construction (2024), Paving, Architectural Coating, and Finishing/Landscaping</i>	10	15	18	0	1	1

Phase 2 Construction

	ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
<i>Phase 2 Building and Asphalt Demolition and Debris Haul</i>	1	6	10	0	1	0
<i>Phase 2 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	1	12	20	0	1	1
<i>Phase 2 Site Preparation</i>	1	6	10	0	0	0
<i>Phase 2 Site Preparation and Rough Grading</i>	2	20	25	0	4	2
<i>Phase 2 Rough Grading</i>	2	15	15	0	3	2
<i>Phase 2 Fine Grading</i>	2	15	15	0	3	2
<i>Phase 2 Fine Grading and Utilities Trenching</i>	2	15	17	0	3	2
<i>Phase 2 Utilities Trenching</i>	0	1	1	0	0	0
<i>Phase 2 Utilities Trenching and Building Construction (2025)</i>	1	11	13	0	0	0
<i>Phase 2 Building Construction (2025)</i>	1	11	12	0	0	0
<i>Phase 2 Building Construction (2026)</i>	1	10	12	0	0	0
<i>Phase 2 Building Construction (2026), Paving, and Architectural Coating</i>	4	14	18	0	1	0
<i>Phase 2 Building Construction (2026), Paving, Architectural Coating, and Finishing/Landscaping</i>	4	15	19	0	1	0

Phase 3 Construction

	ROG	NOx	CO	SO2	PM10 Total	PM2.5 Total
<i>Phase 3 Building and Asphalt Demolition and Debris Haul</i>	1	5	10	0	1	0
<i>Phase 3 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	1	10	19	0	2	1
<i>Phase 3 Site Preparation</i>	1	5	10	0	0	0
<i>Phase 3 Site Preparation and Rough Grading</i>	2	17	24	0	4	2
<i>Phase 3 Rough Grading</i>	1	12	15	0	4	2
<i>Phase 3 Fine Grading</i>	1	12	15	0	4	2
<i>Phase 3 Fine Grading and Utilities Trenching</i>	1	13	16	0	4	2
<i>Phase 3 Utilities Trenching</i>	0	1	1	0	0	0
<i>Phase 3 Utilities Trenching and Building Construction (2028)</i>	1	9	12	0	0	0
<i>Phase 3 Building Construction (2028)</i>	1	8	11	0	0	0
<i>Phase 3 Building Construction (2029)</i>	1	8	10	0	0	0
<i>Phase 3 Building Construction (2030)</i>	1	8	10	0	0	0
<i>Phase 3 Building Construction (2030), Paving, and Architectural Coating</i>	8	11	17	0	1	0
<i>Phase 3 Building Construction (2030), Paving, Architectural Coating, and Finishing/Landscaping</i>	8	12	18	0	1	0

MAX DAILY	10	24	27	0	4	3
Regional Thresholds	75	100	550	150	150	55
Exceeds Thresholds?	No	No	No	No	No	No

Construction LST Worksheet:

Phase 1					
3.1. Phase 1 Building Demolition (2023)					
		NOx	CO	PM10 Total	PM2.5Total
Onsite	Off-Road Equipment	4.88	7.03	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.88	7.03	0.23	0.21
TOTAL		4.88	7.03	0.23	0.21
Onsite	Off-Road Equipment	0.45	0.66	0.02	0.02
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.45	0.66	0.02	0.02
TOTAL		0.45	0.66	0.02	0.02
Onsite	Off-Road	4.88	7.03	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.88	7.03	0.23	0.21
TOTAL		4.88	7.03	0.23	0.21
3.3. Building Demolition Debris Hauling (2023)					
		NOx	CO	PM10 Total	PM2.5Total
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.21	0.03
TOTAL		0.00	0.00	0.21	0.03
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.02	0.01
TOTAL		0.00	0.00	0.02	0.01
Onsite	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.21	0.03
TOTAL		0.00	0.00	0.21	0.03

3.5. Phase 1 Asphalt Demolition (2023)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00

3.7. Phase 1 Asphalt Demolition Debris Haul (2023)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.21	0.03
TOTAL		0.00	0.00	0.21	0.03
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.02	0.01
TOTAL		0.00	0.00	0.02	0.01
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.21	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.21	0.03
TOTAL		0.00	0.00	0.21	0.03

3.9. Phase 1 Site Preparation (2023)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	6.03	8.67	0.29	0.27
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	6.03	8.67	0.29	0.27
TOTAL		6.03	8.67	0.29	0.27
Onsite					
	Off-Road Equipment	0.07	0.10	0.01	0.01
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.07	0.10	0.01	0.01
TOTAL		0.07	0.10	0.01	0.01
Onsite					
	Off-Road	6.03	8.67	0.29	0.27
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	6.03	8.67	0.29	0.27
Offsite					
	Hauling	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00
	Worker	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		6.03	8.67	0.29	0.27

3.11. Phase 1 Rough Grading (2023)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	17.50	16.30	0.83	0.77
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	17.50	16.30	3.59	2.11
TOTAL		17.50	16.30	3.59	2.11
Onsite					
	Off-Road Equipment	0.34	0.31	0.02	0.01
	Dust From Material Movement	0.00	0.00	0.05	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.34	0.31	0.07	0.04
TOTAL		0.34	0.31	0.07	0.04
Onsite					
	Off-Road Equipment	17.50	16.30	0.83	0.77
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	17.50	16.30	3.59	2.11
TOTAL		17.50	16.30	3.59	2.11

3.13. Phase 1 Fine Grading (2023)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	17.50	16.30	0.83	0.77
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	17.50	16.30	3.59	2.11
TOTAL		17.50	16.30	3.59	2.11
Onsite					
	Off-Road Equipment	0.29	0.27	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.05	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.29	0.27	0.06	0.03
TOTAL		0.29	0.27	0.06	0.03
Onsite					
	Off-Road Equipment	17.50	16.30	0.83	0.77
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	17.50	16.30	3.59	2.11
Offsite					
	Worker	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		17.50	16.30	3.59	2.11

3.15. Phase 1 Building Construction (2023)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	9.81	10.20	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.81	10.20	0.41	0.38
TOTAL		9.81	10.20	0.41	0.38
Onsite					
	Off-Road Equipment	9.81	10.20	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.81	10.20	0.41	0.38
TOTAL		9.81	10.20	0.41	0.38
Onsite					
	Off-Road Equipment	9.81	10.20	0.41	0.38
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.81	10.20	0.41	0.38
Offsite					
	Worker	0.00	0.00	0.00	0.00
	Vendor	0.00	0.00	0.00	0.00
	Hauling	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		9.81	10.20	0.41	0.38

3.17. Phase 1 Building Construction (2024)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	9.44	10.10	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.44	10.10	0.37	0.34
TOTAL		9.44	10.10	0.37	0.34
Onsite					
	Off-Road Equipment	9.44	10.10	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.44	10.10	0.37	0.34
TOTAL		9.44	10.10	0.37	0.34
Onsite					
	Off-Road Equipment	9.44	10.10	0.37	0.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	9.44	10.10	0.37	0.34
TOTAL		9.44	10.10	0.37	0.34

3.19. Phase 1 Paving (2024)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	3.32	4.84	0.15	0.14
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	3.32	4.84	0.15	0.14
TOTAL		3.32	4.84	0.15	0.14
Onsite					
	Off-Road Equipment	3.32	4.84	0.15	0.14
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	3.32	4.84	0.15	0.14
TOTAL		3.32	4.84	0.15	0.14

3.21. Phase 1 Architectural Coating (2024)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	1.60	1.05	0.07	0.06
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	1.60	1.05	0.07	0.06
TOTAL		1.60	1.05	0.07	0.06
Onsite					
	Off-Road Equipment	1.60	1.05	0.07	0.06
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	1.60	1.05	0.07	0.06
TOTAL		1.60	1.05	0.07	0.06

3.23. Phase 1 Utilities Trenching (2023)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.87	1.02	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.87	1.02	0.03	0.03
TOTAL		0.87	1.02	0.03	0.03
Onsite					
	Off-Road Equipment	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01
TOTAL		0.01	0.01	0.01	0.01
Onsite					
	Off-Road Equipment	0.87	1.02	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.87	1.02	0.03	0.03
TOTAL		0.87	1.02	0.03	0.03

3.25. Phase 1 Finishing/Landscaping (2024)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.84	1.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.84	1.01	0.03	0.03
TOTAL		0.84	1.01	0.03	0.03
Onsite					
	Off-Road Equipment	0.84	1.01	0.03	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.84	1.01	0.03	0.03
TOTAL		0.84	1.01	0.03	0.03

Phase 2

3.2. Phase 2 Building Demolition (2025)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	5.61	8.82	0.23	0.21
	Demolition			0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	5.61	8.82	0.23	0.21
TOTAL		5.61	8.82	0.23	0.21
Onsite					
	Off-Road Equipment	0.46	0.73	0.02	0.02
	Demolition			0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.46	0.73	0.02	0.02
TOTAL		0.46	0.73	0.02	0.02
Onsite					
	Off-Road	5.61	8.82	0.23	0.21
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	5.61	8.82	0.23	0.21
TOTAL		5.61	8.82	0.23	0.21

3.3. Building Demolition Debris Hauling (2025)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition			0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.01	0.01
TOTAL		0.00	0.00	0.01	0.01
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition			0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.01	0.01
TOTAL		0.00	0.00	0.01	0.01
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.01	0.01
TOTAL		0.00	0.00	0.01	0.01

3.5. Phase 2 Asphalt Demolition (2025)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00

3.7. Phase 2 Asphalt Demolition Debris Haul (2025)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition			0.50	0.08
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.50	0.08
TOTAL		0.00	0.00	0.50	0.08
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition			0.04	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.04	0.01
TOTAL		0.00	0.00	0.04	0.01
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.50	0.08
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.50	0.08
TOTAL		0.00	0.00	0.50	0.08

3.9. Phase 2 Site Preparation (2025)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	5.29	8.63	0.21	0.19
	Demolition			0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	5.29	8.63	0.21	0.19
TOTAL		5.29	8.63	0.21	0.19
Onsite					
	Off-Road Equipment	0.07	0.12	0.01	0.01
	Demolition			0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.07	0.12	0.01	0.01
TOTAL		0.07	0.12	0.01	0.01
Onsite					
	Off-Road	5.29	8.63	0.21	0.19
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	5.29	8.63	0.21	0.19
TOTAL		5.29	8.63	0.21	0.19

3.11. Phase 2 Rough Grading (2025)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	14.10	14.50	0.64	0.59
	Onsite truck			2.76	1.34
	Total	14.10	14.50	3.40	1.93
TOTAL		14.10	14.50	3.40	1.93
Onsite					
	Off-Road Equipment	0.35	0.36	0.02	0.01
	Onsite truck			0.07	0.03
	Total	0.35	0.36	0.09	0.04
TOTAL		0.35	0.36	0.09	0.04
Onsite					
	Off-Road Equipment	14.10	14.50	0.64	0.59
	Onsite truck	0.00	0.00	2.76	1.34
	Total	14.10	14.50	3.40	1.93
TOTAL		14.10	14.50	3.40	1.93

3.13. Phase 2 Fine Grading (2025)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	14.10	14.50	0.64	0.59
	Onsite truck			2.76	1.34
	Total	14.10	14.50	3.40	1.93
TOTAL		14.10	14.50	3.40	1.93
Onsite					
	Off-Road Equipment	0.31	0.32	0.01	0.01
	Onsite truck			0.06	0.03
	Total	0.31	0.32	0.07	0.04
TOTAL		0.31	0.32	0.07	0.04
Onsite					
	Off-Road Equipment	14.10	14.50	0.64	0.59
	Onsite truck	0.00	0.00	2.76	1.34
	Total	14.10	14.50	3.40	1.93
TOTAL		14.10	14.50	3.40	1.93

3.15. Phase 2 Building Construction (2025)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	10.60	11.90	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.60	11.90	0.40	0.37
TOTAL		10.60	11.90	0.40	0.37
Onsite					
	Off-Road Equipment	10.60	11.90	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.60	11.90	0.40	0.37
TOTAL		10.60	11.90	0.40	0.37
Onsite					
	Off-Road Equipment	10.60	11.90	0.40	0.37
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.60	11.90	0.40	0.37
TOTAL		10.60	11.90	0.40	0.37

3.17. Phase 2 Building Construction (2026)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	10.10	11.80	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.10	11.80	0.36	0.33
TOTAL		10.10	11.80	0.36	0.33
Onsite					
	Off-Road Equipment	10.10	11.80	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.10	11.80	0.36	0.33
TOTAL		10.10	11.80	0.36	0.33
Onsite					
	Off-Road Equipment	10.10	11.80	0.36	0.33
	Onsite truck	0.00	0.00	0.00	0.00
	Total	10.10	11.80	0.36	0.33
TOTAL		10.10	11.80	0.36	0.33

3.19. Phase 2 Paving (2026)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	2.94	4.80	0.11	0.10
	Paving				
	Onsite truck	0.00	0.00	0.00	0.00
	Total	2.94	4.80	0.11	0.10
TOTAL		2.94	4.80	0.11	0.10
Onsite					
	Off-Road Equipment	2.94	4.80	0.11	0.10
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	2.94	4.80	0.11	0.10
TOTAL		2.94	4.80	0.11	0.10
3.21. Phase 2 Architectural Coating (2026)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.86	1.13	0.02	0.02
	Architectural Coatings				
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.86	1.13	0.02	0.02
TOTAL		0.86	1.13	0.02	0.02
Onsite					
	Off-Road Equipment	0.86	1.13	0.02	0.02
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.86	1.13	0.02	0.02
TOTAL		0.86	1.13	0.02	0.02
3.23. Phase 2 Utilities Trenching (2025)					
		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.83	1.02	0.03	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.83	1.02	0.03	0.02
TOTAL		0.83	1.02	0.03	0.02
Onsite					
	Off-Road Equipment	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01
TOTAL		0.01	0.01	0.01	0.01
Onsite					
	Off-Road Equipment	0.83	1.02	0.03	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.83	1.02	0.03	0.02
TOTAL		0.83	1.02	0.03	0.02

3.25. Phase 2 Finishing/Landscaping (2026)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.82	1.02	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.82	1.02	0.02	0.02
TOTAL		0.82	1.02	0.02	0.02
Onsite					
	Off-Road Equipment	0.82	1.02	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.82	1.02	0.02	0.02
TOTAL		0.82	1.02	0.02	0.02

Phase 3

3.1. Phase 3 Building Demolition (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	4.86	8.83	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.86	8.83	0.14	0.13
TOTAL		4.86	8.83	0.14	0.13
Onsite					
	Off-Road Equipment	0.52	0.94	0.02	0.01
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.52	0.94	0.02	0.01
TOTAL		0.52	0.94	0.02	0.01
Onsite					
	Off-Road	4.86	8.83	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.86	8.83	0.14	0.13
TOTAL		4.86	8.83	0.14	0.13

3.3. Building Demolition Debris Hauling (2028)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.59	0.09
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.59	0.09
TOTAL		0.00	0.00	0.59	0.09
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.06	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.06	0.01
TOTAL		0.00	0.00	0.06	0.01
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.59	0.09
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.59	0.09
TOTAL		0.00	0.00	0.59	0.09

3.5. Phase 3 Asphalt Demolition (2028)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	TOTAL	0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	TOTAL	0.00	0.00	0.00	0.00
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00

3.7. Phase 3 Asphalt Demolition Debris Haul (2028)

		NOx	CO	PM10 Total	PM2.5Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.15	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	TOTAL	0.00	0.00	0.15	0.02
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	TOTAL	0.00	0.00	0.02	0.01
Onsite					
	Off-Road	0.00	0.00	0.00	0.00
	Demolition	0.00	0.00	0.15	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.15	0.02
TOTAL		0.00	0.00	0.15	0.02

3.9. Phase 3 Site Preparation (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	4.68	8.65	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.68	8.65	0.14	0.13
TOTAL		4.68	8.65	0.14	0.13
Onsite					
	Off-Road Equipment	0.05	0.09	0.01	0.01
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.05	0.09	0.01	0.01
TOTAL		0.05	0.09	0.01	0.01
Onsite					
	Off-Road	4.68	8.65	0.14	0.13
	Demolition	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	4.68	8.65	0.14	0.13
TOTAL		4.68	8.65	0.14	0.13

3.11. Phase 3 Rough Grading (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	11.80	13.90	0.52	0.47
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	11.80	13.90	3.28	1.81
TOTAL		11.80	13.90	3.28	1.81
Onsite					
	Off-Road Equipment	0.26	0.30	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.06	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.26	0.30	0.07	0.04
TOTAL		0.26	0.30	0.07	0.04
Onsite					
	Off-Road Equipment	11.80	13.90	0.52	0.47
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	11.80	13.90	3.28	1.81
TOTAL		11.80	13.90	3.28	1.81

3.13. Phase 3 Fine Grading (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	11.80	13.90	0.52	0.47
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	11.80	13.90	3.28	1.81
TOTAL		11.80	13.90	3.28	1.81
Onsite					
	Off-Road Equipment	0.23	0.27	0.01	0.01
	Dust From Material Movement	0.00	0.00	0.05	0.03
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.23	0.27	0.06	0.04
TOTAL		0.23	0.27	0.06	0.04
Onsite					
	Off-Road Equipment	11.80	13.90	0.52	0.47
	Dust From Material Movement	0.00	0.00	2.76	1.34
	Onsite truck	0.00	0.00	0.00	0.00
	Total	11.80	13.90	3.28	1.81
TOTAL		11.80	13.90	3.28	1.81

3.15. Phase 3 Building Construction (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	7.89	9.88	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.89	9.88	0.23	0.21
TOTAL		7.89	9.88	0.23	0.21
Onsite					
	Off-Road Equipment	7.89	9.88	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.89	9.88	0.23	0.21
TOTAL		7.89	9.88	0.23	0.21
Onsite					
	Off-Road Equipment	7.89	9.88	0.23	0.21
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.89	9.88	0.23	0.21
TOTAL		7.89	9.88	0.23	0.21

3.17. Phase 3 Building Construction (2029)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	7.62	9.82	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.62	9.82	0.21	0.19
TOTAL		7.62	9.82	0.21	0.19
Onsite					
	Off-Road Equipment	7.62	9.82	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.62	9.82	0.21	0.19
TOTAL		7.62	9.82	0.21	0.19
Onsite					
	Off-Road Equipment	7.62	9.82	0.21	0.19
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.62	9.82	0.21	0.19
TOTAL		7.62	9.82	0.21	0.19

3.19. Phase 3 Building Construction (2030)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	7.48	9.79	0.20	0.18
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.48	9.79	0.20	0.18
TOTAL		7.48	9.79	0.20	0.18
Onsite					
	Off-Road Equipment	7.48	9.79	0.20	0.18
	Onsite truck	0.00	0.00	0.00	0.00
	Total	7.48	9.79	0.20	0.18
TOTAL		7.48	9.79	0.20	0.18

3.21. Phase 3 Paving (2030)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	2.67	4.82	0.07	0.07
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	2.67	4.82	0.07	0.07
TOTAL		2.67	4.82	0.07	0.07
Onsite					
	Off-Road Equipment	2.67	4.82	0.07	0.07
	Paving	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	2.67	4.82	0.07	0.07
TOTAL		2.67	4.82	0.07	0.07

3.23. Phase 3 Architectural Coating (2030)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.00	0.00	0.00	0.00
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite					
	Off-Road Equipment	0.78	1.11	0.01	0.01
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.78	1.11	0.01	0.01
TOTAL		0.78	1.11	0.01	0.01
Onsite					
	Off-Road Equipment	0.78	1.11	0.01	0.01
	Architectural Coatings	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.78	1.11	0.01	0.01
TOTAL		0.78	1.11	0.01	0.01

3.25. Phase 3 Utilities Trenching (2028)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite					
	Off-Road Equipment	0.81	1.02	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.81	1.02	0.02	0.02
TOTAL		0.81	1.02	0.02	0.02
Onsite					
	Off-Road Equipment	0.01	0.01	0.01	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.01	0.01	0.01	0.01
TOTAL		0.01	0.01	0.01	0.01
Onsite					
	Off-Road Equipment	0.81	1.02	0.02	0.02
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.81	1.02	0.02	0.02
TOTAL		0.81	1.02	0.02	0.02

3.25. Phase 3 Finishing/Landscaping (2030)

		NOx	CO	PM10 Total	PM2.5 Total
Onsite	Off-Road Equipment	0.00	0.00	0.00	0.00
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.00	0.00	0.00	0.00
TOTAL		0.00	0.00	0.00	0.00
Onsite	Off-Road Equipment	0.80	1.01	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.80	1.01	0.02	0.01
TOTAL		0.80	1.01	0.02	0.01
Onsite	Off-Road Equipment	0.80	1.01	0.02	0.01
	Onsite truck	0.00	0.00	0.00	0.00
	Total	0.80	1.01	0.02	0.01
TOTAL		0.80	1.01	0.02	0.01

Phase 1 Construction

		NOx	CO	PM10 Total	PM2.5 Total
Phase 1 Building and Asphalt Demolition and Debris Haul		4.88	7.03	0.65	0.27
	1.50 Acre LST	125	694	5.00	3.50
	Exceeds LST?	no	no	no	no
Phase 1 Building and Asphalt Demolition and Debris Haul, Site Preparation		10.91	15.70	0.94	0.54
	1.97 Acre LST	146	819	5.94	3.97
	Exceeds LST?	no	no	no	no
Phase 1 Site Preparation		6.03	8.67	0.29	0.27
	1.97 Acre LST	146	819	5.94	3.97
	Exceeds LST?	no	no	no	no
Phase 1 Site Preparation and Rough Grading		23.53	24.97	3.88	2.38
	1.97 Acre LST	146	819	5.94	3.97
	Exceeds LST?	no	no	no	no
Phase 1 Rough Grading		17.50	16.30	3.59	2.11
	1.88 Acre LST	142	794	5.75	3.87
	Exceeds LST?	no	no	no	no
Phase 1 Fine Grading		17.50	16.30	3.59	2.11
	1.88 Acre LST	142	794	5.75	3.87
	Exceeds LST?	no	no	no	no
Phase 1 Fine Grading and Utilities Trenching		18.37	17.32	3.62	2.14
	1.88 Acre LST	142	794	5.75	3.87
	Exceeds LST?	no	no	no	no
Phase 1 Utilities Trenching		0.87	1.02	0.03	0.03
	≤1.00 Acre LST	103	562	4	3
	Exceeds LST?	no	no	no	no

Phase 1 Utilities Trenching and Building Construction (2023)	10.68	11.22	0.44	0.41
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 1 Building Construction (2023)	9.81	10.20	0.41	0.38
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 1 Building Construction (2024)	9.44	10.10	0.37	0.34
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 1 Building Construction (2024), Paving, and Architectural Coating	14.36	15.99	0.59	0.54
1.38 Acre LST	120	661	4.75	3.37
Exceeds LST?	no	no	no	no
Phase 1 Building Construction (2024), Paving, Architectural Coating, and Finishing/Landscaping	15.20	17.00	0.62	0.57
1.38 Acre LST	120	661	4.75	3.37
Exceeds LST?	no	no	no	no

Phase 2 Construction

	NOx	CO	PM10 Total	PM2.5 Total
Phase 2 Building and Asphalt Demolition and Debris Haul	5.61	8.82	0.74	0.30
1.50 Acre LST	125	694	5.00	3.50
Exceeds LST?	no	no	no	no
Phase 2 Building and Asphalt Demolition and Debris Haul, Site Preparation	10.90	17.45	0.95	0.49
2.82 Acre LST	167	1019	7.91	4.55
Exceeds LST?	no	no	no	no
Phase 2 Site Preparation	5.29	8.63	0.21	0.19
2.00 Acre LST	147	827	6.00	4.00
Exceeds LST?	no	no	no	no
Phase 2 Site Preparation and Rough Grading	19.39	23.13	3.61	2.12
2.82 Acre LST	167	1019	7.91	4.55
Exceeds LST?	no	no	no	no
Phase 2 Rough Grading	14.10	14.50	3.40	1.93
1.88 Acre LST	142	794	5.75	3.87
Exceeds LST?	no	no	no	no
Phase 2 Fine Grading	14.10	14.50	3.40	1.93
1.88 Acre LST	142	794	5.75	3.87
Exceeds LST?	no	no	no	no

<i>Phase 2 Fine Grading and Utilities Trenching</i>	14.93	15.52	3.43	1.95
1.88 Acre LST	142	794	5.75	3.87
Exceeds LST?	no	no	no	no
<i>Phase 2 Utilities Trenching</i>	0.83	1.02	0.03	0.02
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
<i>Phase 2 Utilities Trenching and Building Construction (2025)</i>	11.43	12.92	0.43	0.39
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
<i>Phase 2 Building Construction (2025)</i>	10.60	11.90	0.40	0.37
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
<i>Phase 2 Building Construction (2026)</i>	10.10	11.80	0.36	0.33
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
<i>Phase 2 Building Construction (2026), Paving, and Architectural Coating</i>	13.90	17.73	0.49	0.45
1.38 Acre LST	120	661	4.75	3.37
Exceeds LST?	no	no	no	no
<i>Phase 2 Building Construction (2026), Paving, Architectural Coating, and Finishing/Landscaping</i>	14.72	18.75	0.51	0.47
1.38 Acre LST	120	661	4.75	3.37
Exceeds LST?	no	no	no	no
Phase 3 Construction				
	NOx	CO	PM10 Total	PM2.5 Total
<i>Phase 3 Building and Asphalt Demolition and Debris Haul</i>	4.86	8.83	0.88	0.24
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
<i>Phase 3 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	9.54	17.48	1.02	0.37
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
<i>Phase 3 Site Preparation</i>	4.68	8.65	0.14	0.13
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
<i>Phase 3 Site Preparation and Rough Grading</i>	16.48	22.55	3.42	1.94
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no

Phase 3 Rough Grading	11.80	13.90	3.28	1.81
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
Phase 3 Fine Grading	11.80	13.90	3.28	1.81
1.35 Acre LST	119	655	4.70	3.35
Exceeds LST?	no	no	no	no
Phase 3 Fine Grading and Utilities Trenching	12.61	14.92	3.30	1.83
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
Phase 3 Utilities Trenching	0.81	1.02	0.02	0.02
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 3 Utilities Trenching and Building Construction (2028)	8.70	10.90	0.25	0.23
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 3 Building Construction (2028)	7.89	9.88	0.23	0.21
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 3 Building Construction (2029)	7.62	9.82	0.21	0.19
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 3 Building Construction (2030)	7.48	9.79	0.20	0.18
≤1.00 Acre LST	103	562	4.00	3.00
Exceeds LST?	no	no	no	no
Phase 3 Building Construction (2030), Paving, and Architectural Coating	10.93	15.72	0.28	0.26
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no
Phase 3 Building Construction (2030), Paving, Architectural Coating, and Finishing/Landscaping	11.73	16.73	0.30	0.27
1.35 Acre LST	118	655	4.70	3.35
Exceeds LST?	no	no	no	no

GHG Emissions Inventory

Proposed Project Buildout

Construction¹

Phase 1 Construction

	MTCO ₂ e
2023	137
2024	246
Total Construction	383
30-Year Amortization²	13

Phase 2 Construction

	MTCO ₂ e
2025	149
2026	260
Total Construction	409
30-Year Amortization²	14

Phase 3 Construction

	MTCO ₂ e
2028	138
2029	246
2030	56
Total Construction	440
30-Year Amortization²	15

Totals

	MTCO ₂ e	%
Year 2023	137	11%
Year 2024	246	20%
Year 2025	149	12%
Year 2026	260	21%
Year 2028	138	11%
Year 2029	246	20%
Year 2030	56	5%
Total Construction	1,232	100%
Total 30-Year Amortization²	41	

Notes

¹ CalEEMod, Version 2022.1

² Total construction emissions are amortized over 30 years per SCAQMD methodology; SCAQMD. 2009, November 19.

Greenhouse Gases (GHG) CEQA Significance Thresholds Working Group Meeting 14. [http://www.aqmd.gov/docs/default-source/ceqa/handbook/greenhouse-gases-\(ghg\)-ceqa-significance-thresholds/year-2008-2009/ghg-meeting-14/ghg-meeting-14-main-presentation.pdf?sfvrsn=2](http://www.aqmd.gov/docs/default-source/ceqa/handbook/greenhouse-gases-(ghg)-ceqa-significance-thresholds/year-2008-2009/ghg-meeting-14/ghg-meeting-14-main-presentation.pdf?sfvrsn=2).

Assumptions Worksheet

CalEEMod Inputs- McKinley Elementary School, Construction

Name: McKinley Elementary School, Construction
Project Number: SMM-07
Project Location: North of 23rd Ct and Santa Monica Blvd
County/Air Basin: Los Angeles - South Coast AQMD
Climate Zone: 11
Land Use Setting: Urban
Operational Year: 2028
Utility Company: Southern California Edison
Air Basin: South Coast Air Basin
Air District: South Coast AQMD
SRA: 2 - Northwest Coastal LA County

Project Site Acreage 6.48

	Phase 1	Phase 2	Phase 3	Total
Disturbed Site Acreage	1.97	2.82	1.35	6.14

Project Components	SQFT	Amount of Debris	Notes
Demolition			
Phase 1			
Building Demolition (CY)	11,028	1,015	Eleven Portable Classrooms (B1-B11) and Playground Restrooms
Asphalt Demolition (Tons)	35,284	523	
Phase 2			
Building Demolition (CY)	397	37	Removal of Elevator that serves Buildings B and C
Asphalt Demolition (Tons)	73,424	1,088	
Phase 3			
Building Demolition (CY)	3,796	349	Modular Building D, Interim Parking
Asphalt Demolition (Tons)	32,000	474	

Project Components	Number of Stories	SQFT	Building Footprint	Acres
Construction				
Phase 1				
Two-Story Classroom Building	2	24,410	12,205	0.28
Library Renovation	1	1,354	1,354	0.03
Parking		32,000		0.73
Asphalt Surfaces		10,244		0.24
Landscaping		3,133		0.07
Hardscape		7,547		0.17
Remaining Area		19,330		0.44
TOTAL ACREAGE				1.97

Notes

¹ Assumes asphalt surfaces, landscaping and hardscaping SF will covers the 14,500 sf playfields and playgrounds (see Project Description)

Project Components	Number of Stories	SQFT	Building Footprint	Acres
Phase 2				
Building C Renovation	2	2,330	1,165	0.00
Elevator and Stair Core Reconstruction	2	870	435	0.01
Lunch Shelter	1	3,500	3,500	0.08
Asphalt Surfaces		2,438		0.06
Landscaping		29,720		0.68
Hardscape		64,007		1.47
Remaining Area		22,738		0.52
			TOTAL ACREAGE	2.82

Project Components	Number of Stories	SQFT	Building Footprint	Acres
Phase 3				
Two-Story Classroom Building	2	26,500	13,250	0.30
Parking		23,000		0.53
Asphalt Surfaces		2,580		0.06
Landscaping		10,798		0.25
Hardscape		8,973		0.21
			TOTAL ACREAGE	1.35

CalEEMod Land Use Inputs - Phase 1

Land Use Type	Land Use Subtype	Unit Amount	Size Metric	Lot Acreage	Land Use Square
					Feet
Educational	Elementary School	24.410	1000 sqft	0.31	24,410
Parking	Parking	32.000	1000 sqft	0.73	32,000
Parking	Other Asphalt Surfaces	10.244	1000 sqft	0.24	10,244
	Other Non-asphalt				
Parking	Surfaces (Landscape)	3.133	1000 sqft	0.07	3,133
	Other Non-asphalt				
Parking	Surfaces (Hardscape)	26.877	1000 sqft	0.62	26,877
				1.97	

CalEEMod Land Use Inputs - Phase 2

Land Use Type	Land Use Subtype	Unit Amount	Size Metric	Lot Acreage	Land Use Square
					Feet
Educational	Elementary School	4.370	1000 sqft	0.09	4,370
Parking	Other Asphalt Surfaces	2.438	1000 sqft	0.06	2,438
	Other Non-asphalt				
Parking	Surfaces (Landscape)	29.720	1000 sqft	0.68	29,720
	Other Non-asphalt				
Parking	Surfaces (Hardscape)	86.745	1000 sqft	1.99	86,745
				2.82	

CalEEMod Land Use Inputs - Phase 3

Land Use Type	Land Use Subtype	Unit Amount	Size Metric	Lot Acreage	Land Use Square
					Feet
Educational	Elementary School	26.500	1000 sqft	0.30	26,500
Parking	Parking	23.000	1000 sqft	0.53	23,000
Parking	Other Asphalt Surfaces	2.580	1000 sqft	0.06	2,580
	Other Non-asphalt				
Parking	Surfaces (Landscape)	10.798	1000 sqft	0.25	10,798
	Other Non-asphalt				
Parking	Surfaces (Hardscape)	8.973	1000 sqft	0.21	8,973
				1.35	

Demolition - Phase 1

Component	Amount to be Demolished	Haul Truck Capacity	Haul Distance (miles)	Total Trip Ends	Duration (days)	Trip Ends Per Day
Building (CY)	1,015	16	20	130	34	4
Asphalt (tons)	523	20	20	53	34	2
Total	1,537			183		

Demolition - Phase 2

Component	Amount to be Demolished	Haul Truck Capacity	Haul Distance (miles)	Total Trip Ends	Duration (days)	Trip Ends Per Day
Building (CY)	37	16	20	6	30	1
Asphalt (tons)	1,088	20	20	109	30	4
Total	1,124			115		

Demolition - Phase 3

Component	Amount to be Demolished	Haul Truck Capacity	Haul Distance (miles)	Total Trip Ends	Duration (days)	Trip Ends Per Day
Building (CY)	349	16	20	46	39	2
Asphalt (tons)	474	20	20	48	39	2
Total	823			94		

Note: Demolition haul distance based on CalEEMod Defaults

Architectural Coating

	Percent Painted
Interior Painted:	100%
Exterior Painted:	100%

Rule 1113

Interior Paint VOC content:	50	grams per liter
Exterior Paint VOC content:	50	grams per liter

Phase 1

Structures	Land Use Square Feet	CalEEMod Factor ²	Total Paintable Surface Area	Paintable Interior Area ¹	Paintable Exterior Area ¹
Non-Residential Structures					
Elementary School	25,764	2.0	51,528	38,646	12,882
			51,528	38,646	12,882
Parking					
Parking	32,000	6%	1,920	-	1,920
Playground/ Playfield Area	14,500	6%	870	-	870
			2,790		2,790

Phase 2

Structures	Land Use Square Feet	CalEEMod Factor ²	Total Paintable Surface Area	Paintable Interior Area ¹	Paintable Exterior Area ¹
Non-Residential Structures					
Elementary School	6,700	2.0	13,400	10,050	3,350
			13,400	10,050	3,350
Parking					
Playground/ Playfield Area	32,159	6%	1,930	-	1,930
			1,930		1,930

Phase 3

Structures	Land Use Square Feet	CalEEMod Factor ²	Total Paintable Surface Area	Paintable Interior Area ¹	Paintable Exterior Area ¹
Non-Residential Structures					
Elementary School	26,500	2.0	53,000	39,750	13,250
			53,000	39,750	13,250
Parking					
Parking	23,000	6%	1,380	-	1,380
Asphalt Surfaces/Landscaped Surfaces	13,377	6%	803	-	803
			2,183		2,183

Notes:

¹ CalEEMod methodology calculates the paintable interior and exterior areas by multiplying the total paintable surface area by 75 and 25 percent, respectively.

² The program assumes the total surface for painting equals 2.7 times the floor square footage for residential and 2.0 times that for nonresidential square footage defined by the user. Assumes 0.5 times the lot acreage (converted to square feet) for Parking

³ Assumes that all Parking

Construction Mitigation

SCAQMD Rule 403

Replace Ground Cover	PM10:	5	% Reduction
	PM25:	5	% Reduction

Water Exposed Area	Frequency:	2	per day
	PM10:	61	% Reduction
	PM25:	61	% Reduction

Unpaved Roads	Vehicle Speed:	25	mph
---------------	----------------	----	-----

SCAQMD Rule 1186

Clean Paved Road	9	% PM Reduction
------------------	---	----------------

Southern California Edison Carbon Intensity Factors

CO ₂ : ^{1,2}	449.98	pounds per megawatt hour	RPS Year: <u>2021</u>
CH ₄ : ³	0.033	pound per megawatt hour	
N ₂ O: ³	0.004	pound per megawatt hour	

Notes:

Based on CO₂e intensity factor of 452 pounds per megawatt hour; Southern California Edison. 2022. 2021 Sustainability Report.

¹ <https://www.edison.com/home/sustainability/sustainability-report.html>

Based on Intergovernmental Panel on Climate Change Fourth Assessment Report global warming potentials for CH₄ and N₂O; Intergovernmental

² Panel on Climate Change (IPCC). 2007. Fourth Assessment Report: Climate Change 2007.

³ CalEEMod2022 default values.

Global Warming Potentials (GWP)		
	AR4	AR5
CO ₂	1	1
CH ₄	25	28
N ₂ O	298	265

Based on Intergovernmental Panel on Climate Change Fourth Assessment Report global warming potentials for CH₄ and N₂O; Intergovernmental Panel on Climate Change (IPCC).

Building Demolition Haul Trip Calculation

Conversion factors*

0.046 ton/SF	Building Debris
2.0 CY/ton	Building Debris
1.2641662 tons/cy	Soil
20 tons	Truck Capacity in tons
16 CY	Truck Capacity in CY
0.791035229 CY/ton	Soil

Building	BSF Demo	Tons/SF	Tons	CY of Building Materials	Haul Truck (CY)	Round Trips	Total Trip Ends
Phase 1 Building Demolition	11,028	0.046	507	1,015	16	65	130
Phase 2 Building Demolition	397	0.046	18	37	16	3	6
Phase 3 Building Demolition	3,796	0.046	175	349	16	23	46
	15,221						

*CalEEMod User's Guide Version 2022, Appendix C

Pavement Volume to Weight Conversion

Component	Total SF of Area¹	Assumed Thickness (foot)²	Debris Volume (cu. ft)	Weight of Crushed Asphalt (lbs/cf)³	AC Mass (lbs)	AC Mass (tons)
Phase 1 Asphalt Demolition	35,284	0.333	11,761	89	1,045,452	522.73
Phase 2 Asphalt Demolition	73,424	0.333	24,475	89	2,175,526	1087.76
Phase 3 Asphalt Demolition	32,000	0.333	10,667	89	948,148	474.07
Total	140,708					2,085

¹ Based on aerial image of existing project site.

² Pavements and Surface Materials. Nonpoint Education for Municipal Officials, Technical Paper Number 8. University of Connecticut Cooperative Extension System, 1999.

³ <https://www.delmar.ca.us/DocumentCenter/View/5668/CalRecycle-Conversion-Table>

Construction Activities and Schedule Assumption

* based on information provided by the Applicant

Construction Activities	Construction Schedule		
	Start Date	End Date	CalEEMod Duration (Workday)
Phase 1			
Phase 1 Building Demolition	6/15/2023	7/12/2023	20
Phase 1 Building Demolition Debris Haul	6/15/2023	7/12/2023	20
Phase 1 Asphalt Demolition	6/15/2023	7/12/2023	20
Phase 1 Asphalt Demolition Debris Haul	6/15/2023	7/12/2023	20
Phase 1 Site Preparation	7/12/2023	7/13/2023	2
Phase 1 Rough Grading	7/13/2023	7/18/2023	4
Phase 1 Fine Grading	7/18/2023	7/23/2023	4
Phase 1 Utility Trenching	7/23/2023	7/28/2023	5
Phase 1 Building Construction	7/28/2023	5/2/2024	200
Phase 1 Paving	4/19/2024	5/2/2024	10
Phase 1 Architectural Coating	4/19/2024	5/2/2024	10
Phase 1 Finishing/Landscaping	4/26/2024	5/2/2024	5
Phase 2			
Phase 2 Building Demolition	6/15/2025	7/12/2025	20
Phase 2 Building Demolition Debris Haul	6/15/2025	7/12/2025	20
Phase 2 Asphalt Demolition	6/15/2025	7/12/2025	20
Phase 2 Asphalt Demolition Debris Haul	6/15/2025	7/12/2025	20
Phase 2 Site Preparation	7/12/2025	7/16/2025	3
Phase 2 Rough Grading	7/16/2025	7/23/2025	6
Phase 2 Fine Grading	7/23/2025	7/30/2025	6
Phase 2 Utility Trenching	7/30/2025	8/5/2025	5
Phase 2 Building Construction	8/5/2025	6/8/2026	220
Phase 2 Paving	5/26/2026	6/8/2026	10
Phase 2 Architectural Coating	5/26/2026	6/8/2026	10
Phase 2 Finishing/Landscaping	6/2/2026	6/8/2026	5
Phase 3			
Phase 3 Building Demolition	6/15/2028	6/28/2028	10
Phase 3 Building Demolition Debris Haul	6/15/2028	6/28/2028	10
Phase 3 Asphalt Demolition	6/15/2028	6/28/2028	10
Phase 3 Asphalt Demolition Debris Haul	6/15/2028	6/28/2028	10
Phase 3 Site Preparation	6/28/2028	6/28/2028	1
Phase 3 Rough Grading	6/29/2028	7/1/2028	2
Phase 3 Fine Grading	7/1/2028	7/4/2028	2
Phase 3 Utility Trenching	7/4/2028	7/10/2028	5
Phase 3 Building Construction	7/10/2028	11/25/2028	100
Phase 3 Paving	11/20/2028	11/25/2028	5
Phase 3 Architectural Coating	11/20/2028	11/25/2028	5
Phase 3 Finishing/Landscaping	11/20/2028	11/25/2028	5

Normalization Calculations Phase 1

CalEEMod Defaults Construction Duration		Assumed Construction Duration	
322	days of construction	6/15/2023	12/15/2024
0.88	years of construction	549	days
10.59	months of construction	18.05	months

Normalization Factor: 1.70

Normalization Calculations Phase 2

CalEEMod Defaults Construction Duration		Assumed Construction Duration	
358	days of construction	6/15/2025	12/15/2026
0.98	years of construction	548	days
11.77	months of construction	18.02	months

Normalization Factor: 1.53

Normalization Calculations Phase 3

CalEEMod Defaults Construction Duration		Assumed Construction Duration	
163	days of construction	6/15/2028	3/15/2030
0.45	years of construction	638	days
5.36	months of construction	20.98	months

Normalization Factor: 3.91

Overlapping Schedule			
Construction Activities	Construction Schedule		
	Start Date	End Date	CalEEMod Duration (Workday)
Phase 1			
Phase 1 Building Demolition	6/15/2023	8/1/2023	34
Phase 1 Building Demolition Debris Haul	6/15/2023	8/1/2023	34
Phase 1 Asphalt Demolition	6/15/2023	8/1/2023	34
Phase 1 Asphalt Demolition Debris Haul	6/15/2023	8/1/2023	34
Phase 1 Site Preparation	8/1/2023	8/4/2023	4
Phase 1 Rough Grading	8/4/2023	8/14/2023	7
Phase 1 Fine Grading	8/15/2023	8/22/2023	6
Phase 1 Utility Trenching	8/22/2023	8/28/2023	5
Phase 1 Building Construction	8/28/2023	12/16/2024	341
Phase 1 Paving	11/22/2024	12/16/2024	17
Phase 1 Architectural Coating	11/22/2024	12/16/2024	17
Phase 1 Finishing/Landscaping	12/10/2024	12/16/2024	5
Phase 2			
Phase 2 Building Demolition	6/15/2025	7/25/2025	30
Phase 2 Building Demolition Debris Haul	6/15/2025	7/25/2025	30
Phase 2 Asphalt Demolition	6/15/2025	7/25/2025	30
Phase 2 Asphalt Demolition Debris Haul	6/15/2025	7/25/2025	30
Phase 2 Site Preparation	7/25/2025	7/31/2025	5
Phase 2 Rough Grading	7/31/2025	8/12/2025	9
Phase 2 Fine Grading	8/13/2025	8/22/2025	8
Phase 2 Utility Trenching	8/22/2025	8/28/2025	5
Phase 2 Building Construction	8/28/2025	12/12/2026	337
Phase 2 Paving	11/21/2026	12/12/2026	15
Phase 2 Architectural Coating	11/21/2026	12/12/2026	15
Phase 2 Finishing/Landscaping	12/7/2026	12/12/2026	5
Phase 3			
Phase 3 Building Demolition	6/15/2028	8/8/2028	39
Phase 3 Building Demolition Debris Haul	6/15/2028	8/8/2028	39
Phase 3 Asphalt Demolition	6/15/2028	8/8/2028	39
Phase 3 Asphalt Demolition Debris Haul	6/15/2028	8/8/2028	39
Phase 3 Site Preparation	8/8/2028	8/13/2028	4
Phase 3 Rough Grading	8/13/2028	8/23/2028	8
Phase 3 Fine Grading	8/24/2028	9/1/2028	7
Phase 3 Utility Trenching	9/1/2028	9/7/2028	5
Phase 3 Building Construction	9/7/2028	3/10/2030	392
Phase 3 Paving	2/10/2030	3/10/2030	20
Phase 3 Architectural Coating	2/10/2030	3/10/2030	20
Phase 3 Finishing/Landscaping	3/4/2030	3/10/2030	5

Phase Name	Worker Trip Ends Per Day	Vendor Trip Ends Per Day	Haul Truck Trip Ends Per Day	Total Trip Ends Per Day	Start Date	End Date	Workdays
Phase 1							
Phase 1 Building Demolition	13	8	0	21	6/15/2023	8/1/2023	34
Phase 1 Building Demolition Debris Haul	0	0	4	4	6/15/2023	8/1/2023	34
Phase 1 Asphalt Demolition	0	0	0	0	6/15/2023	8/1/2023	34
Phase 1 Asphalt Demolition Debris Haul	0	0	2	2	6/15/2023	8/1/2023	34
Phase 1 Site Preparation	13	10	0	23	8/1/2023	8/4/2023	4
Phase 1 Rough Grading	10	10	0	20	8/4/2023	8/14/2023	7
Phase 1 Fine Grading	10	10	0	20	8/15/2023	8/22/2023	6
Phase 1 Utility Trenching	3	0	0	3	8/22/2023	8/28/2023	5
Phase 1 Building Construction	10	4	0	14	8/28/2023	12/16/2024	341
Phase 1 Paving	8	0	0	8	11/22/2024	12/16/2024	17
Phase 1 Architectural Coating	2	0	0	2	11/22/2024	12/16/2024	17
Phase 1 Finishing/Landscaping	3	0	0	3	12/10/2024	12/16/2024	5
Phase 2							
Phase 2 Building Demolition	15	8	0	23	6/15/2025	7/25/2025	30
Phase 2 Building Demolition Debris Haul	0	0	1	1	6/15/2025	7/25/2025	30
Phase 2 Asphalt Demolition	0	0	0	0	6/15/2025	7/25/2025	30
Phase 2 Asphalt Demolition Debris Haul	0	0	4	4	6/15/2025	7/25/2025	30
Phase 2 Site Preparation	13	10	0	23	7/25/2025	7/31/2025	5
Phase 2 Rough Grading	10	10	0	20	7/31/2025	8/12/2025	9
Phase 2 Fine Grading	10	10	0	20	8/13/2025	8/22/2025	8
Phase 2 Utility Trenching	3	0	0	3	8/22/2025	8/28/2025	5
Phase 2 Building Construction	2	1	0	3	8/28/2025	12/12/2026	337
Phase 2 Paving	8	0	0	8	11/21/2026	12/12/2026	15
Phase 2 Architectural Coating	1	0	0	1	11/21/2026	12/12/2026	15
Phase 2 Finishing/Landscaping	3	0	0	3	12/7/2026	12/12/2026	5
Phase 3							
Phase 3 Building Demolition	15	8	0	23	6/15/2028	8/8/2028	39
Phase 3 Building Demolition Debris Haul	0	0	2	2	6/15/2028	8/8/2028	39
Phase 3 Asphalt Demolition	0	0	0	0	6/15/2028	8/8/2028	39
Phase 3 Asphalt Demolition Debris Haul	0	0	2	2	6/15/2028	8/8/2028	39
Phase 3 Site Preparation	13	10	0	23	8/8/2028	8/13/2028	4
Phase 3 Rough Grading	10	10	0	20	8/13/2028	8/23/2028	8
Phase 3 Fine Grading	10	10	0	20	8/24/2028	9/1/2028	7
Phase 3 Utility Trenching	3	0	0	3	9/1/2028	9/7/2028	5
Phase 3 Building Construction	11	4	0	15	9/7/2028	3/10/2030	392
Phase 3 Paving	8	0	0	8	2/10/2030	3/10/2030	20
Phase 3 Architectural Coating	2	0	0	2	2/10/2030	3/10/2030	20
Phase 3 Finishing/Landscaping	3	0	0	3	3/4/2030	3/10/2030	5

Construction Activity (Overlapping)	Worker Trip Ends Per Day	Vendor Trip Ends Per Day	Haul Truck Trip Ends Per Day	Total Trip Ends Per Day	Start Date	End Date	Workdays
Phase 1							
<i>Phase 1 Building and Asphalt Demolition and Debris Haul</i>	13	8	6	27	6/15/2023	7/31/2023	33
<i>Phase 1 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	26	18	6	50	8/1/2023	8/1/2023	1
<i>Phase 1 Site Preparation</i>	13	10	0	23	8/2/2023	8/3/2023	2
<i>Phase 1 Site Preparation and Rough Grading</i>	23	20	0	43	8/4/2023	8/4/2023	1
<i>Phase 1 Rough Grading</i>	10	10	0	20	8/5/2023	8/14/2023	6
<i>Phase 1 Fine Grading</i>	10	10	0	20	8/15/2023	8/21/2023	5
<i>Phase 1 Fine Grading and Utilities Trenching</i>	13	10	0	23	8/22/2023	8/22/2023	1
<i>Phase 1 Utilities Trenching</i>	3	0	0	3	8/23/2023	8/27/2023	3
<i>Phase 1 Utilities Trenching and Building Construction (2023)</i>	13	4	0	17	8/28/2023	8/28/2023	1
<i>Phase 1 Building Construction (2023)</i>	10	4	0	14	8/29/2023	12/31/2023	89
<i>Phase 1 Building Construction (2024)</i>	10	4	0	14	1/1/2024	11/21/2024	234
<i>Phase 1 Building Construction (2024), Paving, and Architectural Coating</i>	20	4	0	24	11/22/2024	12/9/2024	12
<i>Phase 1 Building Construction (2024), Paving, Architectural Coating, and Finishing/Landscaping</i>	23	4	0	27	12/10/2024	12/16/2024	5
Phase 2							
<i>Phase 2 Building and Asphalt Demolition and Debris Haul</i>	15	8	5	28	6/15/2025	7/24/2025	29
<i>Phase 2 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	28	18	5	51	7/25/2025	7/25/2025	1
<i>Phase 2 Site Preparation</i>	13	10	0	23	7/26/2025	7/30/2025	3
<i>Phase 2 Site Preparation and Rough Grading</i>	23	20	0	43	7/31/2025	7/31/2025	1
<i>Phase 2 Rough Grading</i>	10	10	0	20	8/1/2025	8/12/2025	8
<i>Phase 2 Fine Grading</i>	10	10	0	20	8/13/2025	8/21/2025	7
<i>Phase 2 Fine Grading and Utilities Trenching</i>	13	10	0	23	8/22/2025	8/22/2025	1
<i>Phase 2 Utilities Trenching</i>	3	0	0	3	8/23/2025	8/27/2025	3
<i>Phase 2 Utilities Trenching and Building Construction (2025)</i>	5	1	0	6	8/28/2025	8/28/2025	1
<i>Phase 2 Building Construction (2025)</i>	2	1	0	3	8/29/2025	12/31/2025	89
<i>Phase 2 Building Construction (2026)</i>	2	1	0	3	1/1/2026	11/20/2026	232
<i>Phase 2 Building Construction (2026), Paving, and Architectural Coating</i>	11	1	0	12	11/21/2026	12/6/2026	10
<i>Phase 2 Building Construction (2026), Paving, Architectural Coating, and Finishing/Landscaping</i>	14	1	0	15	12/7/2026	12/12/2026	5

Phase 3							
<i>Phase 3 Building and Asphalt Demolition and Debris Haul</i>	15	8	4	27	6/15/2028	8/7/2028	38
<i>Phase 3 Building and Asphalt Demolition and Debris Haul, Site Preparation</i>	28	18	4	50	8/8/2028	8/8/2028	1
<i>Phase 3 Site Preparation</i>	13	10	0	23	8/9/2028	8/12/2028	3
<i>Phase 3 Site Preparation and Rough Grading</i>	23	20	0	43	8/13/2028	8/13/2028	0
<i>Phase 3 Rough Grading</i>	10	10	0	20	8/14/2028	8/23/2028	8
<i>Phase 3 Fine Grading</i>	10	10	0	20	8/24/2028	8/31/2028	6
<i>Phase 3 Fine Grading and Utilities Trenching</i>	13	10	0	23	9/1/2028	9/1/2028	1
<i>Phase 3 Utilities Trenching</i>	3	0	0	3	9/2/2028	9/6/2028	3
<i>Phase 3 Utilities Trenching and Building Construction (2028)</i>	14	4	0	18	9/7/2028	9/7/2028	1
<i>Phase 3 Building Construction (2028)</i>	11	4	0	15	9/8/2028	12/31/2028	81
<i>Phase 3 Building Construction (2029)</i>	11	4	0	15	1/1/2029	12/31/2029	261
<i>Phase 3 Building Construction (2030)</i>	11	4	0	15	1/1/2030	2/9/2030	29
<i>Phase 3 Building Construction (2030), Paving, and Architectural Coating</i>	21	4	0	25	2/10/2030	3/3/2030	15
<i>Phase 3 Building Construction (2030), Paving, Architectural Coating, and Finishing/Landscaping</i>	24	4	0	28	3/4/2030	3/10/2030	5
	28	20	6	51			

CalEEMod Construction Off-Road Equipment Inputs

*Based on CalEEMod defaults, assumed equipment would not be shared for most conservative results

General Construction Hours: 8 hours btwn 7:00 AM to 4:00 PM (with 1 hr break), Mon-Fri

Water Truck Vendor Trip Calculation

Amount of Water (gal/acre/day) ¹	Water Truck Capacity (gallons) ²
10,000	4,000

Notes:

¹ Based on data provided in Guidance for Application for Dust Control Permit

Maricopa County Air Quality Department. 2005, June. Guidance for Application of Dust Control Permit.
https://www.epa.gov/sites/default/files/2019-04/documents/mr_guidanceforapplicationfordustcontrolpermit.pdf

² Based on standard water truck capacity:

McLellan Industries. 2022, January (access). Water Trucks. <https://www.mclellanindustries.com/trucks/water-trucks/>

³ Assumes that dozers, tractors/loaders/backhoes, and graders can disturb 0.50 acres per day and scrapers can disturb 1 acre per day.

Construction Equipment Details						
Equipment	model	# of Equipment	hr/day	hp	load factor*	total trips
Building Demolition						
Front End Loader		1	8	84	0.37	
Forklift		2	8	82	0.2	
Skid Steer		2	8	71	0.37	
Worker Trips						13
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.5		8
Building Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						4
Asphalt Demolition						
assumes asphalt demolition equipment is shared building demolition equipment						
Worker Trips						0
Vendor Trips						0
Hauling Trips						0
Asphalt Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						2
Site Preparation						
Skip Loaders		3	8	84	0.37	
Backhoe		1	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						13
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	2		10
Rough Grading						
Graders		1	8	148	0.41	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Rubber Tired Dozers		1	8	367	0.4	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.875		10

Fine Grading						
Graders		1	8	148	0.41	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Rubber Tired Dozers		1	8	367	0.4	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.875		10
Utilities Trenching						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0
Building Construction						
Cranes		1	6	367	0.29	
Forklifts		1	6	82	0.2	
Generator Sets		1	8	14	0.74	
Tractors/Loaders/Backhoes		1	6	84	0.37	
Welders		3	8	46	0.45	
Worker Trips						10
Vendor Trips						4
Hauling Trips						0
Paving						
Skip Loader		2	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						8
Vendor Trips						0
Hauling Trips						0
Architectural Coating (surface lots, etc...)						
Generator		2	8	14	0.74	
Worker Trips						2
Vendor Trips						0
Hauling Trips						0
Finishing/Landscaping						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0

CalEEMod Construction Off-Road Equipment Inputs

*Based on CalEEMod defaults, assumed equipment would not be shared for most conservative results

General Construction Hours: 8 hours btwn 7:00 AM to 4:00 PM (with 1 hr break), Mon-Fri

Water Truck Vendor Trip Calculation

Amount of Water (gal/acre/day) ¹	Water Truck Capacity (gallons) ²
10,000	4,000

Notes:

¹ Based on data provided in Guidance for Application for Dust Control Permit

https://www.epa.gov/sites/default/files/2019-04/documents/mr_guidanceforapplicationfordustcontrolpermit.pdf

² Based on standard water truck capacity:

McLellan Industries. 2022, January (access). Water Trucks. <https://www.mclellanindustries.com/trucks/water-trucks/>

³ Assumes that dozers, tractors/loaders/backhoes, and graders can disturb 0.50 acres per day and scrapers can disturb 1 acre per day.

Construction Equipment Details						
Equipment	model	# of Equipment	hr/day	hp	load factor*	total trips
Building Demolition						
Front End Loader		1	8	84	0.37	
Skip Loader		2	8	84	0.37	
Forklift		2	8	82	0.2	
Excavator		1	8	36	0.38	
Worker Trips						15
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.5		8
Building Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						1
Asphalt Demolition						
assumes asphalt demolition equipment is shared building demolition equipment						
Worker Trips						0
Vendor Trips						0
Hauling Trips						0
Asphalt Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						4
Site Preparation						
Skip Loader		3	8	84	0.37	
Backhoe		1	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						13
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	2		10
Rough Grading						
Graders		1	8	148	0.41	
Rubber Tired Dozers		1	8	367	0.4	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.875		10

Fine Grading						
Graders		1	8	148	0.41	
Rubber Tired Dozers		1	8	367	0.4	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.875		10
Utilities Trenching						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0
Building Construction						
Cranes		1	8	367	0.29	
Forklifts		2	7	82	0.2	
Generator Sets		1	8	14	0.74	
Tractors/Loaders/Backhoes		1	6	84	0.37	
Welders		3	8	46	0.45	
Worker Trips						2
Vendor Trips						1
Hauling Trips						0
Paving						
Skip Loader		2	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						8
Vendor Trips						0
Hauling Trips						0
Architectural Coating (surface lots, etc...)						
Air Compressors		1	6	37	0.48	
Worker Trips						1
Vendor Trips						0
Hauling Trips						0
Finishing/Landscaping						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0

CalEEMod Construction Off-Road Equipment Inputs

*Based on CalEEMod defaults, assumed equipment would not be shared for most conservative results

General Construction Hours: 8 hours

btwn 7:00 AM to 4:00 PM (with 1 hr break), Mon-Fri

Water Truck Vendor Trip Calculation

Amount of Water (gal/acre/day) ¹	Water Truck Capacity (gallons) ²
10,000	4,000

Notes:

¹ Based on data provided in Guidance for Application for Dust Control Permit

https://www.epa.gov/sites/default/files/2019-04/documents/mr_guidanceforapplicationfordustcontrolpermit.pdf

² Based on standard water truck capacity:

McLellan Industries. 2022, January (access). Water Trucks. <https://www.mclellanindustries.com/trucks/water-trucks/>

³ Assumes that dozers, tractors/loaders/backhoes, and graders can disturb 0.50 acres per day and scrapers can disturb 1 acre per day.

Construction Equipment Details						
Equipment	model	# of Equipment	hr/day	hp	load factor*	total trips
Building Demolition						
Front End Loader		1	8	84	0.37	
Skip Loader		2	8	84	0.37	
Forklift		2	8	82	0.2	
Excavator		1	8	36	0.38	
Worker Trips						15
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.5		8
Building Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						2
Asphalt Demolition						
assumes asphalt demolition equipment is shared building demolition equipment						
Worker Trips						0
Vendor Trips						0
Hauling Trips						0
Asphalt Demolition Debris Haul						
no additional equipment required for debris hauling						
Worker Trips						0
Vendor Trips						0
Hauling Trips						2
Site Preparation						
Skip Loader		3	8	84	0.37	
Backhoe		1	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						13
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	2		10
Rough Grading						
Graders		1	8	148	0.41	
Rubber Tired Dozers		1	8	367	0.4	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)			Acres Disturbed:	1.875		10

Fine Grading						
Graders		1	8	148	0.41	
Rubber Tired Dozers		1	8	367	0.4	
Tractors/Loaders/Backhoes		2	7	84	0.37	
Worker Trips						10
Vendor Trips						0
Hauling Trips						0
Water Trucks (Added to Vendor Trips)	Acres Disturbed:			1.875		10
Utilities Trenching						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0
Building Construction						
Cranes		1	6	367	0.29	
Forklifts		1	6	82	0.2	
Generator Sets		1	8	14	0.74	
Tractors/Loaders/Backhoes		1	6	84	0.37	
Welders		3	8	46	0.45	
Worker Trips						11
Vendor Trips						4
Hauling Trips						0
Paving						
Skip Loader		2	8	84	0.37	
Compaction Roller		1	8	36	0.38	
Worker Trips						8
Vendor Trips						0
Hauling Trips						0
Architectural Coating (surface lots, etc...)						
Air Compressors		1	6	37	0.48	
Worker Trips						2
Vendor Trips						0
Hauling Trips						0
Finishing/Landscaping						
Excavators		1	8	36	0.38	
Worker Trips						3
Vendor Trips						0
Hauling Trips						0

CalEEMod Inputs- McKinley Elementary School, Operations

Name: McKinley Elementary School, Operations
Project Number: SMM-07
Project Location: North of 23rd Ct and Santa Monica Blvd
County/Air Basin: Los Angeles - South Coast AQMD
Climate Zone: 11
Land Use Setting: Urban
Operational Year: 2028
Utility Company: Southern California Edison
Air Basin: South Coast Air Basin
Air District: South Coast AQMD
SRA: 2 - Northwest Coastal LA County

Proposed Project				
Project Components	Stories	SQFT	Building Footprint	Acres
Phase 1				
Two-Story Classroom Building	2	24,410	12,205	0.28
Phase 2				
Elevator and Stair Core Reconstruction	2	870	435	0.01
Lunch Shelter	1	3,500	3,500	0.08
Phase 3				
Two-Story Classroom Building	2	26,500	13,250	0.30
TOTAL BUILDING SQFT		55,280	29,390	0.67
Parking Lot		24,306		0.56
Other Asphalt Surfaces		15,262		0.35
Landscaping		43,651		1.00
Hardscape		80,527		1.85
Remaining Area		754		0.02

Operational Energy Use

Land Use Subtype ¹	Total Annual Electricity Consumption (kWh/year)	Total Annual Natural Gas Consumption (kBtu/year)	Title-24 Electricity Energy Intensity (kWhr/size/year)*	Title-24 Natural Gas Energy Intensity (kBtu/size/year)*	Nontitle-24	
					Electricity Intensity (kWhr/size/year)	Nontitle-24 Natural Gas Energy Intensity (kBtu/size/year)
Elementary School Rates	6,254.30	20,979.90	5,406.80	10,671.50	847.50	10,308.40
Parking Lot Rates	876.00	0.00	876.00	0.00	0.00	0.00
New Elementary School Buildings	345,738	1,159,768.87	298,887.90	589,920.52	46,849.80	569,848.35
New Parking Lot	21,292	0.00	21,292.06	0.00	0.00	0.00
TOTAL	367,030	1,159,769				

CalEEMod Construction Model

1. Basic Project Information

1.1. Basic Project Information

Data Field	Value
Project Name	McKinley Elementary School Mitigated Construction (Phase 1)
Lead Agency	
Land Use Scale	Project/site
Analysis Level for Defaults	County
Windspeed (m/s)	2.7
Precipitation (days)	18.4
Location	2401 Santa Monica Blvd, Santa Monica, CA 90404, USA
County	Los Angeles-South Coast
City	Santa Monica
Air District	South Coast AQMD
Air Basin	South Coast
TAZ	4409
EDFZ	7
Electric Utility	Southern California Edison
Gas Utility	Southern California Gas

1.2. Land Use Types

Land Use Subtype	Size	Unit	Lot Acreage	Building Area	Landscape Area	Special Land	Population	Description
Elementary School	24.4	1000sqft	0.31	24410	0		0	
Parking Lot	32	1000sqft	0.73	0	0		0	
Other Asphalt Surfaces	10.2	1000sqft	0.24	0	0		0	
Other Non-Asphalt Surfaces	3.13	1000sqft	0.07	0	3133		0	
Other Non-Asphalt Surfaces	26.9	1000sqft	0.62	0	0		0	

1.3. User-Selected Emission Reduction Measures by Emissions Sector

Sector	#	Measure Title
Construction	C-5	Use Advanced Engine Tiers

2. Emissions Summary

2.1. Construction Emissions Compared Against Thresholds

Un/Mit.	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily - Summer (Max)																			
Unmit.																			
Mit.	0.54	0.49	5.47	25.6	0.04	0.08	3.23	3.31	0.08	1.45	1.53		4736	4736	0.19	0.18	4.08	4783	
% Reduced																			
Daily - Winter (Max)																			
Unmit.																			
Mit.	0.78	8.64	7.83	19.6	0.03	0.15	0.33	0.47	0.14	0.08	0.22		3301	3301	0.14	0.05	0.04	3320	
% Reduced																			
Average Daily (Max)																			
Unmit.																			
Mit.	0.28	0.62	3.26	8.41	0.01	0.05	0.22	0.24	0.05	0.07	0.09		1473	1473	0.06	0.03	0.28	1483	
% Reduced																			
Annual (Max)																			
Unmit.																			
Mit.	0.05	0.11	0.6	1.53	< 0.005	0.01	0.04	0.04	0.01	0.01	0.02		244	244	0.01	< 0.005	0.05	246	
% Reduced																			

2.2. Construction Emissions by Year, Unmitigated

Year	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily - Summer (Max)																			
Daily - Winter (Max)																			
Average Daily																			
Annual																			

2.3. Construction Emissions by Year, Mitigated

Year	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily - Summer (Max)																			
2023	0.54	0.49	5.47	25.6	0.04	0.08	3.23	3.31	0.08	1.45	1.53		4736	4736	0.19	0.18	4.08	4783	
2024	0.38	0.35	4.54	11.8	0.02	0.07	0.17	0.23	0.06	0.04	0.1		2075	2075	0.08	0.04	0.92	2089	
Daily - Winter (Max)																			
2023	0.39	0.35	4.57	11.8	0.02	0.07	0.17	0.24	0.06	0.04	0.1		2072	2072	0.08	0.04	0.03	2086	
2024	0.78	8.64	7.83	19.6	0.03	0.15	0.33	0.47	0.14	0.08	0.22		3301	3301	0.14	0.05	0.04	3320	
Average Daily																			
2023	0.13	0.12	1.57	4.41	0.01	0.02	0.22	0.24	0.02	0.07	0.09		819	819	0.03	0.02	0.23	827	
2024	0.28	0.62	3.26	8.41	0.01	0.05	0.12	0.17	0.05	0.03	0.08		1473	1473	0.06	0.03	0.28	1483	
Annual																			
2023	0.02	0.02	0.29	0.81	< 0.005	< 0.005	0.04	0.04	< 0.005	0.01	0.02		136	136	0.01	< 0.005	0.04	137	
2024	0.05	0.11	0.6	1.53	< 0.005	0.01	0.02	0.03	0.01	0.01	0.01		244	244	0.01	< 0.005	0.05	246	

3. Construction Emissions Details

3.2. Demolition (2023) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0.14	0.14	2.83	7.6	0.01	0.02		0.02	0.02		0.02		1084	1084	0.04	0.01		1088	
Demolition								0	0		0		0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment	0.01	0.01	0.26	0.71	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		101	101	< 0.005	< 0.005		101	
Demolition								0	0		0		0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	< 0.005	< 0.005	0.05	0.13	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		16.7	16.7	< 0.005	< 0.005		16.8	
Demolition								0	0		0		0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0.07	0.06	0.07	1.02	0	0	0.16	0.16	0	0.04	0.04		180	180	0.01	0.01	0.77	183	
Vendor	0.02	0.01	0.32	0.16	< 0.005	< 0.005	0.07	0.07	< 0.005	0.02	0.02		262	262	0.01	0.04	0.7	273	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Worker	0.01	0.01	0.01	0.08	0	0	0.02	0.02	0	< 0.005	< 0.005		16.2	16.2	< 0.005	< 0.005	0.03	16.4	
Vendor	< 0.005	< 0.005	0.03	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005		24.4	24.4	< 0.005	< 0.005	0.03	25.4	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Worker	< 0.005	< 0.005	< 0.005	0.02	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		2.68	2.68	< 0.005	< 0.005	0.01	2.71	
Vendor	< 0.005	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		4.04	4.04	< 0.005	< 0.005	< 0.005	4.21	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0

3.4. Demolition (2023) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Demolition								0.21	0.21		0.03		0.03						

Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
3.26. Trenching (2024) - Mitigated																				
Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	B _{CO2}	N _{BCO2}	CO ₂ T	CH ₄	N ₂ O	R	CO _{2e}		
Onsite																				
Daily, Summer (Max)																				
Daily, Winter (Max)																				
Off-Road Equipment	0.02	0.02	0.66	0.99	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		142	142	0.01	< 0.005				142
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																				
Off-Road Equipment	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		1.94	1.94	< 0.005	< 0.005				1.95
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																				
Off-Road Equipment	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		0.32	0.32	< 0.005	< 0.005				0.32
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																				
Daily, Summer (Max)																				
Daily, Winter (Max)																				
Worker	0.01	0.01	0.01	0.16	0	0	0.03	0.03	0	0.01	0.01		33.5	33.5	< 0.005	< 0.005	< 0.005			33.9
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																				
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.47	0.47	< 0.005	< 0.005	< 0.005			0.47
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																				
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.08	0.08	< 0.005	< 0.005	< 0.005			0.08
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

5. Activity Data

5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Phase 1 Building Demolition	Demolition	6/15/2023	8/1/2023		5	34
Phase 1 Building Demolition Debris Haul	Demolition	6/15/2023	8/1/2023		5	34
Phase 1 Asphalt Demolition	Demolition	6/15/2023	8/1/2023		5	34
Phase 1 Asphalt Demolition Debris Haul	Demolition	6/15/2023	8/1/2023		5	34
Phase 1 Site Preparation	Site Preparation	8/1/2023	8/4/2023		5	4
Phase 1 Rough Grading	Grading	8/4/2023	8/14/2023		5	7
Phase 1 Fine Grading	Grading	8/15/2023	8/22/2023		5	6
Phase 1 Building Construction	Building Construction	8/28/2023	12/16/2024		5	341
Phase 1 Paving	Paving	11/22/2024	12/16/2024		5	17
Phase 1 Architectural Coating	Architectural Coating	11/22/2024	12/16/2024		5	17
Phase 1 Utility Trenching	Trenching	8/22/2023	8/28/2023		5	5
Phase 1 Finishing/Landscaping	Trenching	12/10/2024	12/16/2024		5	5

5.2. Off-Road Equipment

5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 1 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Average	1	8	84	0.37
Phase 1 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Average	4	8	84	0.37
Phase 1 Rough Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 1 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 1 Rough Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 1 Paving	Tractors/Loaders/Backhoes	Diesel	Average	2	8	84	0.37
Phase 1 Paving	Rollers	Diesel	Average	1	8	36	0.38
Phase 1 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Fine Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 1 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 1 Fine Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 1 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 1 Site Preparation	Rubber Tired Dozers	Diesel	Average	0	7	367	0.4
Phase 1 Building Construction	Cranes	Diesel	Average	1	6	367	0.29
Phase 1 Building Construction	Forklifts	Diesel	Average	1	6	82	0.2
Phase 1 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 1 Building Construction	Tractors/Loaders/Backhoes	Diesel	Average	1	6	84	0.37
Phase 1 Building Construction	Welders	Diesel	Average	3	8	46	0.45
Phase 1 Paving	Cement and Mortar Mixers	Diesel	Average	0	6	10	0.56
Phase 1 Paving	Pavers	Diesel	Average	0	6	81	0.42
Phase 1 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36
Phase 1 Architectural Coating	Air Compressors	Diesel	Average	0	6	37	0.48
Phase 1 Building Demolition	Forklifts	Diesel	Average	2	8	82	0.2
Phase 1 Building Demolition	Skid Steer Loaders	Diesel	Average	2	8	71	0.37
Phase 1 Site Preparation	Rollers	Diesel	Average	1	8	36	0.38
Phase 1 Architectural Coating	Generator Sets	Diesel	Average	2	8	14	0.74
Phase 1 Utility Trenching	Excavators	Diesel	Average	1	8	36	0.38
Phase 1 Finishing/Landscaping	Excavators	Diesel	Average	1	8	36	0.38

5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 1 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	1	8	84	0.37
Phase 1 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	4	8	84	0.37
Phase 1 Rough Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 1 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37
Phase 1 Rough Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 1 Paving	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	8	84	0.37
Phase 1 Paving	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 1 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 1 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Fine Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 1 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37
Phase 1 Fine Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 1 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 1 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 1 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 1 Site Preparation	Rubber Tired Dozers	Diesel	Average	0	7	367	0.4
Phase 1 Building Construction	Cranes	Diesel	Tier 4 Final	1	6	367	0.29
Phase 1 Building Construction	Forklifts	Diesel	Tier 4 Final	1	6	82	0.2
Phase 1 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 1 Building Construction	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	1	6	84	0.37
Phase 1 Building Construction	Welders	Diesel	Tier 4 Final	3	8	46	0.45
Phase 1 Paving	Cement and Mortar Mixers	Diesel	Average	0	6	10	0.56
Phase 1 Paving	Pavers	Diesel	Average	0	6	81	0.42
Phase 1 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36

Phase 1 Architectural Coating	Air Compressors	Diesel	Average	0	6	37	0.48
Phase 1 Building Demolition	Forklifts	Diesel	Tier 4 Final	2	8	82	0.2
Phase 1 Building Demolition	Skid Steer Loaders	Diesel	Tier 4 Final	2	8	71	0.37
Phase 1 Site Preparation	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 1 Architectural Coating	Generator Sets	Diesel	Average	2	8	14	0.74
Phase 1 Utility Trenching	Excavators	Diesel	Tier 4 Final	1	8	36	0.38
Phase 1 Finishing/Landscaping	Excavators	Diesel	Tier 4 Final	1	8	36	0.38

5.3. Construction Vehicles

5.3.1. Unmitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 1 Building Demolition				
Phase 1 Building Demolition	Worker	12.5	18.5	LDA, LDT1, LDT2
Phase 1 Building Demolition	Vendor	8	10.2	HHDT, MHDT
Phase 1 Building Demolition	Hauling	0	20	HHDT
Phase 1 Building Demolition	Onsite truck	0		HHDT
Phase 1 Site Preparation				
Phase 1 Site Preparation	Worker	12.5	18.5	LDA, LDT1, LDT2
Phase 1 Site Preparation	Vendor	10	10.2	HHDT, MHDT
Phase 1 Site Preparation	Hauling	0	20	HHDT
Phase 1 Site Preparation	Onsite truck	0		HHDT
Phase 1 Rough Grading				
Phase 1 Rough Grading	Worker	10	18.5	LDA, LDT1, LDT2
Phase 1 Rough Grading	Vendor	10	10.2	HHDT, MHDT
Phase 1 Rough Grading	Hauling	0	20	HHDT
Phase 1 Rough Grading	Onsite truck	0		HHDT
Phase 1 Paving				
Phase 1 Paving	Worker	7.5	18.5	LDA, LDT1, LDT2
Phase 1 Paving	Vendor	0	10.2	HHDT, MHDT
Phase 1 Paving	Hauling	0	20	HHDT
Phase 1 Paving	Onsite truck	0		HHDT
Phase 1 Building Demolition Debris Haul				
Phase 1 Building Demolition Debris Haul	Worker	0	18.5	LDA, LDT1, LDT2
Phase 1 Building Demolition Debris Haul	Vendor	0	10.2	HHDT, MHDT
Phase 1 Building Demolition Debris Haul	Hauling	4	20	HHDT
Phase 1 Building Demolition Debris Haul	Onsite truck	0		HHDT
Phase 1 Asphalt Demolition				
Phase 1 Asphalt Demolition	Worker	0	18.5	LDA, LDT1, LDT2
Phase 1 Asphalt Demolition	Vendor	0	10.2	HHDT, MHDT
Phase 1 Asphalt Demolition	Hauling	0	20	HHDT
Phase 1 Asphalt Demolition	Onsite truck	0		HHDT
Phase 1 Asphalt Demolition Debris Haul				
Phase 1 Asphalt Demolition Debris Haul	Worker	0	18.5	LDA, LDT1, LDT2
Phase 1 Asphalt Demolition Debris Haul	Vendor	0	10.2	HHDT, MHDT
Phase 1 Asphalt Demolition Debris Haul	Hauling	2	20	HHDT
Phase 1 Asphalt Demolition Debris Haul	Onsite truck	0		HHDT
Phase 1 Fine Grading				
Phase 1 Fine Grading	Worker	10	18.5	LDA, LDT1, LDT2
Phase 1 Fine Grading	Vendor	10	10.2	HHDT, MHDT
Phase 1 Fine Grading	Hauling	0	20	HHDT
Phase 1 Fine Grading	Onsite truck	0		HHDT
Phase 1 Architectural Coating				
Phase 1 Architectural Coating	Worker	2.05	18.5	LDA, LDT1, LDT2
Phase 1 Architectural Coating	Vendor	0	10.2	HHDT, MHDT
Phase 1 Architectural Coating	Hauling	0	20	HHDT
Phase 1 Architectural Coating	Onsite truck	0		HHDT
Phase 1 Utility Trenching				
Phase 1 Utility Trenching	Worker	2.5	18.5	LDA, LDT1, LDT2
Phase 1 Utility Trenching	Vendor	0	10.2	HHDT, MHDT
Phase 1 Utility Trenching	Hauling	0	20	HHDT
Phase 1 Utility Trenching	Onsite truck	0		HHDT
Phase 1 Finishing/Landscaping				
Phase 1 Finishing/Landscaping	Worker	2.5	18.5	LDA, LDT1, LDT2
Phase 1 Finishing/Landscaping	Vendor	0	10.2	HHDT, MHDT
Phase 1 Finishing/Landscaping	Hauling	0	20	HHDT
Phase 1 Finishing/Landscaping	Onsite truck	0		HHDT
Phase 1 Building Construction				
Phase 1 Building Construction	Worker	10.3	18.5	LDA, LDT1, LDT2
Phase 1 Building Construction	Vendor	4	10.2	HHDT, MHDT
Phase 1 Building Construction	Hauling	0	20	HHDT
Phase 1 Building Construction	Onsite truck	0		HHDT

5.3.2. Mitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 1 Building Demolition				
Phase 1 Building Demolition	Worker	12.5	18.5	LDA, LDT1, LDT2
Phase 1 Building Demolition	Vendor	8	10.2	HHDT, MHDT
Phase 1 Building Demolition	Hauling	0	20	HHDT
Phase 1 Building Demolition	Onsite truck	0		HHDT
Phase 1 Site Preparation				
Phase 1 Site Preparation	Worker	12.5	18.5	LDA, LDT1, LDT2
Phase 1 Site Preparation	Vendor	10	10.2	HHDT, MHDT
Phase 1 Site Preparation	Hauling	0	20	HHDT
Phase 1 Site Preparation	Onsite truck	0		HHDT
Phase 1 Rough Grading				
Phase 1 Rough Grading	Worker	10	18.5	LDA, LDT1, LDT2
Phase 1 Rough Grading	Vendor	10	10.2	HHDT, MHDT
Phase 1 Rough Grading	Hauling	0	20	HHDT
Phase 1 Rough Grading	Onsite truck	0		HHDT
Phase 1 Paving				
Phase 1 Paving	Worker	7.5	18.5	LDA, LDT1, LDT2
Phase 1 Paving	Vendor	0	10.2	HHDT, MHDT
Phase 1 Paving	Hauling	0	20	HHDT

Phase 1 Paving	Onsite truck	0	HHDT
Phase 1 Building Demolition Debris Haul			
Phase 1 Building Demolition Debris Haul	Worker	0	18.5 LDA,LDT1,LDT2
Phase 1 Building Demolition Debris Haul	Vendor	0	10.2 HHDT,MHDT
Phase 1 Building Demolition Debris Haul	Hauling	4	20 HHDT
Phase 1 Building Demolition Debris Haul	Onsite truck	0	HHDT
Phase 1 Asphalt Demolition			
Phase 1 Asphalt Demolition	Worker	0	18.5 LDA,LDT1,LDT2
Phase 1 Asphalt Demolition	Vendor	0	10.2 HHDT,MHDT
Phase 1 Asphalt Demolition	Hauling	0	20 HHDT
Phase 1 Asphalt Demolition	Onsite truck	0	HHDT
Phase 1 Asphalt Demolition Debris Haul			
Phase 1 Asphalt Demolition Debris Haul	Worker	0	18.5 LDA,LDT1,LDT2
Phase 1 Asphalt Demolition Debris Haul	Vendor	0	10.2 HHDT,MHDT
Phase 1 Asphalt Demolition Debris Haul	Hauling	2	20 HHDT
Phase 1 Asphalt Demolition Debris Haul	Onsite truck	0	HHDT
Phase 1 Fine Grading			
Phase 1 Fine Grading	Worker	10	18.5 LDA,LDT1,LDT2
Phase 1 Fine Grading	Vendor	10	10.2 HHDT,MHDT
Phase 1 Fine Grading	Hauling	0	20 HHDT
Phase 1 Fine Grading	Onsite truck	0	HHDT
Phase 1 Architectural Coating			
Phase 1 Architectural Coating	Worker	2.05	18.5 LDA,LDT1,LDT2
Phase 1 Architectural Coating	Vendor	0	10.2 HHDT,MHDT
Phase 1 Architectural Coating	Hauling	0	20 HHDT
Phase 1 Architectural Coating	Onsite truck	0	HHDT
Phase 1 Utility Trenching			
Phase 1 Utility Trenching	Worker	2.5	18.5 LDA,LDT1,LDT2
Phase 1 Utility Trenching	Vendor	0	10.2 HHDT,MHDT
Phase 1 Utility Trenching	Hauling	0	20 HHDT
Phase 1 Utility Trenching	Onsite truck	0	HHDT
Phase 1 Finishing/Landscaping			
Phase 1 Finishing/Landscaping	Worker	2.5	18.5 LDA,LDT1,LDT2
Phase 1 Finishing/Landscaping	Vendor	0	10.2 HHDT,MHDT
Phase 1 Finishing/Landscaping	Hauling	0	20 HHDT
Phase 1 Finishing/Landscaping	Onsite truck	0	HHDT
Phase 1 Building Construction			
Phase 1 Building Construction	Worker	10.3	18.5 LDA,LDT1,LDT2
Phase 1 Building Construction	Vendor	4	10.2 HHDT,MHDT
Phase 1 Building Construction	Hauling	0	20 HHDT
Phase 1 Building Construction	Onsite truck	0	HHDT

5.4. Vehicles

5.4.1. Construction Vehicle Control Strategies

Control Strategies Applied	PM10 Reduction	PM2.5 Reduction
Water unpaved roads twice daily	55	55
Limit vehicle speeds on unpaved roads to 25 mph	44	44
Sweep paved roads once per month	9	9

5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Phase 1 Architectural Coating	0	0	38646	12882	2790

5.6. Dust Mitigation

5.6.1. Construction Earthmoving Activities

Phase Name	Material Imported (Cubic Yards)	Material Exported (Cubic Yards)	Acres Graded (acres)	Material Demolished (Ton)	Acres Paved (acres)
Phase 1 Building Demolition	0	0	0	0	0
Phase 1 Building Demolition Debris Haul	0	0	0	0	507
Phase 1 Asphalt Demolition	0	0	0	0	0
Phase 1 Asphalt Demolition Debris Haul	0	0	0	0	523
Phase 1 Site Preparation	0	0	0	0	0
Phase 1 Rough Grading	0	0	7	0	0
Phase 1 Fine Grading	0	0	6	0	0
Phase 1 Paving	0	0	0	0	1.66

5.6.2. Construction Earthmoving Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Exposed Area	2	61	61
Water Demolished Area	2	36	36

5.7. Construction Paving Land Use

Elementary School	Area Paved (acres)	% Asphalt
Elementary School	0	0
Parking Lot	0.73	100
Other Asphalt Surfaces	0.24	100
Other Non-Asphalt Surfaces	0.07	0
Other Non-Asphalt Surfaces	0.62	0

5.8. Construction Electricity Consumption and Emissions Factors

Year	kWh per Year	CO2	CH4	N2O
2023	0	450	0.03	< 0.005
2024	0	450	0.03	< 0.005

8. User Changes to Default Data Screen	Justification
Characteristics: Project Details	
Characteristics: Utility Information Land Use	SCE 2021 Sustainability Report based on information from District
Construction: Construction Phases	based on CalEEMod default construction schedule, normalized to fit schedule provided by District
Construction: Off-Road Equipment	based on equipment list provided by applicant. CalEEMod defaults used for grading activities and building construction
Construction: Trips and VMT	See assumptions file for water truck calculations and demolition haul calculations
Construction: Architectural Coatings	South Coast Rule 1113 applied. Includes coating for renovated library. Parking area only includes area to be striped.
Construction: Electricity	SCE 2021 Sustainability Report

1. Basic Project Information

1.1. Basic Project Information

Data Field	Value
Project Name	McKinley Elementary School Mitigated Construction (Phase 2)
Lead Agency	
Land Use Scale	Project/site
Analysis Level for Defaults	County
Windspeed (m/s)	2.7
Precipitation (days)	18.4
Location	34.032286176402195, -118.47783688338554
County	Los Angeles-South Coast
City	Santa Monica
Air District	South Coast AQMD
Air Basin	South Coast
TAZ	4409
EDFZ	7
Electric Utility	Southern California Edison
Gas Utility	Southern California Gas

1.2. Land Use Types

Land Use Subtype	Size	Unit	Lot Acreage	Building Area	Landscaping Area	Special Land	Population	Description
Elementary School	4.37	1000sqft	0.1	4370	0		0	
Other Asphalt Surfaces	2.44	1000sqft	0.06	0	0			
Other Non-Asphalt Surfaces	29.7	1000sqft	0.68	0	29720			
Other Non-Asphalt Surfaces	86.7	1000sqft	1.99	0	0			

1.3. User-Selected Emission Reduction Measures by Emissions Sector

Sector	#	Measure Title
Construction	C-5	Use Advanced Engine Tiers

2. Emissions Summary

2.1. Construction Emissions Compared Against Thresholds

Un/Mit.	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily, Summer (Max)																			
Unmit.	2.63	2.19	20.2	25.1	0.04	0.86	3.23	4.09	0.79	1.45	2.24		4704	4704	0.19	0.17	3.76	4750	
Mit.	0.52	0.48	5.24	25.3	0.04	0.08	3.23	3.31	0.08	1.45	1.53		4704	4704	0.19	0.17	3.76	4750	
% Reduced	80.4	78.2	74	-0.81		90.8		19.1	90.5		31.9								
Daily, Winter (Max)																			
Unmit.	2.12	4.45	14.8	19.4	0.03	0.51	0.17	0.69	0.47	0.04	0.51		3386	3386	0.14	0.04	0.02	3400	
Mit.	0.53	3.18	6.87	21	0.03	0.09	0.17	0.26	0.09	0.04	0.13		3386	3386	0.14	0.04	0.02	3400	
% Reduced	75	28.5	53.6	-8.08		82.7		61.8	81.7		75.2								
Average Daily (Max)																			
Unmit.	0.99	0.93	7.04	8.32	0.02	0.25	0.22	0.37	0.23	0.08	0.24		1564	1564	0.06	0.02	0.13	1570	
Mit.	0.25	0.35	3.17	9.36	0.02	0.05	0.22	0.24	0.05	0.08	0.1		1564	1564	0.06	0.02	0.13	1570	
% Reduced	74.3	62.7	55	-12.5		80.5		34.7	79.6		56.2								
Annual (Max)																			
Unmit.	0.18	0.17	1.28	1.52	< 0.005	0.05	0.04	0.07	0.04	0.01	0.04		259	259	0.01	< 0.005	0.02	260	
Mit.	0.05	0.06	0.58	1.71	< 0.005	0.01	0.04	0.04	0.01	0.01	0.02		259	259	0.01	< 0.005	0.02	260	
% Reduced	74.3	62.7	55	-12.5		80.5		34.7	79.6		56.2								

2.2. Construction Emissions by Year, Unmitigated

Year	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily - Summer (Max)																			
2025	2.63	2.19	20.2	25.1	0.04	0.86	3.23	4.09	0.79	1.45	2.24		4704	4704	0.19	0.17	3.76	4750	
2026	1.42	1.19	10.1	11.9	0.02	0.36	0.03	0.39	0.33	0.01	0.34		2248	2248	0.09	0.02	0.14	2257	
Daily - Winter (Max)																			
2025	1.5	1.25	10.6	12	0.02	0.4	0.03	0.43	0.37	0.01	0.38		2248	2248	0.09	0.02	< 0.005	2257	
2026	2.12	4.45	14.8	19.4	0.03	0.51	0.17	0.69	0.47	0.04	0.51		3386	3386	0.14	0.04	0.02	3400	
Average Daily																			
2025	0.53	0.44	3.92	4.64	0.01	0.15	0.22	0.37	0.14	0.08	0.22		891	891	0.04	0.02	0.13	897	
2026	0.99	0.93	7.04	8.32	0.02	0.25	0.03	0.28	0.23	0.01	0.24		1564	1564	0.06	0.02	0.05	1570	
Annual																			
2025	0.1	0.08	0.71	0.85	< 0.005	0.03	0.04	0.07	0.03	0.01	0.04		147	147	0.01	< 0.005	0.02	149	
2026	0.18	0.17	1.28	1.52	< 0.005	0.05	< 0.005	0.05	0.04	< 0.005	0.04		259	259	0.01	< 0.005	0.01	260	

2.3. Construction Emissions by Year, Mitigated

Year	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Daily - Summer (Max)																			
2025	0.52	0.48	5.24	25.3	0.04	0.08	3.23	3.31	0.08	1.45	1.53		4704	4704	0.19	0.17	3.76	4750	
2026	0.37	0.34	4.56	13.4	0.02	0.07	0.03	0.1	0.07	0.01	0.08		2248	2248	0.09	0.02	0.14	2257	
Daily - Winter (Max)																			
2025	0.37	0.35	4.57	13.4	0.02	0.07	0.03	0.1	0.07	0.01	0.08		2248	2248	0.09	0.02	< 0.005	2257	
2026	0.53	3.18	6.87	21	0.03	0.09	0.17	0.26	0.09	0.04	0.13		3386	3386	0.14	0.04	0.02	3400	
Average Daily																			
2025	0.13	0.12	1.4	5.02	0.01	0.02	0.22	0.24	0.02	0.08	0.1		891	891	0.04	0.02	0.13	897	
2026	0.25	0.35	3.17	9.36	0.02	0.05	0.03	0.07	0.05	0.01	0.05		1564	1564	0.06	0.02	0.05	1570	
Annual																			
2025	0.02	0.02	0.26	0.92	< 0.005	< 0.005	0.04	0.04	< 0.005	0.01	0.02		147	147	0.01	< 0.005	0.02	149	
2026	0.05	0.06	0.58	1.71	< 0.005	0.01	< 0.005	0.01	0.01	< 0.005	0.01		259	259	0.01	< 0.005	0.01	260	

3. Construction Emissions Details

3.2. Demolition (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0.13	0.13	1.24	9.21	0.01	0.02		0.02	0.02		0.02		1318	1318	0.05	0.01			1322
Demolition							0	0	0	0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment	0.01	0.01	0.1	0.76	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		108	108	< 0.005	< 0.005			109
Demolition							0	0	0	0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	< 0.005	< 0.005	0.02	0.14	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		17.9	17.9	< 0.005	< 0.005			18
Demolition							0	0	0	0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0.07	0.06	0.06	1.04	0	0	0.2	0.2	0	0.05	0.05		207	207	0.01	0.01	0.76	210	
Vendor	0.02	0.01	0.29	0.14	< 0.005	< 0.005	0.07	0.07	< 0.005	0.02	0.02		254	254	0.01	0.04	0.69	265	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	
Daily, Winter (Max)																			
Average Daily																			
Worker	0.01	0.01	0.01	0.08	0	0	0.02	0.02	0	< 0.005	< 0.005		16.4	16.4	< 0.005	< 0.005	0.03	16.6	
Vendor	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005									

3.4. Demolition (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0.01	0.01	< 0.005	< 0.005	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment Demolition	0	0	0	0	0	0	< 0.005	< 0.005	< 0.005	< 0.005	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment Demolition	0	0	0	0	0	0	< 0.005	< 0.005	< 0.005	< 0.005	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0.01 < 0.005		0.09	0.03 < 0.005	< 0.005	0.02	0.02 < 0.005		0.01	0.01			69.3	69.3 < 0.005		0.01	0.16	72.8	
Daily, Winter (Max)																			
Average Daily																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		5.69	5.69 < 0.005	< 0.005		0.01	5.97	
Annual																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		0.94	0.94 < 0.005	< 0.005	< 0.005		0.99	

3.6. Demolition (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

3.8. Demolition (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0.5	0.5	0	0.08	0.08	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0.04	0.04	0	0.01	0.01	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment Demolition	0	0	0	0	0	0	0.01	0.01	< 0.005	< 0.005	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0.02 < 0.005		0.34	0.13 < 0.005	< 0.005	0.07	0.08 < 0.005		0.02	0.02			277	277	0.02	0.04	0.64	291	
Daily, Winter (Max)																			
Average Daily																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	0.03	0.01 < 0.005	< 0.005	0.01	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005		22.8	22.8 < 0.005	< 0.005		0.02	23.9	
Annual																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		3.77	3.77 < 0.005	< 0.005	< 0.005		3.96	

3.10. Site Preparation (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment Demolition	0.13	0.13	1.23	9.1	0.01	0.02	0	0	0.02	0.02	0.02	0	1303	1303	0.05	0.01		1308	
Dust From Material Movement							0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment Demolition	< 0.005	< 0.005	0.02	0.12 < 0.005	< 0.005		< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		17.9	17.9 < 0.005	< 0.005			17.9	
Dust From Material Movement							0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment Demolition	< 0.005	< 0.005	< 0.005	0.02 < 0.005	< 0.005		< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		2.96	2.96 < 0.005	< 0.005			2.97	
Dust From Material Movement							0	0	0	0	0	0	0	0	0	0	0	0	0
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			

Daily, Summer (Max)																		
Worker	0.06	0.05	0.05	0.87	0	0	0.16	0.16	0	0.04	0.04	173	173	0.01	0.01	0.63	175	
Vendor	0.02	0.01	0.36	0.18 < 0.005	< 0.005		0.09	0.09 < 0.005	0	0.02	0.03	317	317	0.01	0.04	0.87	332	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Daily, Winter (Max)																		
Average Daily																		
Worker	< 0.005	< 0.005	< 0.005	0.01	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		2.28	2.28 < 0.005	< 0.005	< 0.005		2.31	
Vendor	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	4.35	4.35 < 0.005	< 0.005	< 0.005	0.01	4.54	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Annual																		
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		0.38	0.38 < 0.005	< 0.005	< 0.005		0.38	
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	0.72	0.72 < 0.005	< 0.005	< 0.005		0.75	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3.12. Grading (2025) - Mitigated																		
Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e
Onsite																		
Daily, Summer (Max)																		
Off-Road Equipment	0.23	0.23	1.2	14.2	0.02	0.05		0.05	0.05		0.05		2455	2455	0.1	0.02		2463
Dust From Material Movement							2.76	2.76			1.34	1.34						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																		
Average Daily																		
Off-Road Equipment	0.01	0.01	0.03	0.35 < 0.005	< 0.005			< 0.005	< 0.005		< 0.005		60.5	60.5 < 0.005	< 0.005			60.7
Dust From Material Movement							0.07	0.07			0.03	0.03						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																		
Off-Road Equipment	< 0.005	< 0.005	0.01	0.06 < 0.005	< 0.005			< 0.005	< 0.005		< 0.005		10	10 < 0.005	< 0.005			10.1
Dust From Material Movement							0.01	0.01			0.01	0.01						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																		
Daily, Summer (Max)																		
Worker	0.05	0.04	0.04	0.7	0	0	0.13	0.13	0	0.03	0.03	138	138	0.01 < 0.005		0.51	140	
Vendor	0.02	0.01	0.36	0.18 < 0.005	< 0.005		0.09	0.09 < 0.005		0.02	0.03	317	317	0.01	0.04	0.87	332	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Daily, Winter (Max)																		
Average Daily																		
Worker	< 0.005	< 0.005	< 0.005	0.02	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		3.28	3.28 < 0.005	< 0.005		0.01	3.32	
Vendor	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	7.82	7.82 < 0.005	< 0.005	< 0.005	0.01	8.17	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Annual																		
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		0.54	0.54 < 0.005	< 0.005	< 0.005		0.55	
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	1.3	1.3 < 0.005	< 0.005	< 0.005		1.35	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3.14. Grading (2025) - Mitigated																		
Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e
Onsite																		
Daily, Summer (Max)																		
Off-Road Equipment	0.23	0.23	1.2	14.2	0.02	0.05		0.05	0.05		0.05		2455	2455	0.1	0.02		2463
Dust From Material Movement							2.76	2.76			1.34	1.34						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																		
Average Daily																		
Off-Road Equipment	0.01	0.01	0.03	0.31 < 0.005	< 0.005			< 0.005	< 0.005		< 0.005		53.8	53.8 < 0.005	< 0.005			54
Dust From Material Movement							0.06	0.06			0.03	0.03						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																		
Off-Road Equipment	< 0.005	< 0.005	< 0.005	0.06 < 0.005	< 0.005			< 0.005	< 0.005		< 0.005		8.91	8.91 < 0.005	< 0.005			8.94
Dust From Material Movement							0.01	0.01			0.01	0.01						
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																		
Daily, Summer (Max)																		
Worker	0.05	0.04	0.04	0.7	0	0	0.13	0.13	0	0.03	0.03	138	138	0.01 < 0.005		0.51	140	
Vendor	0.02	0.01	0.36	0.18 < 0.005	< 0.005		0.09	0.09 < 0.005		0.02	0.03	317	317	0.01	0.04	0.87	332	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Daily, Winter (Max)																		
Average Daily																		
Worker	< 0.005	< 0.005	< 0.005	0.01	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		2.92	2.92 < 0.005	< 0.005	< 0.005		2.95	
Vendor	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	6.95	6.95 < 0.005	< 0.005	< 0.005	0.01	7.26	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Annual																		
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0 < 0.005	< 0.005		0 < 0.005	< 0.005		0.48	0.48 < 0.005	< 0.005	< 0.005		0.49	
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	1.15	1.15 < 0.005	< 0.005	< 0.005		1.2	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
3.16. Building Construction (2025) - Mitigated																		
Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e
Onsite																		
Daily, Summer (Max)																		
Off-Road Equipment	0.36	0.34	4.53	13.3	0.02	0.07		0.07	0.07		0.07		2201	2201	0.09	0.02		2209
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																		
Off-Road Equipment	0.36	0.34	4.53	13.3	0.02	0.07		0.07	0.07		0.07		2201	2201	0.09	0.02		2209
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																		
Off-Road Equipment	0.09	0.08	1.12	3.28	0.01	0.02		0.02	0.02		0.02		543	543	0.02 < 0.005			545
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																		
Off-Road Equipment	0.02	0.02	0.2	0.6 < 0.005	< 0.005			< 0.005	< 0.005		< 0.005		89.9	89.9 < 0.005	< 0.005			90.2
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																		
Daily, Summer (Max)																		
Worker	0.01	0.01	0.01	0.13	0	0	0.02	0.02	0	0.01	0.01	25.4	25.4 < 0.005	< 0.005		0.09	25.8	
Vendor	< 0.005	< 0.005	0.03	0.01 < 0.005	< 0.005		0.01	0.01 < 0.005	< 0.005	< 0.005	< 0.005	22.7	22.7 < 0.005	< 0.005	< 0.005	0.06	23.8	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Daily, Winter (Max)																		
Worker	0.01	0.01	0.01	0.11	0	0	0.02	0.02	0	0.01	0.01	24.1	24.1 < 0.005	< 0.005	< 0.005		24.4	
Vendor	< 0.005	< 0.005	0.03	0.01 < 0.005	< 0.005		0.01	0.01 < 0.005	< 0.005	< 0.005	< 0.005	22.7	22.7 < 0.005	< 0.005	< 0.005	< 0.005	23.7	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Average Daily																		
Worker	< 0.005	< 0.005	< 0.005	0.03	0	0	0.01	0.01	0	0 < 0.005	< 0.005	6.02	6.02 < 0.005	< 0.005	< 0.005	0.01	6.1	
Vendor	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	5.6	5.6 < 0.005	< 0.005	< 0.005	0.01	5.85	
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Annual																		
Worker	< 0.005	< 0.005	< 0.005															

Onsite																				
Daily, Summer (Max)																				
Off-Road Equipment	0.36	0.34	4.53	13.3	0.02	0.07		0.07	0.07			0.07	2201	2201	0.09	0.02			2208	
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																				
Off-Road Equipment	0.36	0.34	4.53	13.3	0.02	0.07		0.07	0.07			0.07	2201	2201	0.09	0.02			2208	
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																				
Off-Road Equipment	0.24	0.23	3.07	9	0.02	0.05		0.05	0.05			0.05	1490	1490	0.06	0.01			1495	
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																				
Off-Road Equipment	0.04	0.04	0.56	1.64	< 0.005	0.01		0.01	0.01			0.01	247	247	0.01	< 0.005			248	
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																				
Daily, Summer (Max)																				
Worker	0.01	0.01	0.01	0.12	0	0	0.02	0.02	0	0.01	0.01		24.9	24.9	< 0.005	< 0.005		0.08	25.2	
Vendor	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005		22.3	22.3	< 0.005	< 0.005		0.06	23.4	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0	
Daily, Winter (Max)																				
Worker	0.01	0.01	0.01	0.1	0	0	0.02	0.02	0	0.01	0.01		23.6	23.6	< 0.005	< 0.005	< 0.005		23.9	
Vendor	< 0.005	< 0.005	0.03	0.01	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005		22.3	22.3	< 0.005	< 0.005	< 0.005		23.3	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0	
Average Daily																				
Worker	0.01	< 0.005	0.01	0.07	0	0	0.02	0.02	0	< 0.005	< 0.005		16.2	16.2	< 0.005	< 0.005		0.02	16.4	
Vendor	< 0.005	< 0.005	0.02	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		15.1	15.1	< 0.005	< 0.005		0.02	15.8	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0	
Annual																				
Worker	< 0.005	< 0.005	< 0.005	0.01	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		2.68	2.68	< 0.005	< 0.005	< 0.005		2.72	
Vendor	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		2.5	2.5	< 0.005	< 0.005	< 0.005		2.62	
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0	

3.20. Paving (2026) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Off-Road Equipment	0.08	0.08	0.95	5.05	0.01	0.01		0.01	0.01		0.01		722	722	0.03	0.01			725
Paving																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Average Daily																			
Off-Road Equipment	< 0.005	< 0.005	0.04	0.21	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		29.7	29.7	< 0.005	< 0.005			29.8
Paving																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	< 0.005	< 0.005	0.01	0.04	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		4.91	4.91	< 0.005	< 0.005			4.93
Paving																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Worker	0.03	0.03	0.03	0.41	0	0	0.1	0.1	0	0.02	0.02		96.3	96.3	< 0.005	< 0.005		0.01	97.5
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Average Daily																			
Worker	< 0.005	< 0.005	< 0.005	0.02	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		4.02	4.02	< 0.005	< 0.005		0.01	4.07
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.67	0.67	< 0.005	< 0.005	< 0.005		0.67
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0

3.22. Architectural Coating (2026) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Off-Road Equipment	0.02	0.02	0.65	0.96	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		134	134	0.01	< 0.005			134
Architectural Coatings																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Average Daily																			
Off-Road Equipment	< 0.005	< 0.005	0.03	0.04	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		5.49	5.49	< 0.005	< 0.005			5.51
Architectural Coatings																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	< 0.005	< 0.005	< 0.005	0.01	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		0.91	0.91	< 0.005	< 0.005			0.91
Architectural Coatings																			
Onsite truck	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Worker	< 0.005	< 0.005	< 0.005	0.06	0	0	0.01	0.01	0	< 0.005	< 0.005		12.8	12.8	< 0.005	< 0.005	< 0.005		13
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Average Daily																			
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.54	0.54	< 0.005	< 0.005	< 0.005		0.54
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Annual																			
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.09	0.09	< 0.005	< 0.005	< 0.005		0.09
Vendor	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0		0	0	0	0	0	0	0

3.24. Trenching (2025) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0.02	0.02	0.66	0.99	< 0.005	< 0.005		< 0.005	< 0.005		< 0.005		142	142	0.01	< 0.005			

3.26. Trenching (2026) - Mitigated																			
Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Off-Road Equipment		0.02	0.02	0.66	0.99	< 0.005	< 0.005		< 0.005	< 0.005			142	142	0.01	< 0.005			142
Onsite truck		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																			
Off-Road Equipment	< 0.005	< 0.005	0.01	0.01	< 0.005	< 0.005			< 0.005	< 0.005			1.94	1.94	< 0.005	< 0.005			1.95
Onsite truck		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005			< 0.005	< 0.005			0.32	0.32	< 0.005	< 0.005			0.32
Onsite truck		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Daily, Winter (Max)																			
Worker		0.01	0.01	0.01	0.14	0	0	0.03	0.03	0	0.01	0.01		32.1	32.1	< 0.005	< 0.005		32.5
Vendor		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Average Daily																			
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.45	0.45	< 0.005	< 0.005			0.45
Vendor		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Worker	< 0.005	< 0.005	< 0.005	< 0.005	0	0	< 0.005	< 0.005	0	< 0.005	< 0.005		0.07	0.07	< 0.005	< 0.005			0.07
Vendor		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

5. Activity Data

5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Phase 2 Building Demolition	Demolition	6/15/2025	7/25/2025		5	30
Phase 2 Building Demolition Debris Haul	Demolition	6/15/2025	7/25/2025		5	30
Phase 2 Asphalt Demolition	Demolition	6/15/2025	7/25/2025		5	30
Phase 2 Asphalt Demolition Debris Haul	Demolition	6/15/2025	7/25/2025		5	30
Phase 2 Site Preparation	Site Preparation	7/25/2025	7/31/2025		5	5
Phase 2 Rough Grading	Grading	7/31/2025	8/12/2025		5	9
Phase 2 Fine Grading	Grading	8/13/2025	8/22/2025		5	8
Phase 2 Building Construction	Building Construction	8/28/2025	12/12/2026		5	337
Phase 2 Paving	Paving	11/21/2026	12/12/2026		5	15
Phase 2 Architectural Coating	Architectural Coating	11/21/2026	12/12/2026		5	15
Phase 2 Utility Trenching	Trenching	8/22/2025	8/28/2025		5	5
Phase 2 Finishing/Landscaping	Trenching	12/7/2026	12/12/2026		5	5

5.2. Off-Road Equipment

5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 2 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Average	3	8	84	0.37
Phase 2 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 2 Site Preparation	Scrapers	Diesel	Average	0	8	423	0.48
Phase 2 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Average	4	8	84	0.37
Phase 2 Rough Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 2 Rough Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 2 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 2 Building Construction	Cranes	Diesel	Average	1	8	367	0.29
Phase 2 Building Construction	Forklifts	Diesel	Average	2	7	82	0.2
Phase 2 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 2 Building Construction	Tractors/Loaders/Backhoes	Diesel	Average	1	6	84	0.37
Phase 2 Building Construction	Welders	Diesel	Average	3	8	46	0.45
Phase 2 Paving	Cement and Mortar Mixers	Diesel	Average	0	8	10	0.56
Phase 2 Paving	Pavers	Diesel	Average	0	8	81	0.42
Phase 2 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36
Phase 2 Paving	Rollers	Diesel	Average	1	8	36	0.38
Phase 2 Paving	Tractors/Loaders/Backhoes	Diesel	Average	2	8	84	0.37
Phase 2 Architectural Coating	Air Compressors	Diesel	Average	1	6	37	0.48
Phase 2 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Fine Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 2 Fine Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 2 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 2 Building Demolition	Forklifts	Diesel	Average	2	8	82	0.2
Phase 2 Site Preparation	Rollers	Diesel	Average	1	8	36	0.38
Phase 2 Utility Trenching	Excavators	Diesel	Average	1	8	36	0.38
Phase 2 Finishing/Landscaping	Excavators	Diesel	Average	1	8	36	0.38
Phase 2 Building Demolition	Excavators	Diesel	Average	1	8	36	0.38

5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 2 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	3	8	84	0.37
Phase 2 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 2 Site Preparation	Scrapers	Diesel	Average	0	8	423	0.48
Phase 2 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	4	8	84	0.37
Phase 2 Rough Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 2 Rough Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 2 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37
Phase 2 Building Construction	Cranes	Diesel	Tier 4 Final	1	8	367	0.29
Phase 2 Building Construction	Forklifts	Diesel	Tier 4 Final	2	7	82	0.2
Phase 2 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 2 Building Construction	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	1	6	84	0.37
Phase 2 Building Construction	Welders	Diesel	Tier 4 Final	3	8	46	0.45
Phase 2 Paving	Cement and Mortar Mixers	Diesel	Average	0	8	10	0.56
Phase 2 Paving	Pavers	Diesel	Average	0	8	81	0.42
Phase 2 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36
Phase 2 Paving	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 2 Paving	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	8	84	0.37
Phase 2 Architectural Coating	Air Compressors	Diesel	Tier 4 Final	1	6	37	0.48
Phase 2 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 2 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 2 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 2 Fine Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 2 Fine Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 2 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37

Phase 2 Building Demolition	Forklifts	Diesel	Tier 4 Final	2	8	82	0.2
Phase 2 Site Preparation	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 2 Utility Trenching	Excavators	Diesel	Tier 4 Final	1	8	36	0.38
Phase 2 Finishing/Landscaping	Excavators	Diesel	Tier 4 Final	1	8	36	0.38
Phase 2 Building Demolition	Excavators	Diesel	Tier 4 Final	1	8	36	0.38

5.3. Construction Vehicles

5.3.1. Unmitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 2 Building Demolition	Worker	15	18.5	LDA,LDT1,LDT2
Phase 2 Building Demolition	Vendor	8	10.2	HHDT,MHDT
Phase 2 Building Demolition	Hauling	0	20	HHDT
Phase 2 Building Demolition	Onsite truck	0		HHDT
Phase 2 Site Preparation	Worker	12.5	18.5	LDA,LDT1,LDT2
Phase 2 Site Preparation	Vendor	10	10.2	HHDT,MHDT
Phase 2 Site Preparation	Hauling	0	20	HHDT
Phase 2 Site Preparation	Onsite truck	0		HHDT
Phase 2 Rough Grading	Worker	10	18.5	LDA,LDT1,LDT2
Phase 2 Rough Grading	Vendor	10	10.2	HHDT,MHDT
Phase 2 Rough Grading	Hauling	0	20	HHDT
Phase 2 Rough Grading	Onsite truck	0		HHDT
Phase 2 Building Construction	Worker	1.84	18.5	LDA,LDT1,LDT2
Phase 2 Building Construction	Vendor	0.72	10.2	HHDT,MHDT
Phase 2 Building Construction	Hauling	0	20	HHDT
Phase 2 Building Construction	Onsite truck	0		HHDT
Phase 2 Paving	Worker	7.5	18.5	LDA,LDT1,LDT2
Phase 2 Paving	Vendor	0	10.2	HHDT,MHDT
Phase 2 Paving	Hauling	0	20	HHDT
Phase 2 Paving	Onsite truck	0		HHDT
Phase 2 Architectural Coating	Worker	1	18.5	LDA,LDT1,LDT2
Phase 2 Architectural Coating	Vendor	0	10.2	HHDT,MHDT
Phase 2 Architectural Coating	Hauling	0	20	HHDT
Phase 2 Architectural Coating	Onsite truck	0		HHDT
Phase 2 Building Demolition Debris Haul				
Phase 2 Building Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Building Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 2 Building Demolition Debris Haul	Hauling	1	20	HHDT
Phase 2 Building Demolition Debris Haul	Onsite truck	0		HHDT
Phase 2 Asphalt Demolition	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Asphalt Demolition	Vendor	0	10.2	HHDT,MHDT
Phase 2 Asphalt Demolition	Hauling	0	20	HHDT
Phase 2 Asphalt Demolition	Onsite truck	0		HHDT
Phase 2 Asphalt Demolition Debris Haul				
Phase 2 Asphalt Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Asphalt Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 2 Asphalt Demolition Debris Haul	Hauling	4	20	HHDT
Phase 2 Asphalt Demolition Debris Haul	Onsite truck	0		HHDT
Phase 2 Fine Grading	Worker	10	18.5	LDA,LDT1,LDT2
Phase 2 Fine Grading	Vendor	10	10.2	HHDT,MHDT
Phase 2 Fine Grading	Hauling	0	20	HHDT
Phase 2 Fine Grading	Onsite truck	0		HHDT
Phase 2 Utility Trenching	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 2 Utility Trenching	Vendor	0	10.2	HHDT,MHDT
Phase 2 Utility Trenching	Hauling	0	20	HHDT
Phase 2 Utility Trenching	Onsite truck	0		HHDT
Phase 2 Finishing/Landscaping	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 2 Finishing/Landscaping	Vendor	0	10.2	HHDT,MHDT
Phase 2 Finishing/Landscaping	Hauling	0	20	HHDT
Phase 2 Finishing/Landscaping	Onsite truck	0		HHDT

5.3.2. Mitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 2 Building Demolition	Worker	15	18.5	LDA,LDT1,LDT2
Phase 2 Building Demolition	Vendor	8	10.2	HHDT,MHDT
Phase 2 Building Demolition	Hauling	0	20	HHDT
Phase 2 Building Demolition	Onsite truck	0		HHDT
Phase 2 Site Preparation	Worker	12.5	18.5	LDA,LDT1,LDT2
Phase 2 Site Preparation	Vendor	10	10.2	HHDT,MHDT
Phase 2 Site Preparation	Hauling	0	20	HHDT
Phase 2 Site Preparation	Onsite truck	0		HHDT
Phase 2 Rough Grading	Worker	10	18.5	LDA,LDT1,LDT2
Phase 2 Rough Grading	Vendor	10	10.2	HHDT,MHDT
Phase 2 Rough Grading	Hauling	0	20	HHDT
Phase 2 Rough Grading	Onsite truck	0		HHDT
Phase 2 Building Construction	Worker	1.84	18.5	LDA,LDT1,LDT2
Phase 2 Building Construction	Vendor	0.72	10.2	HHDT,MHDT
Phase 2 Building Construction	Hauling	0	20	HHDT
Phase 2 Building Construction	Onsite truck	0		HHDT
Phase 2 Paving	Worker	7.5	18.5	LDA,LDT1,LDT2

Phase 2 Paving	Vendor	0	10.2	HHDT,MHDT
Phase 2 Paving	Hauling	0	20	HHDT
Phase 2 Paving	Onsite truck	0		HHDT
Phase 2 Architectural Coating				
Phase 2 Architectural Coating	Worker	1	18.5	LDA,LDT1,LDT2
Phase 2 Architectural Coating	Vendor	0	10.2	HHDT,MHDT
Phase 2 Architectural Coating	Hauling	0	20	HHDT
Phase 2 Architectural Coating	Onsite truck	0		HHDT
Phase 2 Building Demolition Debris Haul				
Phase 2 Building Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Building Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 2 Building Demolition Debris Haul	Hauling	1	20	HHDT
Phase 2 Building Demolition Debris Haul	Onsite truck	0		HHDT
Phase 2 Asphalt Demolition				
Phase 2 Asphalt Demolition	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Asphalt Demolition	Vendor	0	10.2	HHDT,MHDT
Phase 2 Asphalt Demolition	Hauling	0	20	HHDT
Phase 2 Asphalt Demolition	Onsite truck	0		HHDT
Phase 2 Asphalt Demolition Debris Haul				
Phase 2 Asphalt Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 2 Asphalt Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 2 Asphalt Demolition Debris Haul	Hauling	4	20	HHDT
Phase 2 Asphalt Demolition Debris Haul	Onsite truck	0		HHDT
Phase 2 Fine Grading				
Phase 2 Fine Grading	Worker	10	18.5	LDA,LDT1,LDT2
Phase 2 Fine Grading	Vendor	10	10.2	HHDT,MHDT
Phase 2 Fine Grading	Hauling	0	20	HHDT
Phase 2 Fine Grading	Onsite truck	0		HHDT
Phase 2 Utility Trenching				
Phase 2 Utility Trenching	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 2 Utility Trenching	Vendor	0	10.2	HHDT,MHDT
Phase 2 Utility Trenching	Hauling	0	20	HHDT
Phase 2 Utility Trenching	Onsite truck	0		HHDT
Phase 2 Finishing/Landscaping				
Phase 2 Finishing/Landscaping	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 2 Finishing/Landscaping	Vendor	0	10.2	HHDT,MHDT
Phase 2 Finishing/Landscaping	Hauling	0	20	HHDT
Phase 2 Finishing/Landscaping	Onsite truck	0		HHDT

5.4. Vehicles

5.4.1. Construction Vehicle Control Strategies

Control Strategies Applied	PM10 Reduction	PM2.5 Reduction
Water unpaved roads twice daily	55	55
Limit vehicle speeds on unpaved roads to 25 mph	44	44
Sweep paved roads once per month	9	9

5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Phase 2 Architectural Coating	0	0	10050	3350	1930

5.6. Dust Mitigation

5.6.1. Construction Earthmoving Activities

Phase Name	Material Imported (Cubic Yards)	Material Exported (Cubic Yards)	Acres Graded (acres)	Material Demolished (Ton)	Acres Paved (acres)
Phase 2 Building Demolition	0	0	0	0	0
Phase 2 Building Demolition Debris Haul	0	0	0	18	0
Phase 2 Asphalt Demolition	0	0	0	0	0
Phase 2 Asphalt Demolition Debris Haul	0	0	0	1088	0
Phase 2 Site Preparation	0	0	0	0	0
Phase 2 Rough Grading	0	0	9	0	0
Phase 2 Fine Grading	0	0	8	0	0
Phase 2 Paving	0	0	0	0	2.73

5.6.2. Construction Earthmoving Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Exposed Area	2	61	61
Water Demolished Area	2	36	36

5.7. Construction Paving

Land Use	Area Paved (acres)	% Asphalt
Elementary School	0	0
Other Asphalt Surfaces	0.06	100
Other Non-Asphalt Surfaces	0.68	0
Other Non-Asphalt Surfaces	1.99	0

5.8. Construction Electricity Consumption and Emissions

Year	kWh per Year	CO2	CH4	N2O
2025		0	450	0.03 < 0.005
2026		0	450	0.03 < 0.005

8. User Changes to Default Data

Screen	Justification
Characteristics: Project Details	m

Characteristics: Utility Information 2021 SCE Sustainability Report

Construction: Construction Phases based on CalEEMod default construction schedule, normalized to fit duration provided by District

Construction: Off-Road Equipment based on data provided by District. Uses default construction equipment or grading activities and building construction.

Construction: Trips and VMT see assumptions file for demolition haul and water truck calculations

Construction: Architectural

Coatings SCAQMD Rule 1113. Assumes playground and playfield area (asphalt area and landscaping) will be striped.

Construction: Electricity 2021 SCE Sustainability Report

Worker	0.01	0.01	0.01	0.08	0	0	0.02	0.02	0 < 0.005	< 0.005	20.1	20.1 < 0.005	< 0.005	0.03	20.4
Vendor	< 0.005	< 0.005	0.03	0.01 < 0.005	< 0.005	0	0.01	0.01 < 0.005	< 0.005	< 0.005	25.5	25.5 < 0.005	< 0.005	0.03	26.7
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual															
Worker	< 0.005	< 0.005	< 0.005	0.01	0	0 < 0.005	< 0.005	< 0.005	0 < 0.005	< 0.005	3.33	3.33 < 0.005	< 0.005	< 0.005	3.37
Vendor	< 0.005	< 0.005	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	4.23	4.23 < 0.005	< 0.005	< 0.005	4.41
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

3.4. Demolition (2028) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0.59	0.59		0.09	0.09								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0.06	0.06		0.01	0.01								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0.01	0.01		< 0.005	< 0.005								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0.01 < 0.005		0.15	0.06 < 0.005	< 0.005		0.04	0.04 < 0.005		0.01	0.01		130	130	0.01	0.02	0.26		137
Daily, Winter (Max)																			
Average Daily																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	0.02	0.01 < 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		13.9	13.9 < 0.005	< 0.005		0.01		14.6
Annual																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005		2.31	2.31 < 0.005	< 0.005	< 0.005			2.42

3.6. Demolition (2028) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0	0		0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0	0		0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0	0		0	0								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

3.8. Demolition (2028) - Mitigated

Location	TOG	ROG	NOx	CO	SO ₂	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO ₂	NBCO ₂	CO ₂ T	CH ₄	N ₂ O	R	CO ₂ e	
Onsite																			
Daily, Summer (Max)																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0.15	0.15		0.02	0.02								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Daily, Winter (Max)																			
Average Daily																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							0.02	0.02		< 0.005	< 0.005								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Annual																			
Off-Road Equipment	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Demolition							< 0.005	< 0.005		< 0.005	< 0.005								
Onsite truck	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Offsite																			
Daily, Summer (Max)																			
Worker	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Vendor	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Hauling	0.01 < 0.005		0.15	0.06 < 0.005	< 0.005		0.04	0.04 < 0.005		0.01	0.01		130	130	0.01</				

5. Activity Data

5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Phase 3 Building Demolition	Demolition	6/15/2028	8/8/2028		5	39
Phase 3 Building Demolition Debris Haul	Demolition	6/15/2028	8/8/2028		5	39
Phase 3 Asphalt Demolition	Demolition	6/15/2028	8/8/2028		5	39
Phase 3 Asphalt Demolition Debris Haul	Demolition	6/15/2028	8/8/2028		5	39
Phase 3 Site Preparation	Site Preparation	8/8/2028	8/13/2028		5	4
Phase 3 Rough Grading	Grading	8/13/2028	8/23/2028		5	8
Phase 3 Fine Grading	Grading	8/24/2028	9/1/2028		5	7
Phase 3 Building Construction	Building Construction	9/7/2028	3/10/2030		5	392
Phase 3 Paving	Paving	2/10/2030	3/10/2030		5	20
Phase 3 Architectural Coating	Architectural Coating	2/10/2030	3/10/2030		5	20
Phase 3 Utility Trenching	Trenching	9/1/2028	9/7/2028		5	5
Phase 3 Finishing/Landscaping	Trenching	3/4/2030	3/10/2030		5	5

5.2. Off-Road Equipment

5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 3 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Average	3	8	84	0.37
Phase 3 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 3 Site Preparation	Rubber Tired Dozers	Diesel	Average	0	7	367	0.4
Phase 3 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Average	4	8	84	0.37
Phase 3 Rough Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 3 Rough Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 3 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 3 Building Construction	Cranes	Diesel	Average	1	6	367	0.29
Phase 3 Building Construction	Forklifts	Diesel	Average	1	6	82	0.2
Phase 3 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 3 Building Construction	Tractors/Loaders/Backhoes	Diesel	Average	1	6	84	0.37
Phase 3 Building Construction	Welders	Diesel	Average	3	8	46	0.45
Phase 3 Paving	Cement and Mortar Mixers	Diesel	Average	0	6	10	0.56
Phase 3 Paving	Pavers	Diesel	Average	0	6	81	0.42
Phase 3 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36
Phase 3 Paving	Rollers	Diesel	Average	1	8	36	0.38
Phase 3 Paving	Tractors/Loaders/Backhoes	Diesel	Average	2	8	84	0.37
Phase 3 Architectural Coating	Air Compressors	Diesel	Average	1	6	37	0.48
Phase 3 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Fine Grading	Graders	Diesel	Average	1	8	148	0.41
Phase 3 Fine Grading	Rubber Tired Dozers	Diesel	Average	1	8	367	0.4
Phase 3 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Average	2	7	84	0.37
Phase 3 Building Demolition	Forklifts	Diesel	Average	2	8	82	0.2
Phase 3 Building Demolition	Excavators	Diesel	Average	1	8	36	0.38
Phase 3 Site Preparation	Rollers	Diesel	Average	1	8	36	0.38
Phase 3 Utility Trenching	Excavators	Diesel	Average	1	8	36	0.38
Phase 3 Finishing/Landscaping	Excavators	Diesel	Average	1	8	36	0.38

5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Phase 3 Building Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Building Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Building Demolition	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	3	8	84	0.37
Phase 3 Site Preparation	Graders	Diesel	Average	0	8	148	0.41
Phase 3 Site Preparation	Rubber Tired Dozers	Diesel	Average	0	7	367	0.4
Phase 3 Site Preparation	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	4	8	84	0.37
Phase 3 Rough Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 3 Rough Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 3 Rough Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37
Phase 3 Building Construction	Cranes	Diesel	Tier 4 Final	1	6	367	0.29
Phase 3 Building Construction	Forklifts	Diesel	Tier 4 Final	1	6	82	0.2
Phase 3 Building Construction	Generator Sets	Diesel	Average	1	8	14	0.74
Phase 3 Building Construction	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	1	6	84	0.37
Phase 3 Building Construction	Welders	Diesel	Tier 4 Final	3	8	46	0.45
Phase 3 Paving	Cement and Mortar Mixers	Diesel	Average	0	6	10	0.56
Phase 3 Paving	Pavers	Diesel	Average	0	6	81	0.42
Phase 3 Paving	Paving Equipment	Diesel	Average	0	8	89	0.36
Phase 3 Paving	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 3 Paving	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	8	84	0.37
Phase 3 Architectural Coating	Air Compressors	Diesel	Tier 4 Final	1	6	37	0.48
Phase 3 Building Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Building Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Building Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Asphalt Demolition	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Asphalt Demolition	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Asphalt Demolition	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Asphalt Demolition Debris Haul	Concrete/Industrial Saws	Diesel	Average	0	8	33	0.73
Phase 3 Asphalt Demolition Debris Haul	Rubber Tired Dozers	Diesel	Average	0	8	367	0.4
Phase 3 Asphalt Demolition Debris Haul	Tractors/Loaders/Backhoes	Diesel	Average	0	8	84	0.37
Phase 3 Fine Grading	Graders	Diesel	Tier 4 Final	1	8	148	0.41
Phase 3 Fine Grading	Rubber Tired Dozers	Diesel	Tier 4 Final	1	8	367	0.4
Phase 3 Fine Grading	Tractors/Loaders/Backhoes	Diesel	Tier 4 Final	2	7	84	0.37

Phase 3 Building Demolition	Forklifts	Diesel	Tier 4 Final	2	8	82	0.2
Phase 3 Building Demolition	Excavators	Diesel	Tier 4 Final	1	8	36	0.38
Phase 3 Site Preparation	Rollers	Diesel	Tier 4 Final	1	8	36	0.38
Phase 3 Utility Trenching	Excavators	Diesel	Tier 4 Final	1	8	36	0.38
Phase 3 Finishing/Landscaping	Excavators	Diesel	Tier 4 Final	1	8	36	0.38

5.3. Construction Vehicles

5.3.1. Unmitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 3 Building Demolition	Worker	15	18.5	LDA,LD11,LD12
Phase 3 Building Demolition	Vendor	8	10.2	HHDT,MHDT
Phase 3 Building Demolition	Hauling	0	20	HHDT
Phase 3 Building Demolition	Onsite truck	0		HHDT
Phase 3 Site Preparation	Worker	12.5	18.5	LDA,LD11,LD12
Phase 3 Site Preparation	Vendor	10	10.2	HHDT,MHDT
Phase 3 Site Preparation	Hauling	0	20	HHDT
Phase 3 Site Preparation	Onsite truck	0		HHDT
Phase 3 Rough Grading	Worker	10	18.5	LDA,LD11,LD12
Phase 3 Rough Grading	Vendor	10	10.2	HHDT,MHDT
Phase 3 Rough Grading	Hauling	0	20	HHDT
Phase 3 Rough Grading	Onsite truck	0		HHDT
Phase 3 Building Construction	Worker	11.1	18.5	LDA,LD11,LD12
Phase 3 Building Construction	Vendor	4.34	10.2	HHDT,MHDT
Phase 3 Building Construction	Hauling	0	20	HHDT
Phase 3 Building Construction	Onsite truck	0		HHDT
Phase 3 Paving	Worker	7.5	18.5	LDA,LD11,LD12
Phase 3 Paving	Vendor	0	10.2	HHDT,MHDT
Phase 3 Paving	Hauling	0	20	HHDT
Phase 3 Paving	Onsite truck	0		HHDT
Phase 3 Architectural Coating	Worker	2.23	18.5	LDA,LD11,LD12
Phase 3 Architectural Coating	Vendor	0	10.2	HHDT,MHDT
Phase 3 Architectural Coating	Hauling	0	20	HHDT
Phase 3 Architectural Coating	Onsite truck	0		HHDT
Phase 3 Building Demolition Debris Haul				
Phase 3 Building Demolition Debris Haul	Worker	0	18.5	LDA,LD11,LD12
Phase 3 Building Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 3 Building Demolition Debris Haul	Hauling	2	20	HHDT
Phase 3 Building Demolition Debris Haul	Onsite truck	0		HHDT
Phase 3 Asphalt Demolition	Worker	0	18.5	LDA,LD11,LD12
Phase 3 Asphalt Demolition	Vendor	0	10.2	HHDT,MHDT
Phase 3 Asphalt Demolition	Hauling	0	20	HHDT
Phase 3 Asphalt Demolition	Onsite truck	0		HHDT
Phase 3 Asphalt Demolition Debris Haul				
Phase 3 Asphalt Demolition Debris Haul	Worker	0	18.5	LDA,LD11,LD12
Phase 3 Asphalt Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 3 Asphalt Demolition Debris Haul	Hauling	2	20	HHDT
Phase 3 Asphalt Demolition Debris Haul	Onsite truck	0		HHDT
Phase 3 Fine Grading	Worker	10	18.5	LDA,LD11,LD12
Phase 3 Fine Grading	Vendor	10	10.2	HHDT,MHDT
Phase 3 Fine Grading	Hauling	0	20	HHDT
Phase 3 Fine Grading	Onsite truck	0		HHDT
Phase 3 Utility Trenching	Worker	2.5	18.5	LDA,LD11,LD12
Phase 3 Utility Trenching	Vendor	0	10.2	HHDT,MHDT
Phase 3 Utility Trenching	Hauling	0	20	HHDT
Phase 3 Utility Trenching	Onsite truck	0		HHDT
Phase 3 Finishing/Landscaping	Worker	2.5	18.5	LDA,LD11,LD12
Phase 3 Finishing/Landscaping	Vendor	0	10.2	HHDT,MHDT
Phase 3 Finishing/Landscaping	Hauling	0	20	HHDT
Phase 3 Finishing/Landscaping	Onsite truck	0		HHDT

5.3.2. Mitigated

Phase Name	Trip Type	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Phase 3 Building Demolition	Worker	15	18.5	LDA,LD11,LD12
Phase 3 Building Demolition	Vendor	8	10.2	HHDT,MHDT
Phase 3 Building Demolition	Hauling	0	20	HHDT
Phase 3 Building Demolition	Onsite truck	0		HHDT
Phase 3 Site Preparation	Worker	12.5	18.5	LDA,LD11,LD12
Phase 3 Site Preparation	Vendor	10	10.2	HHDT,MHDT
Phase 3 Site Preparation	Hauling	0	20	HHDT
Phase 3 Site Preparation	Onsite truck	0		HHDT
Phase 3 Rough Grading	Worker	10	18.5	LDA,LD11,LD12
Phase 3 Rough Grading	Vendor	10	10.2	HHDT,MHDT
Phase 3 Rough Grading	Hauling	0	20	HHDT
Phase 3 Rough Grading	Onsite truck	0		HHDT
Phase 3 Building Construction	Worker	11.1	18.5	LDA,LD11,LD12
Phase 3 Building Construction	Vendor	4.34	10.2	HHDT,MHDT
Phase 3 Building Construction	Hauling	0	20	HHDT
Phase 3 Building Construction	Onsite truck	0		HHDT
Phase 3 Paving	Worker	7.5	18.5	LDA,LD11,LD12

Phase 3 Paving	Vendor	0	10.2	HHDT,MHDT
Phase 3 Paving	Hauling	0	20	HHDT
Phase 3 Paving	Onsite truck	0		HHDT
Phase 3 Architectural Coating				
Phase 3 Architectural Coating	Worker	2.23	18.5	LDA,LDT1,LDT2
Phase 3 Architectural Coating	Vendor	0	10.2	HHDT,MHDT
Phase 3 Architectural Coating	Hauling	0	20	HHDT
Phase 3 Architectural Coating	Onsite truck	0		HHDT
Phase 3 Building Demolition Debris Haul				
Phase 3 Building Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 3 Building Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 3 Building Demolition Debris Haul	Hauling	2	20	HHDT
Phase 3 Building Demolition Debris Haul	Onsite truck	0		HHDT
Phase 3 Asphalt Demolition				
Phase 3 Asphalt Demolition	Worker	0	18.5	LDA,LDT1,LDT2
Phase 3 Asphalt Demolition	Vendor	0	10.2	HHDT,MHDT
Phase 3 Asphalt Demolition	Hauling	0	20	HHDT
Phase 3 Asphalt Demolition	Onsite truck	0		HHDT
Phase 3 Asphalt Demolition Debris Haul				
Phase 3 Asphalt Demolition Debris Haul	Worker	0	18.5	LDA,LDT1,LDT2
Phase 3 Asphalt Demolition Debris Haul	Vendor	0	10.2	HHDT,MHDT
Phase 3 Asphalt Demolition Debris Haul	Hauling	2	20	HHDT
Phase 3 Asphalt Demolition Debris Haul	Onsite truck	0		HHDT
Phase 3 Fine Grading				
Phase 3 Fine Grading	Worker	10	18.5	LDA,LDT1,LDT2
Phase 3 Fine Grading	Vendor	10	10.2	HHDT,MHDT
Phase 3 Fine Grading	Hauling	0	20	HHDT
Phase 3 Fine Grading	Onsite truck	0		HHDT
Phase 3 Utility Trenching				
Phase 3 Utility Trenching	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 3 Utility Trenching	Vendor	0	10.2	HHDT,MHDT
Phase 3 Utility Trenching	Hauling	0	20	HHDT
Phase 3 Utility Trenching	Onsite truck	0		HHDT
Phase 3 Finishing/Landscaping				
Phase 3 Finishing/Landscaping	Worker	2.5	18.5	LDA,LDT1,LDT2
Phase 3 Finishing/Landscaping	Vendor	0	10.2	HHDT,MHDT
Phase 3 Finishing/Landscaping	Hauling	0	20	HHDT
Phase 3 Finishing/Landscaping	Onsite truck	0		HHDT

5.4. Vehicles

5.4.1. Construction Vehicle Control

Strategies

Control Strategies Applied	PM10 Reduction	PM2.5 Reduction
Water unpaved roads twice daily	55	55
Limit vehicle speeds on unpaved roads to 25 mph	44	44
Sweep paved roads once per month	9	9

5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Phase 3 Architectural Coating	0	0	39750	13250	2183

5.6. Dust Mitigation

5.6.1. Construction Earthmoving

Activities

Phase Name	Material Imported (Cubic Yards)	Material Exported (Cubic Yards)	Acres Graded (acres)	Material Demolished (Ton)	Acres Paved (acres)
Phase 3 Building Demolition	0	0	0	0	0
Phase 3 Building Demolition Debris Haul	0	0	0	0	1647
Phase 3 Asphalt Demolition	0	0	0	0	0
Phase 3 Asphalt Demolition Debris Haul	0	0	0	0	427
Phase 3 Site Preparation	0	0	0	0	0
Phase 3 Rough Grading	0	0	8	0	0
Phase 3 Fine Grading	0	0	7	0	0
Phase 3 Paving	0	0	0	0	1.04

5.6.2. Construction Earthmoving

Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Exposed Area	2	61	61
Water Demolished Area	2	36	36

5.7. Construction Paving

Land Use

Area Paved (acres)	% Asphalt
Elementary School	0
Parking Lot	0.53
Other Asphalt Surfaces	0.06
Other Non-Asphalt Surfaces	0.25
Other Non-Asphalt Surfaces	0.21

5.8. Construction Electricity

Consumption and Emissions

Factors

Year	kWh per Year	CO2	CH4	N2O
2028	0	0	450	0.03 < 0.005
2029	0	0	450	0.03 < 0.005
2030	0	0	450	0.03 < 0.005

8. User Changes to Default Data

Screen	Justification

Characteristics: Project Details

Characteristics: Utility Information SCE 2021 Sustainability Report
Land Use two story building to be constructed

Construction: Construction Phases based on CalEEMod default schedule, normalized to fit duration provided by District

Construction: Off-Road Equipment based on information provided by the District, CalEEMod defaults used for grading and building construction activities.

Construction: Architectural
Coatings South Coast AQMD Rule 1113. Parking Area considers parking lot, asphalt surfaces, and landscaped surfaces
Construction: Electricity 2021 SCE Sustainability Report
Construction: Trips and VMT see assumptions file for debris hauling and water truck trip calculations

LST Worksheets

Construction Localized Significance Thresholds: Building and Asphalt Demolition and Demolition Debris Haul

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.50	25	82	25	82	1.97
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	8	1	0.5
NOx	125	Tractors	0.5	8	2	1
CO	694	Graders	0.5			0
PM10	5.00	Dozers	0.5			0
PM2.5	3.50	Scrapers	1			0
						0
					Acres	1.50
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
		125	124	139	171	254
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		695	1023	1464	2664	8085
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
		5	16	31	61	150
PM2.5	1	3	4	8	18	77
	2	4	5	10	21	82
		4	5	9	20	80
Northwest Coastal LA County						
1.50 Acres						
	25	50	100	200	500	
NOx	125	124	139	171	254	
CO	695	1023	1464	2664	8085	
PM10	5	16	31	61	150	
PM2.5	4	5	9	20	80	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.97	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
25		Tractors	0.5	8	3	1.5
NOx	146	Tractors	0.5	8	1	0.5
CO	819	Graders	0.5			0
PM10	5.94	Dozers	0.5			0
PM2.5	3.97	Scrapers	1			0
					Acres	2.00

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	146	142	155	185	261
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	819	1202	1681	2943	8424
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	6	19	34	64	154
	2	3	4	8	18	77
		4	5	10	21	82
		4	5	10	21	82
Northwest Coastal LA County						
1.97 Acres						
	25	50	100	200	500	
NOx	146	142	155	185	261	
CO	819	1202	1681	2943	8424	
PM10	6	19	34	64	154	
PM2.5	4	5	10	21	82	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation and Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.97	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	8	3
NOx	146	Tractors	0.5	0.0625	8	1
CO	819	Tractors	0.5	0.0625	7	2
PM10	5.94	Graders	0.5	0.0625	8	1
PM2.5	3.97	Dozers	0.5	0.0625	8	1
		Scrapers	1	0.125		0
					Acres	3.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	146	142	155	185	261
	2	562	833	1233	2367	7724
PM10	1	827	1213	1695	2961	8446
	2	819	1202	1681	2943	8424
PM2.5	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5	1	6	19	34	64	154
	2	3	4	8	18	77
Northwest Coastal LA County	2	4	5	10	21	82
	4	4	5	10	21	82
1.97 Acres						
NOx	25	50	100	200	500	
CO	146	142	155	185	261	
PM10	819	1202	1681	2943	8424	
PM2.5	6	19	34	64	154	
	4	5	10	21	82	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.88	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
25		Tractors	0.5	7	2	0.875
NOx	142	Graders	0.5	8	1	0.5
CO	794	Dozers	0.5	8	1	0.5
PM10	5.75	Scrapers	1			0
PM2.5	3.87				Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		794	1166	1637	2887	8356
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5		6	18	33	63	153
	1	3	4	8	18	77
	2	4	5	10	21	82
		4	5	10	21	81
Northwest Coastal LA County						
1.88 Acres						
	25	50	100	200	500	
NOx	142	138	152	182	260	
CO	794	1166	1637	2887	8356	
PM10	6	18	33	63	153	
PM2.5	4	5	10	21	81	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.88	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day		Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	142	Graders	0.5	0.0625	8	1	0.5
CO	794	Dozers	0.5	0.0625	8	1	0.5
PM10	5.75	Scrapers	1	0.125			0
PM2.5	3.87					Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	142	138	152	182	260
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	794	1166	1637	2887	8356
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	6	18	33	63	153
	2	3	4	8	18	77
		4	5	10	21	82
		4	5	10	21	81
Northwest Coastal LA County						
	1.88 Acres					
	25	50	100	200	500	
NOx	142	138	152	182	260	
CO	794	1166	1637	2887	8356	
PM10	6	18	33	63	153	
PM2.5	4	5	10	21	81	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading and Utilities Trenching

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	1.88	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres	
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	142	Graders	0.5	0.0625	8	1	0.5
CO	794	Dozers	0.5	0.0625	8	1	0.5
PM10	5.75	Scrapers	1	0.125			0
PM2.5	3.87				Acres		1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	142	138	152	182	260
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10		794	1166	1637	2887	8356
	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5		6	18	33	63	153
	1	3	4	8	18	77
	2	4	5	10	21	82
		4	5	10	21	81
Northwest Coastal LA County						
	1.88 Acres					
	25	50	100	200	500	
NOx	142	138	152	182	260	
CO	794	1166	1637	2887	8356	
PM10	6	18	33	63	153	
PM2.5	4	5	10	21	81	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	0.00	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625		0
NOx	103	Graders	0.5	0.0625		0
CO	562	Dozers	0.5	0.0625		0
PM10	4.00	Scrapers	1	0.125		0
PM2.5	3.00				Acres	0.00

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
	0.00 Acres	25	50	100	200	500
NOx	103	104	121	156	245	
CO	562	833	1233	2367	7724	
PM10	4	12	27	57	146	
PM2.5	3	4	8	18	77	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching and Building Construction

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	0.38	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77

Northwest Coastal LA County

	0.38 Acres	25	50	100	200	500
NOx	103	104	121	156	245	245
CO	562	833	1233	2367	7724	7724
PM10	4	12	27	57	146	146
PM2.5	3	4	8	18	77	77

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	0.38	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
	0.38 Acres					
NOx	103	104	121	156	245	
	562	833	1233	2367	7724	
	4	12	27	57	146	
PM10	3	4	8	18	77	
	3	4	8	18	77	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, and Architectural Coating

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.38	25	82	25	82	1.97
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	6	1
NOx	120	Tractors	0.5	0.0625	8	2
CO	661	Graders	0.5	0.0625		0
PM10	4.75	Dozers	0.5	0.0625		0
PM2.5	3.37	Scrapers	1	0.125		0
					Acres	1.38
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	120	119	134	167	251
	2	562	833	1233	2367	7724
PM10	1	827	1213	1695	2961	8446
	2	661	976	1406	2590	7995
PM2.5	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5	1	5	15	30	60	149
	2	3	4	8	18	77
Northwest Coastal LA County	1	4	5	10	21	82
	2	3	4	9	19	79
Northwest Coastal LA County	1.38 Acres	25	50	100	200	500
NOx	120	119	134	167	251	
CO	661	976	1406	2590	7995	
PM10	5	15	30	60	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, Architectural Coating, and Finishing and Landscaping

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.38	25	82	25	82	1.97

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
25		Tractors	0.5	6	1	0.375
NOx	120	Tractors	0.5	8	2	1
CO	661	Graders	0.5			0
PM10	4.75	Dozers	0.5			0
PM2.5	3.37	Scrapers	1			0
					Acres	1.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	120	119	134	167	251
	2	562	833	1233	2367	7724
PM10	1	827	1213	1695	2961	8446
	2	661	976	1406	2590	7995
PM2.5	1	4	12	27	57	146
	2	6	19	34	64	154
Northwest Coastal LA County	1	5	15	30	60	149
	2	3	4	8	18	77
1.38 Acres	1	4	5	10	21	82
	2	3	4	9	19	79
NOx	120	119	134	167	251	
	661	976	1406	2590	7995	
PM10	5	15	30	60	149	
	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building and Asphalt Demolition and Demolition Debris Haul

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.50	25	82	25	82	2.82
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	8	1	0.5
NOx	125	Tractors	0.5	8	2	1
CO	694	Graders	0.5			0
PM10	5.00	Dozers	0.5			0
PM2.5	3.50	Scrapers	1			0
						0
					Acres	1.50
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
		125	124	139	171	254
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		695	1023	1464	2664	8085
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
		5	16	31	61	150
PM2.5	1	3	4	8	18	77
	2	4	5	10	21	82
		4	5	9	20	80
Northwest Coastal LA County						
1.50 Acres						
	25	50	100	200	500	
NOx	125	124	139	171	254	
CO	695	1023	1464	2664	8085	
PM10	5	16	31	61	150	
PM2.5	4	5	9	20	80	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	2.00	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	8	3
NOx	147	Tractors	0.5	0.0625	8	1
CO	827	Graders	0.5	0.0625		0
PM10	6.00	Dozers	0.5	0.0625		0
PM2.5	4.00	Scrapers	1	0.125		0
					Acres	2.00

	Acres	25	50	100	200	500
NOx	2	147	143	156	186	262
	2	147	143	156	186	262
CO	2	827	1213	1695	2961	8446
	2	827	1213	1695	2961	8446
	2	827	1213	1695	2961	8446
PM10	2	6	19	34	64	154
	2	6	19	34	64	154
	2	6	19	34	64	154
PM2.5	2	4	5	10	21	82
	2	4	5	10	21	82
	2	4	5	10	21	82
Northwest Coastal LA County						
2.00 Acres						
NOx	25	50	100	200	500	
NOx	147	143	156	186	262	
CO	827	1213	1695	2961	8446	
PM10	6	19	34	64	154	
PM2.5	4	5	10	21	82	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	2	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation and Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	2.82	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	8	3
NOx	167	Tractors	0.5	0.0625	8	1
CO	1,019	Tractors	0.5	0.0625	7	2
PM10	7.91	Graders	0.5	0.0625	8	1
PM2.5	4.55	Dozers	0.5	0.0625	8	1
		Scrapers	1	0.125		0
					Acres	3.88

	Acres	25	50	100	200	500
NOx	2	147	143	156	186	262
	3	172	166	179	207	279
			167	162	175	203
CO	2	827	1213	1695	2961	8446
	3	1062	1470	2051	3435	9120
			1019	1424	1987	3350
PM10	2	6	19	34	64	154
	3	8	26	41	71	161
			8	25	40	69
PM2.5	2	4	5	10	21	82
	3	5	6	11	24	86
			5	6	11	23
Northwest Coastal LA County						
	2.82 Acres					
	25	50	100	200	500	
NOx	167	162	175	203	276	
CO	1019	1424	1987	3350	8998	
PM10	8	25	40	69	159	
PM2.5	5	6	11	23	86	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	2	2	3
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.88	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres	
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	142	Graders	0.5	0.0625	8	1	0.5
CO	794	Dozers	0.5	0.0625	8	1	0.5
PM10	5.75	Scrapers	1	0.125			0
PM2.5	3.87						0
					Acres		1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		794	1166	1637	2887	8356
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5		6	18	33	63	153
	1	3	4	8	18	77
	2	4	5	10	21	82
		4	5	10	21	81
Northwest Coastal LA County						
1.88 Acres						
	25	50	100	200	500	
NOx	142	138	152	182	260	
CO	794	1166	1637	2887	8356	
PM10	6	18	33	63	153	
PM2.5	4	5	10	21	81	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.88	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day		Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	142	Graders	0.5	0.0625	8	1	0.5
CO	794	Dozers	0.5	0.0625	8	1	0.5
PM10	5.75	Scrapers	1	0.125			0
PM2.5	3.87					Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	142	138	152	182	260
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	794	1166	1637	2887	8356
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	6	18	33	63	153
	2	3	4	8	18	77
		4	5	10	21	82
		4	5	10	21	81
Northwest Coastal LA County						
	1.88 Acres					
	25	50	100	200	500	
NOx	142	138	152	182	260	
CO	794	1166	1637	2887	8356	
PM10	6	18	33	63	153	
PM2.5	4	5	10	21	81	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading and Utilities Trenching

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)	
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)		
2	1.88	25	82	25	82	2.82	
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres	
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	142	Graders	0.5	0.0625	8	1	0.5
CO	794	Dozers	0.5	0.0625	8	1	0.5
PM10	5.75	Scrapers	1	0.125			0
PM2.5	3.87						1.88
					Acres		
	Acres	25	50	100	200	500	
NOx	1	103	104	121	156	245	
	2	147	143	156	186	262	
		142	138	152	182	260	
CO	1	562	833	1233	2367	7724	
	2	827	1213	1695	2961	8446	
		794	1166	1637	2887	8356	
PM10	1	4	12	27	57	146	
	2	6	19	34	64	154	
		6	18	33	63	153	
PM2.5	1	3	4	8	18	77	
	2	4	5	10	21	82	
		4	5	10	21	81	
Northwest Coastal LA County							
1.88 Acres							
	25	50	100	200	500		
NOx	142	138	152	182	260		
CO	794	1166	1637	2887	8356		
PM10	6	18	33	63	153		
PM2.5	4	5	10	21	81		

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	0.00	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625		0
NOx	103	Graders	0.5	0.0625		0
CO	562	Dozers	0.5	0.0625		0
PM10	4.00	Scrapers	1	0.125		0
PM2.5	3.00				Acres	0.00

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
	0.00 Acres	25	50	100	200	500
NOx	103	104	121	156	245	
CO	562	833	1233	2367	7724	
PM10	4	12	27	57	146	
PM2.5	3	4	8	18	77	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching and Building Construction

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	0.38	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77

Northwest Coastal LA County

	0.38 Acres	25	50	100	200	500
NOx	103	104	121	156	245	245
CO	562	833	1233	2367	7724	7724
PM10	4	12	27	57	146	146
PM2.5	3	4	8	18	77	77

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	0.38	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
	0.38 Acres					
NOx	103	104	121	156	245	
	562	833	1233	2367	7724	
	4	12	27	57	146	
PM10	3	4	8	18	77	
	4	12	27	57	146	
PM2.5	3	4	8	18	77	
	4	12	27	57	146	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, and Architectural Coating

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)	
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)		
2	1.38	25	82	25	82	2.82	
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres	
	25	Tractors	0.5	0.0625	6	1	0.375
NOx	120	Tractors	0.5	0.0625	8	2	1
CO	661	Graders	0.5	0.0625			0
PM10	4.75	Dozers	0.5	0.0625			0
PM2.5	3.37	Scrapers	1	0.125			0
						Acres	1.38
	Acres	25	50	100	200	500	
NOx	1	103	104	121	156	245	
	2	147	143	156	186	262	
CO	1	120	119	134	167	251	
	2	562	833	1233	2367	7724	
PM10	1	827	1213	1695	2961	8446	
	2	661	976	1406	2590	7995	
PM2.5	1	4	12	27	57	146	
	2	6	19	34	64	154	
		5	15	30	60	149	
		3	4	8	18	77	
		4	5	10	21	82	
		3	4	9	19	79	
Northwest Coastal LA County	1.38 Acres						
	25	50	100	200	500		
NOx	120	119	134	167	251		
CO	661	976	1406	2590	7995		
PM10	5	15	30	60	149		
PM2.5	3	4	9	19	79		

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, Architectural Coating, and Finishing and Landscaping

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.38	25	82	25	82	2.82

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
25		Tractors	0.5	6	1	0.375
NOx	120	Tractors	0.5	8	2	1
CO	661	Graders	0.5			0
PM10	4.75	Dozers	0.5			0
PM2.5	3.37	Scrapers	1			0
					Acres	1.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	120	119	134	167	251
	2	562	833	1233	2367	7724
PM10	1	827	1213	1695	2961	8446
	2	661	976	1406	2590	7995
PM2.5	1	4	12	27	57	146
	2	6	19	34	64	154
Northwest Coastal LA County	1	5	15	30	60	149
	2	3	4	8	18	77
1.38 Acres	1	4	5	10	21	82
	2	3	4	9	19	79
NOx	120	119	134	167	251	
	661	976	1406	2590	7995	
PM10	5	15	30	60	149	
	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building and Asphalt Demolition and Demolition Debris Haul

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	8	1	0.5
NOx	118	Tractors	0.5	8	2	1
CO	655	Graders	0.5			0
PM10	4.70	Dozers	0.5			0
PM2.5	3.35	Scrapers	1			0
						0
						1.50
	Acres	25	50		200	500
NOx	1	103	104		156	245
	2	147	143		186	262
		118	118		133	251
CO	1	562	833		1233	7724
	2	827	1213		1695	8446
		655	966		1395	7977
PM10	1	4	12		27	146
	2	6	19		34	154
		5	14		29	149
PM2.5	1	3	4		8	77
	2	4	5		10	82
		3	4		9	79
Northwest Coastal LA County						
1.35 Acres						
	25	50	100		200	500
NOx	118	118	133		167	251
CO	655	966	1395		2575	7977
PM10	5	14	29		59	149
PM2.5	3	4	9		19	79

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building and Asphalt Demolition and Demolition Debris Haul, Site Preparation

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	8	1
NOx	118	Tractors	0.5	0.0625	8	2
CO	655	Tractors	0.5	0.0625	8	3
PM10	4.70	Tractors	0.5	0.0625	8	1
PM2.5	3.35	Graders	0.5	0.0625		
		Dozers	0.5	0.0625		
		Scrapers	1	0.125		
						3.50
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
		118	118	133	167	251
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		655	966	1395	2575	7977
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
		5	14	29	59	149
PM2.5	1	3	4	8	18	77
	2	4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County	1.35 Acres					
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	8	3	1.5
NOx	118	Tractors	0.5	8	1	0.5
CO	655	Graders	0.5			0
PM10	4.70	Dozers	0.5			0
PM2.5	3.35	Scrapers	1			0
					Acres	2.00

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	118	118	133	167	251
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	655	966	1395	2575	7977
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	5	14	29	59	149
	2	3	4	8	18	77
		4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County						
	1.35 Acres					
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Site Preparation and Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	8 3	1.5
NOx	118	Tractors	0.5	0.0625	8 1	0.5
CO	655	Tractors	0.5	0.0625	7 2	0.875
PM10	4.70	Graders	0.5	0.0625	8 1	0.5
PM2.5	3.35	Dozers	0.5	0.0625	8 1	0.5
		Scrapers	1	0.125		0
					Acres	3.88
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
		118	118	133	167	251
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		655	966	1395	2575	7977
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
		5	14	29	59	149
PM2.5	1	3	4	8	18	77
	2	4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County	1.35 Acres					
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Rough Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	7	2	0.875
NOx	118	Graders	0.5	8	1	0.5
CO	655	Dozers	0.5	8	1	0.5
PM10	4.70	Scrapers	1			0
PM2.5	3.35				Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		655	966	1395	2575	7977
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5		5	14	29	59	149
	1	3	4	8	18	77
	2	4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County						
1.35 Acres						
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	7	2
NOx	119	Graders	0.5	0.0625	8	1
CO	655	Dozers	0.5	0.0625	8	1
PM10	4.70	Scrapers	1	0.125		
PM2.5	3.35					
					Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	562	833	1233	2367	7724
	2	827	1213	1695	2961	8446
		656	967	1396	2577	7979
PM10	1	4	12	27	57	146
	2	6	19	34	64	154
PM2.5		5	14	29	59	149
	1	3	4	8	18	77
	2	4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County						
1.35 Acres						
	25	50	100	200	500	
NOx	119	118	133	167	251	
CO	656	967	1396	2577	7979	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Fine Grading and Utilities Trenching

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	1.35	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres	
	25	Tractors	0.5	0.0625	7	2	0.875
NOx	118	Graders	0.5	0.0625	8	1	0.5
CO	655	Dozers	0.5	0.0625	8	1	0.5
PM10	4.70	Scrapers	1	0.125			0
PM2.5	3.35					Acres	1.88

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	118	118	133	167	251
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	655	966	1395	2575	7977
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	5	14	29	59	149
	2	3	4	8	18	77
		4	5	10	21	82
		3	4	9	19	79

Northwest Coastal LA County

1.35 Acres

	25	50	100	200	500
NOx	118	118	133	167	251
CO	655	966	1395	2575	7977
PM10	5	14	29	59	149
PM2.5	3	4	9	19	79

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	0.00	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625		0
NOx	103	Graders	0.5	0.0625		0
CO	562	Dozers	0.5	0.0625		0
PM10	4.00	Scrapers	1	0.125		0
PM2.5	3.00				Acres	0.00

Source Receptor Distance (meters)	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
0.00 Acres						
	25	50	100	200	500	
NOx	103	104	121	156	245	
CO	562	833	1233	2367	7724	
PM10	4	12	27	57	146	
PM2.5	3	4	8	18	77	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Utilities Trenching and Building Construction

NOx & CO

PM10 & PM2.5

SRA No.	Acres	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Construction / Project Site Size (Acres)
2	0.38	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77

Northwest Coastal LA County

	0.38 Acres	25	50	100	200	500
NOx	103	104	121	156	245	245
CO	562	833	1233	2367	7724	7724
PM10	4	12	27	57	146	146
PM2.5	3	4	8	18	77	77

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	0.38	25	82	25	82	1.35

Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	103	Graders	0.5			0
CO	562	Dozers	0.5			0
PM10	4.00	Scrapers	1			0
PM2.5	3.00				Acres	0.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	1	103	104	121	156	245
	1	103	104	121	156	245
CO	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
	1	562	833	1233	2367	7724
PM10	1	4	12	27	57	146
	1	4	12	27	57	146
	1	4	12	27	57	146
PM2.5	1	3	4	8	18	77
	1	3	4	8	18	77
	1	3	4	8	18	77
Northwest Coastal LA County						
	0.38 Acres					
NOx	103	104	121	156	245	
	562	833	1233	2367	7724	
	4	12	27	57	146	
PM10	4	12	27	57	146	
	3	4	8	18	77	
PM2.5	3	4	8	18	77	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	1
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, and Architectural Coating

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	0.0625	6	1
NOx	118	Tractors	0.5	0.0625	8	2
CO	655	Graders	0.5	0.0625		0
PM10	4.70	Dozers	0.5	0.0625		0
PM2.5	3.35	Scrapers	1	0.125		0
					Acres	1.38
	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	118	118	133	167	251
	2	562	833	1233	2367	7724
		827	1213	1695	2961	8446
PM10	1	655	966	1395	2575	7977
	2	4	12	27	57	146
		6	19	34	64	154
PM2.5	1	5	14	29	59	149
	2	3	4	8	18	77
		4	5	10	21	82
		3	4	9	19	79
Northwest Coastal LA County	1.35 Acres					
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008

Construction Localized Significance Thresholds: Building Construction, Paving, Architectural Coating, and Finishing and Landscaping

SRA No.	Acres	NOx & CO		PM10 & PM2.5		Construction / Project Site Size (Acres)
		Source Receptor Distance (meters)	Source Receptor Distance (Feet)	Source Receptor Distance (meters)	Source Receptor Distance (Feet)	
2	1.35	25	82	25	82	1.35
Source Receptor Distance (meters)	Northwest Coastal LA County	Equipment	Acres/8-hr Day	Daily hours	Equipment Used	Acres
	25	Tractors	0.5	6	1	0.375
NOx	118	Tractors	0.5	8	2	1
CO	655	Graders	0.5			0
PM10	4.70	Dozers	0.5			0
PM2.5	3.35	Scrapers	1			0
					Acres	1.38

	Acres	25	50	100	200	500
NOx	1	103	104	121	156	245
	2	147	143	156	186	262
CO	1	118	118	133	167	251
	2	562	562	655	833	1233
		827	827	1213	1695	2367
PM10	1	655	655	966	1395	2575
	2	4	4	12	27	57
		6	6	19	34	64
PM2.5	1	5	5	14	29	59
	2	3	3	4	8	18
		4	4	5	10	21
		3	3	4	9	19
Northwest Coastal LA County	1.35 Acres					
	25	50	100	200	500	
NOx	118	118	133	167	251	
CO	655	966	1395	2575	7977	
PM10	5	14	29	59	149	
PM2.5	3	4	9	19	79	

Acre Below		Acre Above	
SRA No.	Acres	SRA No.	Acres
2	1	2	2
Distance Increment Below			
25			
Distance Increment Above			
25			

Updated: 10/21/2009 - Table C-1. 2006 – 2008