Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Isleton Wastewater Treatment System Improvement Project

Lead Agency: City of Isleton

Contact Name: Charles Bergson

Email: cbergson@cityofisleton.com Phone Number: 916-777-7770

Project Location: City of Isleton (*City*) Sacramento County (*County*)

Project Decription (Proposed actions, location, and/or consequences).

The Proposed Project includes sanitary sewer improvements, earthwork for raising pond berms, storm drain reconnections and equipment upgrades at the City's Wastewater Treatment Facility (WWTF, Figures 2a and 2b). The Proposed Project includes replacement of approximately 6,150 linear feet of wastewater gravity pipeline, abandonment of 660 linear feet of gravity sewer, 33 maintenance holes, and abandonment of 5,070 linear feet of wastewater gravity pipeline. Storm drain reconnections will include approximately 1,200 linear feet of new storm drain pipe, nine maintenance holes, and six drain inlet connections. Equipment upgrades at the WWTF will generally include installation of a new backup generator, new aerators, blowers and other required electrical equipment.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Air Quality: Exceeds AQ construction PM thresholds. Mitigation requires implementation of SMAQMD Basic and Enhanced Construction Emission Control Practices to Reduce Fugitive Dust.
Bio Resources: Potential impacts to northwestern pond turtle, giant garter snake, nesting birds, and bats. Mitigation includes preconstruction surveys by qualified personnel and contact CDFW if found.
Cultural Resources: Potential impacts to unknown cultural resources. Mitigation requires notification of discovered resources and investigation by professional archaeologist and proper handling of the resource.
Paleontological Resources: Potential impacts to unknown paleo resources. Mitigation requires notification of discovered resources and investigation by professional paleontologist and proper handling of the resource.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

No areas of controversy surrounding the project are currently known for this project.

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Wildlife, Region 2
Regional Water Quality Control Board, Central Valley Region (Region 5)
Sacramento Metropolitan Air Quality Management District