Print Form

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Roseton Plant New Tank and Booster Station Project

Lead Agency: State Water Resources Control Board

Contact Name: Adrian Dela Calzada

Email: Adrian.Delacalzada@waterboards.ca.gov Phone Number: (916) 341-5167

Project Location: 17456 Roseton Avenue, Artesia, CA, 90701. Los Angeles County.
City *County*

Project Decription (Proposed actions, location, and/or consequences).

The Project involves the construction of a 750,000-gallon above-ground potable water storage tank, booster pump station, stationary emergency generator, associated fencing, lighting, control panels, and appurtenances at the Roseton Well site. The Proposed Project would also relocate the existing backwash tank and motor control center. Existing plant site piping would be modified, as needed. The Project also includes removal of ornamental trees along the western fence line. The Project would increase storage to help provide potable water to the Artesia System and address the existing storage deficiency, add redundancy to the existing system, and maintain an uninterrupted supply of water for the system. The overall capacity required by the Artesia System would be the same as existing conditions, therefore there would be no capacity increase with the Proposed Project.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The following environmental resources are anticipated to have less than significant impact with mitigation measures (MM) incorporated: biological resources, cultural resources, geology and soils, tribal cultural resources, and noise.

a) Biological Resources: Ornamental trees on and near the Project Site could provide habitat for nesting birds. If construction or tree removal occurs during the bird breeding season these activities could directly and indirectly affect native and non-game birds along with their nests. Impacts would be less than significant with the implementation of MM BIO-1.
b) Cultural Resources: There is a potential for buried pre-contact sites below the level of previous disturbance; in compliance of CA H&SC Section 7050.5 and in accordance with PRC 5097.98; implementation of MMs CUL-1 and TCR-1 would reduce these impacts to less than significant.
c) Tribal Cultural Resources: A resource to be significant pursuant to criteria set forth in subdivision (c) of PRC Section 5024.1, in considering the significance of the resource to a California Native American Tribe; If an archaeological resource of Native American origin and cultural significance is discovered during construction and determined to be a TCR, or human remains are discovered at the site, implementation of MMs TCR-1, CUL-1, TCR-2, and TCR-3, as applicable, would reduce impacts to TCRs to a less than significant level.
d)Geology and Soils: If paleontological resources are encountered and destroyed during construction, implementation of MMs GEO-1 and GEO-2, would reduce these impacts would be less than significant.
d)Noise: backup/emergency generator may cause increase in noise levels. NOI-1 MM will be implemented to reduce these impact would be less than significant.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

None

Provide a list of the responsible or trustee agencies for the project.

California State Water Resources Control Board, Division of Drinking Water
South Coast Air Quality Management District