Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: GPC 22-11 Wolf Creek Road over Wolf Creek Bridge Replacement Project

Lead Agency: County of Lake

Contact Name: Katherine Schaefers

Email: resourceplanning@lakecountyca.gov Phone Number: 707-263-2221

Project Location: Spring Valley (*City*) Lake (*County*)

Project Description (Proposed actions, location, and/or consequences).

The bridge has a sufficiency rating of 60.1 and has been designated as functionally obsolete per the Caltrans Structure Maintenance & Investigations, Local Agency Bridge List (July 2015). The functionally obsolete designation is a result of the insufficient deck width. Wolf Creek Road is a two lane road and the clear width of the existing bridge is too narrow to support standard lane and shoulder widths for a two lane facility. Additionally, the existing bridge fails to meet the current Caltrans design standard for freeboard requirements. Hydraulic studies indicate that the existing bridge may be overtopped during a 100-year storm event. Caltrans has reviewed the preliminary details of the project and supports a full replacement scope. The purpose of the proposed project is to provide a replacement structure that is consistent with appropriate Caltrans structural design standards, is placed on a road alignment that meets the appropriate American Association of State Highway and Transportation Officials (AASHTO) roadway geometry standards, and is hydraulically capable of passing and clearing the design storm events (50-year storm plus 2 feet of freeboard and 100-year storm).

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Air Quality, Biological Resources, Hazards & Hazards Materials, Hydrology/Water Quality, Noise and Transportation. Mitigation Measures are listed in the Mitigated Negative Declaration and in Attachment B. All potential impacts will be reduced to less than significant with mitigation measures incorporated.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

Provide a list of the responsible or trustee agencies for the project.