Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: Palo Colorado Road Storm Damage Repair Project

Lead Agency: County of Monterey

Contact Name: Victor Gutierrez

Email: GutierrezVM@co.monterey.ca.us Phone Number: 831-755-4806

Project Location: Carmel-By-The-Sea, Monterey County
City *County*

Project Description (Proposed actions, location, and/or consequences).

The proposed project includes various repairs, including replacement of damaged asphalt, installation of steel guardrails, replacement of existing retaining walls with either steel soldier pile or soil nail retaining walls, replacement or improvements to existing culverts, and temporary relocation of utility lines, at 63 discontinuous work areas along an approximately 4.8 mile segment of Palo Colorado Road. The project also includes the construction of temporary construction storage areas to serve the proposed work areas. The 63 proposed work areas include 13 storm damage sites, 36 additional drainage improvement sites, and 14 construction storage areas.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

Agriculture: The project has the potential to result in loss of forest land. Mitigation has been identified that requires replacement of removed trees.
Air Quality: The project has the potential to expose sensitive receptors to construction-related emissions. Mitigation has been identified to reduce diesel particulate matter and fugitive dust emissions near sensitive receptor locations.
Biological Resources: The project has the potential to adversely affect special-status animal species, water resources, and native trees. Mitigation has been identified to reduce potential impacts through, environmental awareness training, biological monitoring, preconstruction surveys, best management practices (BMPs), permitting, and tree replacement.
Cultural/ Tribal Cultural Resources: The project has the potential to result in inadvertent discovery of archaeological resources. Mitigation has been identified to address inadvertent discovery.
Geology and Soils/Hydrology and Water Quality: The project has the potential to increase erosion and other pollutants at the project site. Mitigation has been identified to require implementation of construction BMPs.
Hazards and Hazardous Materials: The project has the potential to result in polluted runoff and to disturb ACM. Mitigation has been identified to avoid polluted runoff to surrounding areas and the release of asbestos from ACM.
Noise: The project has the potential to result in short-term construction related noise near sensitive land uses. Mitigation has been included to require the implementation of construction noise BMPs.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

N/A

Provide a list of the responsible or trustee agencies for the project.

California Department of Fish and Wildlife
Regional Water Quality Control Board
California Coastal Commission
U.S. Army Corps of Engineers
Monterey Bay Air Resources District