Appendix B
Arborist Report

ARBORIST REPORT

TREE IMPACT ASSESSMENT

APRIL 5, 2022

PREPARED FOR: ANDERSON ARCHITECTS INC

AND ROYGBIV REAL ESTATE DEVELOPMENT



PROJECT: RESIDENCIAS ARIANNA | 1298 TRIPP AVE., SAN JOSE, CA 95116







BO FIRESTONE TREES & GARDENS

BUSARA FIRESTONE, CERTIFIED ARBORIST #WE-8525A

2150 LACEY DR., MILPITAS, CA 95035

E: BUSARA@BOFIRESTONE.COM C: (408) 497-7158

WWW.BOFIRESTONE.COM



CONTENTS

Introduction	1
ASSIGNMENT	1
USES OF THIS REPORT	1
ASSUMPTIONS & LIMITATIONS	2
How Construction Can Damage Trees	2
Damage to Roots	2
Mechanical Injury	3
Tree Impact Assessment	4
TREE INVENTORY	4
SITE DESCRIPTION	4
PROJECT DESCRIPTION	4
IMPACTS OF CONSTRUCTION & TREE REMOVALS	5
Tree Preservation & Mitigation Measures	6
PRE-CONSTRUCTION	6
Establish Tree Protection Zones (TPZ):	6
Preventing Soil Disturbance & Root Damage	6
Pruning Branches	7
Pre-Construction Inspection	7
DURING CONSTRUCTION	7
Special Tree Protection Measures – Trees #2 - #26 and #28	7
Project Arborist Supervision	8
Irrigation	8
Root Pruning	9
POST-CONSTRUCTION	۵

1298 Tripp Ave. • RESIDENCIAS ARIANNA • 04/05/22

TREE IMPACT ASSESSMENT

Page	i
1 agc	

Continued Tree Care	9
Post-Construction Monitoring	10
Conclusion	10
SUPPORTING MATERIALS:	
PHOTOS	11
GLOSSARY	35
TPZ TRUNK WRAP DIAGRAM	36
TREE INVENTORY (TABLE)	37
TRFF MAP	39

Page 1 of 39

Introduction

ASSIGNMENT

On March 30th, 2022, at the request of the developer, I visited the project site at 1298 Tripp Avenue. I had accepted the assignment of Project Arborist and agreed to write an industry-standard tree inventory, impact assessment, and tree protection plan for their building permit application. It was my understanding that all structures on the parcels on Tripp Avenue between Wooster and 26th Street would be demolished and developed with two, multi-family residential buildings with parking on the basement level. The assessments in this report were based off review of the following conceptual plan sheets 002 – 011 (dated 11/19/21) which included but were not limited to the proposed site plan, grading and drainage plan, and elevations.

I identified 52 trees at risk of impact including neighboring trees. An ordinance-size tree in San Jose is generally one with total circumference of trunk(s) over 38 inches, although all trees may be deemed ordinance size on multi-family parcels. 19 trees were requested for removal including 18 small or undesirable trees on the property and one (1) Street Tree on Wooster. Please see the attached Tree Inventory and Tree Map for the locations and basic attributes of the trees identified for removal at the project site.

USES OF THIS REPORT

This report was written by Busara Firestone, Project Arborist, to serve as a resource for the property owner, designer, and builder. I recommend that all tree protection measures in this report be shown on the final grading, construction, and landscape plans, and adhered to during construction. This report may be submitted to the City of San Jose as part of the building permitting process.

Page 2 of 39

ASSUMPTIONS & LIMITATIONS

Trees assessed were limited to the scope of work identified in the assignment. Although general structure and health were assessed, formal Tree Risk Assessments were not conducted unless specified. Disease diagnostic work was not conducted unless specified.

I have estimated the trunk diameters of trees with barriers to access or visibility (such as those on neighboring parcels or behind debris).

All assessments were the result of ground-based, visual inspections. No excavation or aerial inspections were performed. Recommendations beyond those related to the proposed construction were not within the scope of work. Full tree risk assessments were not within the scope of work, although assessments of health and structure factored into my condition ratings for each tree.

My tree impact and preservation assessments were based on information provided in the plans I have reviewed to date, and conversations with the involved parties. I assumed that the guidelines and setbacks recommended in this report would be followed. Assessments, conclusions, and opinions shared in this report are not a guarantee of any specific outcome. If additional information (such as engineering or landscape plans) is provided for my review, these assessments would be subject to change.

How Construction Can Damage Trees

Damage to Roots

Where are the Roots?

The most common types of injury to trees that occur during property improvements are related to root cutting or damage. **Tree roots extend farther out than people realize, and the majority are located within the upper 24 inches of soil.** The thickest roots are found close to the trunk, and taper and branch into ropey roots. These ropey roots taper and branch into an intricate system of fine fibrous roots, which are connected to an even finer system of fungal filaments.

Page 3 of 39

This vast below-ground network is tasked with absorbing water and nutrients, as well as anchoring the tree in the ground, storage, and communication.

Damage from Excavation

Any type of excavation will impact adjacent trees by severing roots and thus cutting off the attached network. Severing larger roots, or trenching across the root plate, destroys large networks. Even work that appears to be far from a tree (like on the far side of the yard), will impact the fibrous root system where excavation is taking place. Placing impervious surface over the ground, or installing below ground structures, such as a pool, or basement wall, will remove rooting area permanently from a site.

Damage from Fill

Adding fill can smother roots, making it difficult for them to access air and water. The roots and other soil life need time to colonize the new upper layers of soil.

Changes to Drainage and Available Water

Changes to the hydrology of the site, caused for instance by new septic fields, changes to grade, and drainage systems, can also cause big changes in available water for trees. Trees can die from lack of water or disease if their water supply dries up or gets much wetter than they are used to.

Soil Compaction and Contamination

In addition, compaction of soil, or contamination of soil with wash-water, paint, fuel, or other chemicals used in the building process, can cause damage to the rooting environment that can last many years. Tree protection fencing creates a barrier to protect as many roots as possible from this damage. Potential causes may include travelling vehicles, equipment storage, and washing out concrete.

Mechanical Injury

Injury from the impact of vehicles or equipment can occur to the root crown, trunk, and lower branches of a tree. The bark protects a tree – creating a skin-like barrier from disease-causing organisms. The stem tissues are in charge of supporting the weight of the plant, and conducting the flow of water, sugars, and other important compounds throughout the tree. When the bark and wood is injured, the structure and health of the tree is compromised.

Page 4 of 39

Tree Impact Assessment

TREE INVENTORY

This report includes an attached inventory of all trees over four inches (4" DBH) that would be potentially impacted. This inventory also includes any trees on adjacent parcels that extended into the work area. The Inventory includes each tree's number (as shown on the TPZ map), measurements, condition, level of impact (due to proximity to work), tolerance to construction, overall suitability for conservation, and prescription (remove/protect).

SITE DESCRIPTION

The proposed building site was comprised of several residential lots on or between W. 26th Street and Wooster Avenue with frontage of the proposed development on Tripp Avenue. The dominant trees were mature zelkova (*Zelkova serrata*) Street Trees and Modesto ash (*Fraxinus velutina*) in the park strip along Tripp Ave. The parcels to be developed had only small trees in poor condition, various fruit trees, and several invasive tree of heaven (*Ailanthus altissima*). All trees on the private properties to be developed were, in my assessment, trees of low landscape value. There was one mature hackberry tree (*Cercis sp.*) in the public right-of-way on Wooster Avenue. Along the back of the proposed development there was a row of neighboring trees with canopies overhanging the site. Trees of note included two rows of Italian cypress (*Cupressus sempervirens*) and several Raywood ash (*Fraxinus oxycarpa* 'Raywood').

PROJECT DESCRIPTION

It was my understanding that two, multi-story, multi-family residential buildings were proposed on the parcels on Tripp Avenue between Wooster and 26th Street. All existing structures would be demolished. Parking would be on the basement level. New landscaping was also proposed.

Page 5 of 39

IMPACTS OF CONSTRUCTION & TREE REMOVALS

I identified 52 trees at risk of impact including neighboring trees. Trees have been labeled #1 - #52 on the Tree Map and Inventory table included in this report. **18 small trees on the site to be developed and one (1) Street Tree on Wooster were requested for removal.**

Trees on private property were low-value species, with the tree of heaven listed as an "undesirable species" by the City of San Jose. Tree #42 was a City Street Tree (hackberry). This tree would need to be removed to make way for the new location of the curb and sidewalk along Wooster Avenue. All the trees on the parcels to be developed would be within the footprint of the proposed buildings or landscape improvements and could not survive the project. Nor could the building be constructed if they were to remain. Removal of Trees #1, #27, #29 - #43, #50, and #52 would be justified for the economic development of the parcel. Furthermore, Trees #29, #30, #37 - #40 and #43 were of undesirable species.

Impacted trees to be preserved included all Street Trees on Tripp Avenue and neighboring trees with canopies overhanging the back property line of the proposed development. Anticipated impacts to these trees are as follows:

Trees #44 - #49 and #51 (Street Trees): These mature zelkova and ash along Tripp Avenue and 26^{th} Street would be expected to sustain a moderate (acceptable) impact of 10 - 25% roots loss from the proposed demo work, excavation of the new foundation, and landscaping in front of the new buildings.

Trees #2 - #26 and #28 (neighboring trees): these trees along the back property line of the proposed development would be expected to sustain a moderate (acceptable) impact of 10 – 25% roots loss from the proposed demo work and excavation of the new foundation. Since landscaping work could damage these trees, I recommend limiting the extent of grading and excavation work within 10 feet of these trees. Please see "Special Tree Protection Measures Section" of this report for instructions.

Page 6 of 39

Tree Preservation & Mitigation Measures

PRE-CONSTRUCTION

Establish Tree Protection Zones (TPZ):

The Tree Protection Zone (TPZ) shall be a fenced-off area where work and material storage is not allowed. This barrier protects the critical root zone and trunk from compaction, mechanical damage, and chemical spills. The TPZ should be in-place before work starts and should stay in-place until the project is complete. Since only neighboring trees and Street trees would be preserved for this project, typical fenced tree enclosures would not be practical. I recommend the following measures:

Trees #44 - #49 and #51 (Street Trees): I recommended TPZ Trunk Wrap as an alternative to protect these street trees where there may not be enough room in the planting strip to install fencing. **Please see attached "TPZ Trunk Wrap" specification for best-practice method using dimensional lumber**. Straw wattle coiled from the ground to 6' height, secured with two layers of plastic construction fencing is also generally acceptable. If the City of San Jose provides a specification for use on City Street Trees, do use those instead.

Trees #2 - #26 and #28 (neighboring trees): These neighboring trees would be protected adequately by the five-foot-tall existing chain link fence at the property line. Due to the location of the work, an additional chain link fence at this location would not be practical.

Preventing Soil Disturbance & Root Damage

I recommend that anywhere workers and vehicles will be traveling over bare ground within fifteen feet of a tree's dripline should have material applied over the ground to disperse the load. This may be done by applying a six to 12-inch layer of wood chip mulch to the area. As an alternative method that would not require mulch removal, the contractor could place plywood

Page **7** of **39**

(>3/4-inch-thick) or road mats over a four-inch layer of mulch. Mulch should be spread manually so as not cause compaction or damage.

Pruning Branches

I recommend that each tree that is designated to remain shall be pruned **only as necessary** to provide clearance for development, while maintaining a natural appearance. Any large dead branches should be removed for the safety of people working on the site. Pruning should be specified in writing adhering to ANSI A300 Pruning Standards and performed according to Best Management Practices endorsed by the International Society of Arboriculture. Any pruning (trimming) of branches should be supervised by an ISA-certified arborist. **Pruning of street trees requires a permit from the City of San Jose.**

Pre-Construction Inspection

Prior to Issuance of a Building Permit (including Grading or Demolition Permits), it is common for municipal Planning and Building Departments to request a pre-construction site inspection and report, to verify that all required tree protection and erosion control measures are in place. Inquire with your Planning Department contact for requirements.

DURING CONSTRUCTION

Special Tree Protection Measures – Trees #2 - #26 and #28

Demolition of existing hardscape should be performed in a manner that avoids tearing roots: Using the smallest effective machinery, break up pieces of the concrete and lift pieces up and away from trees. Cut roots embedded in paving rather than tearing them (see instructions on root cuts).

Landscaping: When excavating within 10 feet of this tree, use hand tools. Leave roots encountered undisturbed if possible. Excavation depth for installation of new landscape

Page 8 of 39

materials within 10 feet of trees should be no more than 4". Minimize compaction of subgrade under pavers. If roots must be cut, please see section titled "Root Pruning." No paving materials or any excavation or grading within three (3) feet of trunks.

Project Arborist Supervision

If arborist monitoring is required during the project, I recommend the following monitoring schedule:

- Pre-construction site inspection, to verify that all required tree protection and erosion control measures are in place.
- Demolition, grading, and excavation, and/or trenching activities where grade changes exceed 4" within the drip line of a protected tree. Boring for pier installation.
- Monthly TPZ compliance inspections.
- Any pruning or root pruning activities.
- Final compliance report

Irrigation

Maintain normal irrigation; as a rule of thumb, provide 1- 2 inches per month. Water slowly so that it penetrates 18 inches into the soil, to the depth of the tree roots. However, native oaks usually should not be provided supplemental water during the warm, dry season (June – September) as this activates oak root fungus. Therefore, native oaks should only be watered October – May when rain has been scarce.

Page 9 of 39

Root Pruning

Roots often extend farther beyond the tree than people realize. Even outside of the fencing protecting the critical root zone, there are roots that are important to the wellbeing of the tree. Builders may notice torn roots after digging or trenching. If this happens, exposed ends should be cut cleanly.

However, the best way to cut roots is to cut them cleanly *before* they are torn by excavating equipment. Roots may be exposed by gentle excavation methods and then cut selectively. Alternatively, a tool specifically designed to cut roots may be used to cut through the soil on the tree-side of the excavation line prior to digging so that roots are not torn. I recommend that root pruning of any root over one inch (1") be supervised by the project arborist.

POST-CONSTRUCTION

Ensure any mitigation measures to ensure long-term survival including but not limited to:

Continued Tree Care

Provide adequate and appropriate irrigation. As a rule of thumb, provide 1- 2 inches of water per month. Water slowly so that it penetrates 18 inches into the soil, to the depth of the tree roots. Native oaks usually should not be provided supplemental water during the warm, dry season (June – September) as this activates oak root fungus. Therefore, native oaks should only be watered October – May when rain has been scarce.

Mulch insulates the soil, reduces weeds, reduces compaction, and promotes myriad benefits to soil life and tree health. Apply four inches of wood chips (or other mulch) to the surface of the soil around trees, extending at least to the dripline when possible. Take care not to pile mulch against the trunk.

Do not fertilize unless a specific nutrient deficiency has been identified and a specific plan prescribed by the project arborist (or a consulting arborist).

Page 10 of 39

Post-Construction Monitoring

Monitor trees for changes in condition. Check trees at least once per month for the first year post-construction. Expert monitoring should be done at least every 6 months or if trees show signs of stress. Signs of stress include unseasonably sparse canopy, leaf drop, early fall color, browning of needles, and shoot die-back. Stressed trees are also more vulnerable to certain disease and pest infestations. Call the Project Arborist, or a consulting arborist if these, or other concerning changes occur in tree health.

Conclusion

The proposed multi-family building project appeared to be a valuable upgrade to the neighborhood. After review of the plan set, I determined that retainment of trees #1, #27, #29 - #43, #50, and #52 would not be possible if the project were to move forward as planned.

If any of the parties involved have questions on this report, or require Project Arborist supervision or technical support, please do not hesitate to contact me at (408) 497-7158 or busara@bofirestone.com.

Signed,

Bo Firestone | ISA Certified Arborist WE-#8525A | ISA Qualified Tree Risk Assessor | ASCA Tree and Plant Appraisal Qualification | Member – American Society of Consulting Arborists

Page 11 of **39**

Supporting Documents

Photos




Page 12 of **39**




Page 13 of **39**



Page 14 of **39**




Page 15 of **39**




Page 16 of **39**



Page 17 of **39**



Page 18 of **39**



Page 19 of **39**




Page 20 of **39**




Page 21 of **39**




Page 22 of **39**



Page 23 of **39**



Page 24 of **39**



Page 25 of **39**



Page 26 of **39**



Page 27 of **39**




Page 28 of **39**




Page 29 of **39**




Page 30 of **39**




Page 31 of **39**



Page 32 of **39**



Page 33 of **39**



Page 34 of **39**



Glossary

DBH / DSH: Trunk diameter at 4.5' above grade. Trees which branch at 4.5' may be measured at the narrowest part below the point of branching.

Mathematic DBH: diameter of multitrunked tree, mathematically derived from the combined area of all trunks.

CONDITION-Ground based visual assessment of structural and physiological well-being:

"Excellent" = 81 - 100%; Good health and structure with significant size, location or quality.

"Good" = 61-80%; Normal vigor, full canopy, no observable significant structural defects, many years of service life remaining.

"Fair" = 41-60%; Reduced vigor, a significant structural defect, or multiple correctable defects, and/or other significant signs of stress

"Poor" = 21- 40%; In potentially irreversible decline, structure an aesthetics severely compromised

"Very Poor" = 6-20%; Nearly dead, or high risk of failure, negative contribution to the landscape


"Dead/Unstable" = 0 - 5%; No live canopy/buds or failure imminent

SPREAD: Diameter of canopy between farthest branch tips

TREE STATUS: A "Protected Tree" in the City of Campbell has a trunk diameter (DBH) of 12 inches or more. Exceptions may be granted by the City for certain undesirable species. "Street Trees" within the public right-of-way and are public property. However, some responsibility for the tree may fall to the adjacent property owner (please refer to your City code).

TPZ II – Alternative Method of Tree Protection

May be used to protect trunk from damage during construction activities when standard TPZ fencing is not practical. Install prior to construction activities. Adjust to allow for diameter growth as needed.



TREE INVENTORY - 1298 Tripp Ave., SAN JOSE, CA

4/5/2022

All trees on th	trees on the property with a trunk > 4" dbh, and over 6' tall.												
Number	Common Name	Botanical Name	Circ. (inches)	DBH (inches)	Height (feet)	Spread (feet)	Status*	Condition	Age	Species Tolerance	Impact Level	Suitability Rating	REMOVE/ RETAIN
1	Chinese Juniper	Juniperus chinensis	35	11	10	5	N/A	POOR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
2	Hollywood Juniper	Juniperus chinensis 'Torulosa'	28	est. 9	20	20	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
3	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
4	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
5	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
6	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
7	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
8	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
9	Italian Cypress	Cupressus sempervirens	25	8	50	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
10	Raywood Ash	Fraxinus oxycarpa 'Raywood'	44	est. 14	35	25	Ordinance-size	POOR	OVERMATURE	MODERATE	MODERATE	LOW	RETAIN
11	Raywood Ash	Fraxinus oxycarpa 'Raywood'	38	est. 12	45	25	Ordinance-size	FAIR	MATURE	MODERATE	MODERATE	MODERATE	RETAIN
12	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
13	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
14	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
15	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
16	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
17	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
18	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
19	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
20	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
21	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
22	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
23	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
24	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
25	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
26	Italian Cypress	Cupressus sempervirens	19	6	45	5	N/A	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
27	Fig	Ficus carica	19	6	20	15	Fruit Tree	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
28	Avocado	Persea americana	44	(2) 10	25	30	Fruit Tree	GOOD	MATURE	MODERATE	MODERATE	HIGH	REMOVE (X)
29	Tree of Heaven	Ailanthus altissima	82	24, 10	45	35	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
30	Tree of Heaven	Ailanthus altissima	38	12	40	30	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)

TREE INVENTORY - 1298 Tripp Ave., SAN JOSE, CA

4/5/2022

All trees on the property with a trunk > 4" dbh, and over 6' tall.								TREE IMPACT ASSESSMENT					
Number	Common Name	Botanical Name	Circ. (inches)	DBH (inches)	Height (feet)	Spread (feet)	Status*	Condition	Age	Species Tolerance	Impact Level	Suitability Rating	REMOVE/ RETAIN
31	Guava species	Psidum spp.	25	est. 8	20	15	Fruit Tree	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
32	Guava species	Psidum spp.	19	est. 6	15	5	Fruit Tree	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
33	Lemon	Citrus limon	13	est. 4	15	10	Fruit Tree	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
34	Apple	Malus spp.	13	est. 4	15	5	Fruit Tree	POOR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
35	Apple	Malus spp.	13	est. 4	15	5	Fruit Tree	POOR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
36	Citrus	Citrus spp.	19	est. 6	20	15	Fruit Tree	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
37	Tree of Heaven	Ailanthus altissima	44	(2) 10	40	15	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
38	Tree of Heaven	Ailanthus altissima	28	est. 9	40	15	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
39	Tree of Heaven	Ailanthus altissima	13	est. 4	40	25	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
40	Tree of Heaven	Ailanthus altissima	25	est. 8	40	15	undesirable species	FAIR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
41	Avocado	Persea americana	19	6	15	10	Fruit Tree	FAIR	YOUNG	MODERATE	SEVERE	LOW	REMOVE (X)
42	Chinese Hackberry	Celtis sinensis	44	14	40	25	STREET TREE	FAIR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
43	Tree of Heaven	Ailanthus altissima	31	est. 10	20	10	undesirable species	POOR	MATURE	HIGH	SEVERE	LOW	REMOVE (X)
44	Sawleaf Zelkova	Zelkova serrata	72	23	60	50	STREET TREE	FAIR	MATURE	MODERATE	MODERATE	MODERATE	RETAIN
45	Sawleaf Zelkova	Zelkova serrata	91	29	60	40	STREET TREE	FAIR	MATURE	MODERATE	MODERATE	MODERATE	RETAIN
46	Sawleaf Zelkova	Zelkova serrata	75	24	55	40	STREET TREE	GOOD	MATURE	MODERATE	MODERATE	HIGH	RETAIN
47	Sawleaf Zelkova	Zelkova serrata	97	31	60	50	STREET TREE	FAIR	MATURE	MODERATE	MODERATE	MODERATE	RETAIN
48	Modesto Ash	Fraxinus velutina	116	37	65	45	STREET TREE	FAIR	OVERMATURE	MODERATE	MODERATE	MODERATE	RETAIN
49	Modesto Ash	Fraxinus velutina	110	35	55	35	STREET TREE	FAIR	OVERMATURE	MODERATE	MODERATE	MODERATE	RETAIN
50	Juniper	Juniperus spp.	25	est. 8	15	5	N/A	POOR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)
51	Modesto Ash	Fraxinus velutina	122	39	60	40	STREET TREE	FAIR	MATURE	MODERATE	SEVERE	LOW	RETAIN
52	Weeping Bottlebrush	Callistemon viminalis	19	est. 6	25	5	N/A	POOR	MATURE	MODERATE	SEVERE	LOW	REMOVE (X)

NAGE NOTES OR REPRESENTATIVE SHALL NOTIFY THE CITY OF SAN JOSE DEPARTMENT OF 12. CIVIL ENGINEER INFORMATION AND STATEMENTS: RT OF ANY GRADING. THE CIVIL ENGINEER FOR THIS PROJECT IS: V7H ENGINEERING, LLP DAVE VOORHIES,5623 LE FEVRE DRIVE, SAN JOSE, CA 95118 B. THIS ROUGH GRADING PLAN HAS BEEN PREPARED UNDER THE DIRECTION OF A LICENSED ENGINEER AND VOICEMAIL NO. (408) 975-____ DESIGNED BASED ON THE RECOMMENDATIONS OF THE REFERENCED PROJECT GEOTECHNICAL REPORT. CEMENT, AND COMPACTION OF NATURAL EARTH MATERIALS, (B) THE C. THE STORMWATER CONVEYANCE SYSTEM HAS BEEN DESIGNED IN ACCORDANCE WITH THE APPROPRIATE NVEYANCE AND TREATMENT FACILITIES THAT ARE OUTSIDE OF THE 5-FOOT BUILDING AND PLUMBING CODES OR HAS BEEN PROVEN TO BE DESIGNED WITH ADEQUATE CAPACITY THROUGH TURES. THIS APPROVAL DOES NOT CONFER ANY RIGHTS OF ENTRY TO EITHER SIGNED AND SEALED HYDRAULIC CALCULATIONS. OF THIS PLAN ALSO DOES NOT CONSTITUTE APPROVAL OF ANY)SED IMPROVEMENTS, WITH THE EXCEPTION OF THOSE LISTED ABOVE, ARE 13. SOILS ENGINEER INFORMATION AND REQUIREMENTS: S AND ALL OTHER REQUIRED PERMITS SHALL BE OBTAINED. A. THE SOIL ENGINEER FOR THIS PROJECT IS: (NAME AND ADDRESS) JING STRUCTURE ON THIS PLAN SHALL NOT CONSTITUTE APPROVAL FOR TRUCTURAL REVIEW, BY THE DEPARTMENT OF PUBLIC WORKS IS COMPLETED B. THE GEOTECHNICAL REPORT FOR THIS PROJECT IS: INTIFY, LOCATE AND PROTECT ALL UNDERGROUND FACILITIES. C. ALL GRADING WORK SHALL CONFORM TO THE RECOMMENDATIONS OF THE PROJECT GEOTECHNICAL REPORT AND/OR THE PROJECT SOIL ENGINEER. AND ALL OTHER PUBLIC RIGHTS-OF-WAY IN A CLEAN, SAFE AND USABLE ALL BE REMOVED FROM THE PUBLICLY OWNED PROPERTY DURING CONSTRUCTION D. ALL GRADING WORK SHALL BE OBSERVED AND APPROVED BY THE SOIL ENGINEER. THE SOIL ENGINEER SHALL BE PRIVATE OR PUBLIC SHALL BE MAINTAINED IN A CLEAN, SAFE AND USABLE NOTIFIED AT LEAST 48 HOURS BEFORE BEGINNING ANY GRADING. UNOBSERVED AND/OR UNAPPROVED GRADING

OBSERVE THE CONSTRUCTION STATING:

(408) 794-6805.

TPZ MAP LEGEND:

LY WITH THE STANDARDS ESTABLISHED BY THE AIR QUALITY MANAGEMENT

ARD AREA REGULATIONS AS STATED IN CHAPTER 17.08 OF THE SAN JOSE

SUCH WELLS SHALL BE MAINTAINED OR ABANDONED ACCORDING TO CURRENT

TRICT. CALL (408) 265-2600 EXTENSION 2660 TO ARRANGE FOR DISTRICT

RE FOUND, ALL PROJECT—RELATED CONSTRUCTION SHOULD CEASE WITHIN A

TE TREE REMOVAL PERMITS AND METHODS OF TREE PRESERVATION SHOULD BE

JLTING FROM PROJECT RELATED EXCAVATION OR LAND CLEARING SHALL BE

PRANT WATER CAN BE CONSIDERED IN THE PW DEVELOPMENT SERVICES OFFICE.

THAN 10,000 C.Y. OF EARTH. THIS GRADING PERMIT IS INVALID WITHOUT THE

1TH OF ANY YEAR WITHOUT EROSION CONTROL PLANS AND MEASURES

TION PREVENTION MEASURES IN ACCORDANCE WITH CITY SPECIFICATIONS AND

THROUGHOUT THE YEAR TO THE SATISFACTION OF THE DIRECTOR OF PUBLIC

OR OF PUBLIC WORKS FROM A CIVIL OR SOILS ENGINEER RETAINED BY THE

OF THE IMPROVEMENTS APPROVED WITH THIS PLAN SUCH AS SUBDRAINS,

3" DEPRESS LANDSCAPE -

2

[26TH

STREET

CURB RAMP -

'050.5 OF THE HEALTH AND SAFETY CODE, AND SECTION 5097.94 OF THE

SANTA CLARA COUNTY CORONER IMMEDIATELY.

OM THE CITY'S TRANSPORTATION DEPARTMENT.

ARDS CODE SECTION 5.408.

ON-SITE RETAINING STRUCTURES.

WORK SHALL BE REMOVED AND REPLACED UNDER OBSERVATION.

COMPATIBLE," AND SUPPLY SUPPORTING DATA; OR

TREE TO REMOVE

TREE TO REMAIN

WORKS" AND THE CIVIL ENGINEER SHALL SUBMIT A "RECORD DRAWING" PLAN.

ENGINEERING GEOLOGIST IF THE PROJECT IS IN A GEOLOGIC HAZARD ZONE, STATING:

PURPOSES INCLUDING CONSOLIDATION OF BACKFILL OR DUST CONTROL IS PROHIBITED.

A. "THAT THE CONSTRUCTION CONFORMS TO THE LINES AND GRADES ON THE APPROVED PLANS;" OR

B. "THAT ALL SIGNIFICANT CHANGES WERE REVIEWED AND APPROVED IN ADVANCE BY THE DEPARTMENT OF PUBLIC

A. "THAT THE ANTICIPATED CONDITIONS AND MATERIALS AND ACTUAL SITE CONDITIONS AND MATERIALS WERE

B. "THAT THE DESIGN WAS MODIFIED TO MEET THE NEW CONDITIONS AND WAS REVIEWED AND APPROVED IN ADVANCE BY THE DEPARTMENT OF PUBLIC WORKS;" AND PROVIDE SUPPORTING DATA FOR THESE STATEMENTS.

TREE ON NEIGHBORS' PROPERTY / PUBLIC RIGHT-OF-WAY

14. A POST CONSTRUCTION "FINAL" REPORT IS REQUIRED BY THE DIRECTOR OF PUBLIC WORKS FROM A CIVIL ENGINEER RETAINED BY THE OWNER TO

15. A POST CONSTRUCTION "FINAL" REPORT IS REQUIRED BY THE DIRECTOR OF PUBLIC WORKS FROM A SOIL ENGINEER, AND ALSO FROM AN

16. ACCORDING TO THE CITY'S WASTE WATER ORDINANCE, THE USE OF POTABLE (PIPED OR HYDRANT) WATER FOR BUILDING OR CONSTRUCTION

RECLAIMED WATER IS AVAILABLE AT MULTIPLE LOCATIONS ACROSS THE CITY. TO CERTIFY FOR A RECYCLED WATER METER, PLEASE CALL LYLE FROHMAN AT

- BIORETENTION BASIN (TYPICAL)

____ 3" DEPRESS LANDSCAPE

SURVEY DATUM NAVD 88.
 EASTERN PORTION OF PROJECT IS IN FEMA FLOOD ZONE AH. REMAINDER OF SITE IS IN FEMA FLOOD ZONE X.

SURVEY NOTES

EXISTING (Symbol Size May Vary) PROPOSED Property Boundary Lot Line Easement Line _ _ _ _ _ _ _ _ Building Line Grade Break — — GB— — — Curb & Gutter Sanitary Sewer Line -----SS------Water Line _____w___ Electric Line —— —— —E— —— —— City Standard Curb Inlet Field Inlet / Flat Grate Inlet Sanitary Sewer Clean Out Water Valve Streetlighting / Utility Box Water Valve **ABBREVIATIONS**

INV

MIN

SD

SDMH

UB

BSW88.85

INVERT ELEVATION

PROPERTY LINE

STORM DRAIN

STREET LIGHT

TOP OF CURB

UTILITY BOX

SANITARY SEWER

STORM DRAIN MANHOLE

SANITARY SEWER CLEAN OUT

MINIMUM

PAVEMENT

LEGEND

BW BACK OF WALK

CONCRETE

FACE OF CURB

FINISH FLOOR

FINISH GRADE

GRADE BREAK

HIGH POINT

HP

BIORETENTION BASIN (TYPICAL)


____ 3" DEPRESS LANDSCAPE

FIRE SERVICE or FINISH SURFACE SSCO

EXISTING

CLEAN OUT TO GRADE

DOMESTIC WATER



TREE MAD

1"= 20' feet \[\begin{align*} \beg

TRUNK WRAP (SEE ATTACHED SPEC. IF APPLICABLE) AND LOCATIONS ARE APPROXIMATE. TRIPP AVE TC88.20 TC88.65 26' DRIVEWAY - CURB RAMP C89.46 0.5% No tree BSW89.68 3" DEPRESS LANDSCAPE 0.5% LP TC88.00 2% — FLOW THROUGH PLANTER (TYPICAL) -GB 89.40 € -_FLOW THROUGH PLANTER_ FF92.2 C82.9 (8'-3" OVERHEAD CLEARANCE) TYPICAL) — FLOW THROUGH PLANTER (TYPICAL) BLDG 2 BLDG 1 BLDG 1 BLDG 2 FF92.2± FF92.2± FF90.7± FF90.7± PROPOSED 10' STREET EASEMENT DICTATION

HP C91.00


NOTE: ALL TREES WERE PLACED BY PROJECT ARBORIST

DATE: 04/05/22

TPZ ELEMENTS DRAWN:
B. FIRESTONE
ISA-CERTIFIED ARBORIST
#WE-8525A

BASE MAP: CONCEPTUAL GRADING & DRAINAGE PLAN by ANDERSON ARCHITECTS (11/19/2021)

> ARBORIST REPORT pg. 39



Anderson Architects INC

The use of these plans and specifications shall be restricted to the specific site for which they were prepared and publication thereof shall be expressly limited to such use. Reuse, reproduction or publication by any method, in whole or in part, is prohibited. Title to the plans and specifications remains with ANDERSON ARCHITECTS INC. without prejudice. Visual contact with these plans and specifications shall constitute prima facie evidence of the acceptance of the restrictions.

ROYGBIV REAL ESTATE


1238 SUTTER ST SUITE 801, SAN FRANCISCO, CA 94109

VILA DE CAMILA

SITE DEVELOPMENT **PERMIT**

Project File Number: H22-012

Taniguchi Landscape Architecture
1013 South Claremont St., Ste 1
San Mateo, CA 94402 v 650.638.9985 | f 650.638.9986



Issued For

	188UCU	1'01
No.	Description	Date
	Resubmittal	03/16/22
	Resubmittal	07/13/22
	Resubmittal	11/03/22
	Resubmittal	01/31/23
Scale	:	1" = 30'-0")"
Draw	n By:	DT
Chec	ked By:	DT

EXISTING TREE PLAN

1:1 1:1 1:1 15 gallon can

20, 15 gallon can or 10, 24 in. box

10, 24" box trees


Less than 19 inches

TOTAL

Landscape Plan Proposal: replacement trees

Unmet replacement trees on-site In-lieu fee (\$755.00 per tree x 0 trees)

File: X:\PROJECTS\605 S 2ND ST Job: VILA DE CAMILA



				1	n	d	6	r	9	o n
A	~	_	h		4	_	_	4	6	1110
		C		_		е	C	т	S	INC

kanderson@andarchinc.com Kurt B. Anderson. AIA Cell 408.202.5462

120 W. Campbell Ave. Suite D Tel. 408.371.1269 Campbell, CA 95008 Fax. 408.371.1276 www. andarchinc.com

specific site for which they were prepared and publication thereof shall be expressly limited to such use. Reuse, reproduction or publication by any method, in whole or in part, is prohibited. Title to the plans and specifications remains with ANDERSON ARCHITECTS INC. without prejudice. Visual contact with these plans and specifications shall constitute prima facie evidence of the acceptance of the restrictions.

ROYGBIV REAL ESTATE DEVELOPMENT

1238 SUTTER ST SUITE 801, SAN FRANCISCO, CA 94109

1347 E JULIAN

1347 E JULIAN ST. SAN JOSE, CA

SITE DEVELOPMENT **PERMIT**

PROJECT FILE NO: H22-001

Taniguchi Landscape Architecture 1013 South Claremont St., Ste 1

San Mateo, CA 94402 v 650.638.9985 | f 650.638.9986 CLA #2942

	Issued For	
No.	Description	Date
0	Resubmittal	May 5, 202
1	Resubmittal	July 20,202
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
Issued	Date: July 14, 2021	•

1" = 10'-0"

Drawn By: DT

Checked By: DT

Sheet Title:

LANDSCAPE PLAN STREET LEVEL

Sheet No .:

TLA Job: 21025.000