

**Appendix E:
Geotechnical Report**

THIS PAGE INTENTIONALLY LEFT BLANK

**GEOTECHNICAL ENGINEERING INVESTIGATION
PROPOSED SDG COMMERCE 220, LLC
DISTRIBUTION CENTER
1055 COMMERCE COURT
AMERICAN CANYON, CALIFORNIA**

**PROJECT NO. 032-20054
JULY 25, 2023**

Prepared for:

**MR. JOHN WOJTAS
INDUSTRIAL AND COMMERCIAL CONTRACTORS, L.P.
413 W. YOSEMITE AVENUE, SUITE 105
MADERA, CALIFORNIA 93637**

Prepared by:

**KRAZAN & ASSOCIATES, INC.
GEOTECHNICAL ENGINEERING DIVISION
4320 ORANGE GROVE AVENUE, SUITE E-F
SACRAMENTO, CALIFORNIA 95841
(916) 564-2200**

 **Krazan & ASSOCIATES, INC.**

GEOTECHNICAL ENGINEERING • ENVIRONMENTAL ENGINEERING
CONSTRUCTION TESTING & INSPECTION

July 25, 2023

KA No. 032-20054

Mr. John Wojtas
Industrial and Commercial Contractors, L.P.
413 W. Yosemite Avenue, Suite 105
Madera, California 93637

**RE: Geotechnical Engineering Investigation
Proposed SDG Commerce 220, LLC Distribution Center
1055 Commerce Court
American Canyon, California**


Dear Mr. Wojtas:

In accordance with your request, we have completed a Geotechnical Engineering Investigation for the above-referenced site. The results of our investigation are presented in the attached report.

If you have any questions or if we may be of further assistance, please do not hesitate to contact our office at or (916) 564-2200.



Respectfully submitted,
KRAZAN & ASSOCIATES, INC.


David R. Jarosz, II
Managing Engineer
RGE No. 2698/RCE No. 60185

DRJ:ht

TABLE OF CONTENTS

INTRODUCTION 1

PURPOSE AND SCOPE..... 1

PROPOSED CONSTRUCTION 2

SITE LOCATION, SITE HISTORY AND SITE DESCRIPTION..... 2

GEOLOGIC SETTING 3

FIELD AND LABORATORY INVESTIGATIONS 3

SOIL PROFILE AND SUBSURFACE CONDITIONS 4

GROUNDWATER..... 4

SOIL LIQUEFACTION..... 5

CONCLUSIONS AND RECOMMENDATIONS..... 6

 Administrative Summary 6

 Groundwater Influence on Structures/Construction..... 8

 Site Preparation..... 8

 Engineered Fill..... 10

 Drainage and Landscaping..... 11

 Utility Trench Backfill..... 11

 Foundations..... 12

 Floor Slabs and Exterior Flatwork..... 12

 Lateral Earth Pressures and Retaining Walls..... 13

 R-Value Test Results and Pavement Design..... 14

 Seismic Parameters – 2019 CBC 16

 Soil Cement Reactivity 17

 Compacted Material Acceptance 17

 Testing and Inspection 17

LIMITATIONS..... 17

SITE PLANS 20

LOGS OF BORINGS (1 TO 24)..... Appendix A

GENERAL EARTHWORK SPECIFICATIONS..... Appendix B

GENERAL PAVING SPECIFICATIONS Appendix C

January 18, 2021

KA Project No. 032-20054

**GEOTECHNICAL ENGINEERING INVESTIGATION
PROPOSED SDG COMMERCE 220, LLC DISTRIBUTION CENTER
1055 COMMERCE COURT
AMERICAN CANYON, CALIFORNIA**

INTRODUCTION

This report presents the results of our Geotechnical Engineering Investigation for the proposed SDG Commerce 220 Distribution Center to be located at Commerce Court near Eucalyptus Drive in American Canyon, California. Discussions regarding site conditions are presented herein, together with conclusions and recommendations pertaining to site preparation, Engineered Fill, utility trench backfill, drainage and landscaping, foundations, concrete floor slabs and exterior flatwork, retaining walls, pavement design and soil cement reactivity.

A site plan showing the approximate boring locations is presented following the text of this report. A description of the field investigation, boring logs, and the boring log legend are presented in Appendix A. Appendix A contains a description of the laboratory-testing phase of this study, along with the laboratory test results. Appendices B and C contain guides to earthwork and pavement specifications. When conflicts in the text of the report occur with the general specifications in the appendices, the recommendations in the text of the report have precedence.

PURPOSE AND SCOPE

This investigation was conducted to evaluate the soil and groundwater conditions at the site, to make geotechnical engineering recommendations for use in design of specific construction elements, and to provide criteria for site preparation and Engineered Fill construction.

Our scope of services was outlined in our proposal dated October 13, 2020 (KA Proposal P721-20 and included the following:

- A site reconnaissance by a member of our engineering staff to evaluate the surface conditions at the project site.
- A field investigation consisting of drilling 24 borings to depths ranging from approximately 10 to 50 feet for evaluation of the subsurface conditions at the project site.
- Performing laboratory tests on representative soil samples obtained from the borings to evaluate the physical and index properties of the subsurface soils.

-
- Evaluation of the data obtained from the investigation and an engineering analysis to provide recommendations for use in the project design and preparation of construction specifications.
 - Preparation of this report summarizing the results, conclusions, recommendations, and findings of our investigation.

PROPOSED CONSTRUCTION

We understand that design of the proposed development is currently underway; structural load information and other final details pertaining to the structures are unavailable. On a preliminary basis, it is understood that development will include the construction of an approximately 220,000 square foot distribution center building. It is anticipated the building will be a single-story concrete tilt-up structure utilizing concrete slab-on-grade construction. Foundation loads are anticipated to be light to moderate. On-site paved areas and landscaping are also planned for the development of the project.

In the event, these structural or grading details are inconsistent with the final design criteria, the Soils Engineer should be notified so that we may update this writing as applicable.

SITE LOCATION, SITE HISTORY AND SITE DESCRIPTION

The site is roughly rectangular in shape encompasses approximately 10.17 acres. The site is located near the south end of Commerce Court, approximately ¼ mile south of Green Island Road in American Canyon, California. The site has a street address of 1055 Commerce Court. The site is surrounded by vacant land, wetlands, groves of trees, and industrial developments.

Site history was obtained by reviewing historical aerial photographs taken in 1948, 1982, 1993, 2002, 2005, 2010, 2012 and 2018. Review of the 1948 aerial photograph indicates that the project site was occupied by a grove of trees. Commerce Boulevard Extension trended north-south along the eastern edge of the site. The surrounding land was occupied by groves of trees. A stream trending north-south was located west of the project site.

Review of the 1982 through 2010 aerial photographs indicate that the project site conditions appeared to be relatively similar to that noted in the 1948 aerial photograph.

Review of the 2012 and 2018 aerial photographs indicate that the project site and the land to the north and south had been cleared of the trees and were vacant.

Presently, the site predominately consists of vacant land. Several stockpiles of soil and rock are located within the site. The southeast corner of the site is utilized as a storage area with chain link fencing. The surface soils have a loose consistency and contain a moderate amount of grass and weeds. The site is bordered by vacant land with some wetlands to the north, Commerce Court and a grove of trees to the east, a warehouse and parking lot to the south, and a grove of trees, wetlands and river to the west. Commerce Court is a paved road and is elevated several feet above the project site. Buried utility lines may be located along Commerce Court. The site gently slopes from east to west.

GEOLOGIC SETTING

The subject site is located in the north-eastern portion of the San Francisco Bay Region, within the Coast Ranges Geomorphic Province of California. The Coast Range Geomorphic Province borders the Coast of California and generally consists, more or less, of a discontinuous series of northwesterly/southeasterly trending mountain ranges, ridges, and intervening valleys characterized by intense, complex folding and faulting. The ridges are most often comprised of granitic, metavolcanic, and metasedimentary rocks. Numerous northwest to southeast trending faults parallel the trend of the Coast Ranges.

The project site is located in a seismically active region, which is situated on a tectonic plate boundary marked by the San Andreas Fault System and several northwest trending active and potentially active faults. The site is in close proximity to several major faults, including the West Napa, Green Valley, Hayward-Rodgers Creek, Mount Diablo Thrust, Calaveras, and San Andreas faults located approximately 0.8 miles west, 8.0 miles east, 11 miles west, 24 miles south, 29 miles southeast, and 30 miles west of the site, respectively. Although the site is in close proximity to several faults, the site is not within a State of California Earthquake Fault Zone or Special Study Zone for faulting. The site is located approximately 3,200 feet west of the West Napa Fault and 600 feet from the California Earthquake fault zone for the West Napa Fault. The site is not located on a State of California Seismic Hazard Zone Map.

The probability of one or more earthquakes of magnitude 6.7 (Richter scale) or higher occurring in the San Francisco Bay Area within a 30-year period of time is evaluated by the U.S. Geological Survey (USGS) Working Group on California Earthquake Probabilities on a periodic basis. The result of the 2008 evaluation indicated a 63 percent likelihood that such an earthquake event will occur in the Bay Area between 2007 and 2036 (USGS 2008). The faults with the greater probability of a magnitude 6.7 or higher earthquake are the Hayward fault at 31 percent and the San Andreas fault at 21 percent.

Based on published geologic maps of the area the near-surface deposits in the vicinity of the subject site are indicated to be comprised of late Pleistocene to Holocene fan deposits of sand, gravel, silt and clay that are moderately to poorly sorted and moderately to poorly bedded. The site is located at an elevation of approximately 20 feet above sea level. Groundwater in the vicinity of the site is typically encountered at depths of approximately 11 to 25 feet.

FIELD AND LABORATORY INVESTIGATIONS

Subsurface soil conditions were explored by drilling 24 borings to depths ranging from approximately 10 to 50 feet below existing site grade, using a truck-mounted drill rig. In addition, 3 bulk subgrade samples were obtained from the site for laboratory R-value testing. The approximate boring and bulk sample locations are shown on the site plan. During drilling operations, penetration tests were performed at regular intervals to evaluate the soil consistency and to obtain information regarding the engineering properties of the subsoils. Soil samples were retained for laboratory testing. The soils encountered were continuously examined and visually classified in accordance with the Unified Soil Classification System. A more detailed description of the field investigation is presented in Appendix A.

Laboratory tests were performed on selected soil samples to evaluate their physical characteristics and engineering properties. The laboratory-testing program was formulated with emphasis on the evaluation of natural moisture, density, gradation, shear strength, consolidation potential, expansion potential, plasticity, R-value and moisture density relationships of the materials encountered. In addition, chemical tests were performed to evaluate the soil-cement reactivity. Details of the laboratory test program and results of the laboratory test are summarized in Appendix A. This information, along with the field observations, was used to prepare the final boring logs in Appendix A.

SOIL PROFILE AND SUBSURFACE CONDITIONS

Based on our findings, the subsurface conditions encountered appear typical of those found in the geologic region of the site. In general, the surface soils consisted of approximately 6 to 12 inches of soft silty clay or sandy clay, or very loose silty sand. These soils are disturbed, have low strength characteristics, and are highly compressible when saturated. Within portions of the site, approximately 6 to 12 inches of fill material was encountered. The fill material predominately consisted of sandy silt, silty sand, gravelly clayey sand, or gravelly sand. The thickness and extent of fill material was determined based on limited test borings and visual observation. Thicker fill may be present at the site. Limited testing was performed on the fill soils during the time of our field and laboratory investigations. The limited testing indicates that the fill soils ranged from loosely placed to compacted.

Beneath the loose surface soils and fill material, approximately 17½ feet of stiff to hard sandy clay, silty clay, and medium dense/very stiff clayey sand/sandy clay were encountered. Field and laboratory tests suggest that these soils are moderately strong and slightly to moderately compressible. The clayey soils had a moderate to high potential for expansion. Penetration resistance ranged from 12 to 63 blows per foot. Dry densities ranged from 89 to 122 pcf. Representative soil samples consolidated approximately 0 to 6 percent under a 2 ksf load when saturated. Representative soil samples had angles of internal friction between 12 and 18 degrees. A representative sample of the clayey soil had an expansion index of 89.

Below 18½ feet, layers of predominately stiff to very stiff sandy clay and silty clay, and medium dense silty sand/sandy silt were encountered. These soils contained varying amounts of gravel. Field and laboratory tests suggest that these soils are moderately strong and slightly compressible. Penetration resistance ranged from 13 to 29 blows per foot. Dry densities ranged from 90 to 111 pcf. These soils had similar strength characteristics than the upper soils and extended to the termination depth of our borings.

For additional information about the soils encountered, please refer to the logs of borings in Appendix A.

GROUNDWATER

Test boring locations were checked for the presence of groundwater during and immediately following the drilling operations. The historic high groundwater depth for the region was determined to be 10 feet below existing site grade, based on the State of California Department of Water Resources data from 2

wells within 1.5 miles of the site. Free groundwater was encountered between depths of 18½ and 22½ feet during our subsurface investigation.

It should be recognized that water table elevations may fluctuate with time, being dependent upon seasonal precipitation, irrigation, land use, and climatic conditions, as well as other factors. Therefore, water level observations at the time of the field investigation may vary from those encountered during the construction phase of the project. The evaluation of such factors is beyond the scope of this report.

SOIL LIQUEFACTION

Soil liquefaction is a state of soil particle suspension, caused by a complete loss of strength when the effective stress drops to zero. Liquefaction normally occurs in soils, such as sands, in which the strength is purely frictional. However, liquefaction has occurred in soils other than clean sands. Liquefaction usually occurs under vibratory conditions, such as those induced by seismic events.

To evaluate the liquefaction potential of the site, the following items were evaluated:

- 1) Soil type
- 2) Groundwater depth
- 3) Relative density
- 4) Initial confining pressure
- 5) Intensity and duration of groundshaking

The predominant soils within the project site consist of alternating layers of silty clays, sandy clays, clayey sands, and silty sand/sandy silt. Groundwater was encountered at depths as shallow as 18½ feet below existing site grade during our exploratory drilling. Information obtained from the Department of Water Resources indicated that water wells had historic groundwater elevations as shallow as 10 feet below existing site grade within the project site vicinity.

The potential for soil liquefaction during a seismic event was evaluated using the LIQUEFYPRO computer program (version 5.9d) developed by CivilTech Software. For the analysis, a maximum earthquake magnitude of 6.7 was used. A peak horizontal ground surface acceleration of 0.986g was considered conservative and appropriate for the liquefaction analysis. An estimated high groundwater depth of 10 feet was used for our analysis. The computer analysis indicates that soils above a depth of 10 feet are non-liquefiable due to the absence of groundwater. The soils below a depth of 10 feet have a slight to very low potential for liquefaction under seismic shaking due to predominately medium dense/stiff to very stiff sandy and clayey soils. The analysis also indicates that the total and differential seismic induced settlement is not anticipated to exceed 1 and ⅔ inch, respectively. Accordingly, measures to mitigate liquefaction potential are not necessary.

CONCLUSIONS AND RECOMMENDATIONS

Based on the findings of our field and laboratory investigations, along with previous geotechnical experience in the project area, the following is a summary of our evaluations, conclusions, and recommendations.

Administrative Summary

In brief, the subject site and soil conditions, with the exception of the loose surface soils, fill material, expansive nature of the clayey soils, moderately compressible upper native soils, and previous and existing developments, appear to be conducive to the development of the project. The surface soils and fill material have a loose consistency. These soils are disturbed, have low strength characteristics, and are highly compressible when saturated. Accordingly, it is recommended that the surface soils be recompacted. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation.

The site was previously utilized as agricultural land consisting of orchards. In addition, a fenced storage area is located in the southeast corner and several stockpiles of soil and rock are located within the site. Associated with these developments may be buried structures, such as utility lines and irrigation lines that extend into portions of the project site. Demolition activities should include proper removal of any buried structures. Any surface or buried structures, including utilities or loosely backfilled excavations, encountered during construction should be properly removed and the resulting excavations backfilled with Engineered Fill. It is suspected that demolition activities of the existing structures will disturb the upper soils. After demolition activities it is recommended that these disturbed soils be removed and/or recompacted. This compaction effort should stabilize the upper soils and locate any unsuitable or pliant areas not found during our field investigation.

The upper native soils at the site are moderately compressible and subject to excessive total and differential settlement. Therefore, it is recommended that following stripping and fill removal operations, the upper 24 inches of soil within the proposed building areas be excavated worked until uniform and free from large clods, moisture-conditioned to a minimum of 2 percent above optimum moisture content and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. In addition, in order to reduce the potential for differential settlement, it is recommended that the proposed structure foundations be supported by a minimum of 24 inches of Engineered Fill. Over-excavation should extend to a minimum of 5 feet beyond structural elements. The on-site, native soils and fill material will be suitable for reuse as Engineered Fill, provided they are cleansed of excessive organics, debris, and fragments larger than 4 inches in maximum dimension. Prior to backfilling, the bottom of the excavation should be proof rolled and observed by Krazan & Associates, Inc. to verify stability. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation. Fill material should be compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

The upper soils within the site are predominately silty clays, sandy clays, clayey sands, gravelly clayey sands, sandy silts, silty sands, and gravelly sands. The clayey soils appeared to have a moderate to high swell potential. The estimated swell pressures of the clayey soils may cause minor movement effecting

slabs and possible stucco or similar brittle exterior finishes. To reduce potential soil movement, it is recommended the upper 30 inches of soil within slab-on-grade and adjacent exterior flatwork areas consist of 24 inches of non-expansive Engineered Fill overlain by 6 inches of Class 2 aggregate base. During construction, it is recommended that additional tests should be performed on the on-site soils to verify their physical and index properties.

As an alternative to the use of non-expansive soils, the upper 30 inches of soil supporting the slab areas can consist of lime-treated clayey soils. The lime-treated soils should be recompact to a minimum of 90 percent of maximum density. Preliminary application rate of lime should be 5 percent by dry weight. The lime material should be calcium oxide, commonly known as quick-lime. The clayey soils should be above optimum moisture during the mixing operations.

Sidewalks not located adjacent to the buildings may be supported on 4 inches of Class 2 aggregate base compacted to a minimum of 95 percent of maximum density. Prior to placing the aggregate base, the subgrade soils should be excavated/scarified to a minimum depth of 12 inches, moisture-conditioned to a minimum of 3 percent above optimum moisture content and compacted to between 90 and 95 percent of maximum density based on ASTM Test Method D1557. As an alternative, the aggregate base can be placed over 12 inches of lime-treated subgrade. The Owner should be aware some movement of the sidewalks may occur which could result in cracking and vertical offsets.

Buried utility lines are located along Commerce Court on the east side of the site and may extend into the site. Demolition activities should include proper removal of any buried structures. Any buried structures encountered during construction should be properly removed and the resulting excavations cleaned to firm native ground and backfilled with Engineered Fill. Disturbed areas caused by demolition activities should be removed and/or recompact.

The site was previously occupied by a eucalyptus grove. Tree removal operations should include roots greater than 1 inch in diameter. The resulting excavations should be cleaned to firm native ground and backfilled with Engineered Fill compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Sandy soil conditions were encountered at the site. These cohesionless soils have a tendency to cave in trench wall excavations. Shoring or sloping back trench sidewalls may be required within these sandy soils.

A bioretention/detention pond is included in the project plans. The bioretention/detention pond should be located at least 50 feet from the structure. Alternatively, the pond can be lined.

After completion of the recommended site preparation, the site should be suitable for shallow footing support. The proposed structure footings may be designed utilizing an allowable bearing pressure of 3,000 psf for dead-plus-live loads. Footings should have a minimum embedment of 18 inches.

Groundwater Influence on Structures/Construction

During our field investigations, groundwater was encountered at depths of 18½ and 22½ feet below site grade. Therefore, dewatering and/or waterproofing may be required should structures or excavations extend below the groundwater table. If groundwater is encountered, our firm should be consulted prior to dewatering the site. Installation of a standpipe piezometer is suggested prior to construction should groundwater levels be a concern.

In addition to the groundwater level, if earthwork is performed during or soon after periods of precipitation, the subgrade soils may become saturated, “pump,” or not respond to densification techniques. Typical remedial measures include: discing and aerating the soil during dry weather; mixing the soil with dryer materials; removing and replacing the soil with an approved fill material; or mixing the soil with an approved lime or cement product. Our firm should be consulted prior to implementing remedial measures to observe the unstable subgrade conditions and provide appropriate recommendations.

Site Preparation

General site clearing should include removal of vegetation; concrete and metal debris; existing utilities; structures including foundations; basement walls and floors; existing stockpiled soil; trees and associated root systems; rubble; rubbish; and any loose and/or saturated materials. Site stripping should extend to a minimum depth of 2 to 4 inches, or until all organics in excess of 3 percent by volume are removed. Deeper stripping may be required in localized areas. These materials will not be suitable for use as Engineered Fill. However, stripped topsoil may be stockpiled and reused in landscape or non-structural areas.

The site was previously utilized as agricultural land consisting of orchards. In addition, a fenced storage area is located in the southeast corner and several stockpiles of soil and rock are located within the site. Associated with these developments are buried structures such, as utility lines that are located along the edges of the site and within the project site vicinity. Demolition activities should include proper removal of any buried structures. Any buried structures encountered during construction should be properly removed and/or relocated and the resulting excavations backfilled. Excavations, depressions, or soft and pliant areas extending below planned finished subgrade levels should be cleaned to firm, undisturbed soil and backfilled with Engineered Fill. In general, any septic tanks, debris pits, cesspools, or similar structures should be entirely removed. Concrete footings should be removed to an equivalent depth of at least 3 feet below proposed footing elevations or as recommended by the Soils Engineer. Any other buried structures should be removed in accordance with the recommendations of the Soils Engineer. The resulting excavations should be backfilled with Engineered Fill.

The site was previously occupied by a eucalyptus grove. Tree root removal operations should include roots greater than 1 inch in diameter. The resulting excavations should be backfilled with Engineered Fill compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

It is recommended that following stripping, tree removal operations and fill removal operations, the upper 24 inches of native soils within the proposed building areas be excavated, worked until uniform and free from large clods, moisture-conditioned to a minimum of 2 percent above optimum moisture content, and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. In addition, it is recommended that the proposed structure foundations be supported by a minimum of 24 inches of Engineered Fill. Over-excavation should extend to a minimum of 5 feet beyond structural elements. The on-site, native soil and fill material will be suitable for reuse as Engineered Fill, provided it is cleansed of excessive organics, debris, and fragments larger than 4 inches in maximum dimension. Prior to backfilling, the bottom of the excavation should be proof rolled and observed by Krazan & Associates, Inc. to verify stability. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation. Fill material should be compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Following stripping and fill removal operations, the exposed subgrade in exterior flatwork and pavement areas should be excavated/scarified to a minimum depth of 12 inches, worked until uniform and free from large clods, moisture-conditioned to a minimum of 2 percent above optimum moisture content, and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. Limits of recompaction should extend 3 feet beyond structural elements. This compaction effort should stabilize the surface soils and located any unsuitable or pliant areas not found during our field investigation.

It is recommended that the upper 30 inches of soil within proposed slab-on-grade and adjacent exterior flatwork areas consist of non-expansive or lime-treated Engineered Fill. The intent is to support slab-on-grade and exterior flatwork areas with 24 inches of non-expansive or lime-treated fill, overlain by 6 inches of compacted Class 2 aggregate base. Alternatively, the upper 30 inches may consist of lime-treated Engineered Fill. The fill placement serves two functions: 1) it provides a uniform amount of soil, which will more evenly distribute the soil pressures and 2) it reduces moisture content fluctuation in the clayey material beneath the building area. The non-expansive fill material should be a well-graded silty sand or sandy silt soil. A clean sand or very sandy soil is not acceptable for this purpose. A sandy soil will allow the surface water to drain into the expansive clayey soil below, which may result in soil swelling. Imported Fill should be approved by the Soils Engineer prior to placement. The fill should be placed as specified as Engineered Fill. In addition, it is recommended conventional foundations and slabs be nominally reinforced to reduce cracking and vertical offsets.

Sidewalks not located adjacent to the buildings may be supported on 4 inches of Class 2 aggregate base compacted to a minimum of 95 percent of maximum density. Prior to placing the aggregate base, the subgrade soils should be excavated/scarified to a minimum depth of 12 inches, moisture-conditioned to a minimum of 3 percent above optimum moisture content and compacted to between 90 and 95 percent of maximum density based on ASTM Test Method D1557. As an alternative, the aggregate base can be placed over 12 inches of lime-treated subgrade. The Owner should be aware some movement of the sidewalks may occur which could result in cracking and vertical offsets.

The upper soils, during wet winter months, become very moist due to the absorptive characteristics of the soil. Earthwork operations performed during winter months may encounter very moist unstable soils, which may require removal to grade a stable building foundation. Project site winterization consisting of placement of aggregate base and protecting exposed soils during the construction phase should be performed.

A bioretention/detention pond is included in the project plans. The bioretention/detention pond should be located at least 50 feet from the structure. Alternatively, the pond can be lined.

A representative of our firm should be present during all site clearing and grading operations to test and observe earthwork construction. This testing and observation is an integral part of our service as acceptance of earthwork construction is dependent upon compaction of the material and the stability of the material. The Soils Engineer may reject any material that does not meet compaction and stability requirements. Further recommendations of this report are predicated upon the assumption that earthwork construction will conform to recommendations set forth in this section and the Engineered Fill section.

Engineered Fill

The organic-free, on-site, upper native soils and fill material are predominately silty clays, sandy clays, clayey sands, gravelly clayey sands, sandy silts, silty sands, and gravelly sands. The clayey soils will not be suitable for re-use as non-expansive Engineered Fill. These clayey soils will be suitable for reuse for fill placement within the upper 30 inches of slab-on-grade and adjacent exterior flatwork areas, provided they are lime-treated. The preliminary application rate of lime should be 5 percent by dry weight. The lime material should be calcium oxide, commonly known as quick-lime. The clayey soils should be at or near optimum moisture-condition during mixing operations. Additional testing is recommended to determine the appropriate application rate of lime prior to placement. These clayey soils will be suitable for reuse as General Engineered Fill, provided they are cleansed of excessive organics, debris, and moisture-conditioned to at least 2 percent above optimum moisture. It is recommended that additional testing be performed on the on-site soils and fill material to evaluate the physical and index properties prior to reuse as Engineered Fill.

The preferred materials specified for Engineered Fill are suitable for most applications with the exception of exposure to erosion. Project site winterization and protection of exposed soils during the construction phase should be the sole responsibility of the Contractor, since he has complete control of the project site at that time.

Imported Fill material should be predominately non-expansive granular material with a plasticity index less than 10 and a UBC Expansion Index less than 15. Imported Fill should be free from rocks and lumps greater than 4 inches in diameter. All Imported Fill material should be submitted for approval to the Soils Engineer at least 48 hours prior to delivery to the site.

Fill soils should be placed in lifts approximately 6 inches thick, moisture-conditioned to a minimum of 2 percent above optimum moisture content, and compacted to achieve at least 90 percent of maximum density based on ASTM Test Method D1557. Additional lifts should not be placed if the previous lift did not meet the required dry density or if soil conditions are not stable.

Drainage and Landscaping

The ground surface should slope away from building pad and pavement areas toward appropriate drop inlets or other surface drainage devices. In accordance with Section 1804 of the 2019 California Building Code, it is recommended that the ground surface adjacent to foundations be sloped a minimum of 5 percent for a minimum distance of 10 feet away from structures, or to an approved alternative means of drainage conveyance. Swales used for conveyance of drainage and located within 10 feet of foundations should be sloped a minimum of 2 percent. Impervious surfaces, such as pavement and adjacent exterior concrete flatwork, within 10 feet of building foundations should be sloped a minimum of 1 percent away from the structure. Drainage gradients should be maintained to carry all surface water to collection facilities and off-site. These grades should be maintained for the life of the project.

Slots or weep holes should be placed in drop inlets or other surface drainage devices in pavement areas to allow free drainage of adjoining base course materials. Cutoff walls should be installed at pavement edges adjacent to vehicular traffic areas these walls should extend to a minimum depth of 12 inches below pavement subgrades to limit the amount of seepage water that can infiltrate the pavements. Where cutoff walls are undesirable subgrade drains can be constructed to transport excess water away from planters to drainage interceptors. If cutoff walls can be successfully used at the site, construction of subgrade drains is considered unnecessary.

Utility Trench Backfill

Utility trenches should be excavated according to accepted engineering practices following OSHA (Occupational Safety and Health Administration) standards by a Contractor experienced in such work. The responsibility for the safety of open trenches should be borne by the Contractor. Traffic and vibration adjacent to trench walls should be reduced; cyclic wetting and drying of excavation side slopes should be avoided. Depending upon the location and depth of some utility trenches, groundwater flow into open excavations could be experienced, especially during or shortly following periods of precipitation.

Sandy soil conditions were encountered at the site. These cohesionless soils have a tendency to cave in trench wall excavations. Shoring or sloping back trench sidewalls may be required within these sandy soils.

Utility trench backfill placed in or adjacent to buildings and exterior slabs should be compacted to at least 90 percent of maximum density based on ASTM Test Method D1557. The utility trench backfill placed in pavement areas should be compacted to at least 90 percent of maximum density based on ASTM Test Method D1557. Pipe bedding should be in accordance with pipe manufacturer's recommendations.

The Contractor is responsible for removing all water-sensitive soils from the trench regardless of the backfill location and compaction requirements. The Contractor should use appropriate equipment and methods to avoid damage to the utilities and/or structures during fill placement and compaction.

Foundations

The proposed structure may be supported on a shallow foundation system bearing on a minimum of 24 inches of Engineered Fill. Spread and continuous footings can be designed for the following maximum allowable soil bearing pressures:

Load	Allowable Loading
Dead Load Only	2,250 psf
Dead-Plus-Live Load	3,000 psf
Total Load, Including Wind or Seismic Loads	4,000 psf

The footings should have a minimum depth of 18 inches below pad subgrade (soil grade) or adjacent exterior grade, whichever is lower. Footings should have a minimum width of 12 inches, regardless of load. Ultimate design of foundations and reinforcement should be performed by the project Structural Engineer. A modulus of subgrade reaction of 35 pci can be used for the on-site soils.

The total soil movement is not expected to exceed 1 inch. Differential movement measured across a horizontal distance of 40 feet should be less than 1 inch. Most of the settlement is expected to occur during construction as the loads are applied. However, additional post-construction settlement may occur if the foundation soils are flooded or saturated.

The footing excavations should not be allowed to dry out any time prior to pouring concrete. It is recommended that footings be reinforced by at least one No. 4 reinforcing bar in both top and bottom.

Resistance to lateral footing displacement can be computed using an allowable friction factor of 0.3 acting between the base of foundations and the supporting subgrade. Lateral resistance for footings can alternatively be developed using an allowable equivalent fluid passive pressure of 250 pounds per cubic foot acting against the appropriate vertical footing faces. The frictional and passive resistance of the soil may be combined without reduction in determining the total lateral resistance. A $\frac{1}{3}$ increase in the above value may be used for short duration, wind, or seismic loads.

Floor Slabs and Exterior Flatwork

In areas that will utilize moisture-sensitive floor coverings, concrete slab-on-grade floors should be underlain by a water vapor retarder. The water vapor retarder should be installed in accordance with accepted engineering practice. The water vapor retarder should consist of a vapor retarder sheeting underlain by a minimum of 3 inches of compacted, clean, gravel of $\frac{3}{4}$ -inch maximum size. To aid in concrete curing an optional 2 to 4 inches of granular fill may be placed on top of the vapor retarder. The granular fill should consist of damp clean sand with at least 10 to 30 percent of the sand passing the 100

sieve. The sand should be free of clay, silt, or organic material. Rock dust which is manufactured sand from rock crushing operations is typically suitable for the granular fill. This granular fill material should be compacted. Floor slabs subject to forklift traffic should be underlain by a minimum of 2 inches of Class 2 aggregate base compacted to a minimum of 95 percent of maximum density based on ASTM Test Method D1557. Slabs can be designed utilizing a modulus of subgrade reaction of 100 pci.

The floor slab should be a minimum of 6 inches thick and reinforced at a minimum with No. 4 reinforcement bars at 24 inches on-center each way within the middle one-third. Thicker floor slabs with increased concrete strength and reinforcement should be designed wherever large vehicular loads, heavy concentrated loads, heavy equipment, or machinery is anticipated.

The exterior floors should be poured separately in order to act independently of the walls and foundation system. All fills required to bring the building pads to grade should be Engineered Fills.

Moisture within the structure may be derived from water vapors, which were transformed from the moisture within the soils. This moisture vapor can travel through the vapor membrane and penetrate the slab-on-grade. This moisture vapor penetration can affect floor coverings and produce mold and mildew in the structure. To reduce moisture vapor intrusion, it is recommended that a vapor retarder be installed. It is recommended that the utility trenches within the structure be compacted, as specified in our report, to reduce the transmission of moisture through the utility trench backfill. Special attention to the immediate drainage and irrigation around the building is recommended. Positive drainage should be established away from the structure and should be maintained throughout the life of the structure. Ponding of water should not be allowed adjacent to the structure. Over-irrigation within landscaped areas adjacent to the structure should not be performed. In addition, ventilation of the structure (i.e. ventilation fans) is recommended to reduce the accumulation of interior moisture.

Lateral Earth Pressures and Retaining Walls

Walls retaining horizontal backfill and capable of deflecting a minimum of 0.1 percent of its height at the top may be designed using an equivalent fluid active pressure of 50 pounds per square foot per foot of depth. Walls that are incapable of this deflection or walls that are fully constrained against deflection may be designed for an equivalent fluid at-rest pressure of 70 pounds per square foot per foot per depth. Expansive soils should not be used for backfill against walls. The wedge of non-expansive backfill material should extend from the bottom of each retaining wall outward and upward at a slope of 2:1 (horizontal to vertical) or flatter. The stated lateral earth pressures do not include the effects of hydrostatic water pressures generated by infiltrating surface water that may accumulate behind the retaining walls; or loads imposed by construction equipment, foundations, or roadways.

Retaining and/or below grade walls should be drained with either perforated pipe encased in free-draining gravel or a prefabricated drainage system. The gravel zone should have a minimum width of 12 inches wide and should extend upward to within 12 inches of the top of the wall. The upper 12 inches of backfill should consist of native soils, concrete, asphaltic concrete or other suitable backfill to minimize surface drainage into the wall drain system. The aggregate should conform to Class 2 permeable materials graded in accordance with the CalTrans Standard Specifications (2018). Prefabricated

drainage systems, such as Miradrain®, Enkadrain®, or an equivalent substitute, are acceptable alternatives in lieu of gravel provided they are installed in accordance with the manufacturer’s recommendations. If a prefabricated drainage system is proposed, our firm should review the system for final acceptance prior to installation.

Drainage pipes should be placed with perforations down and should discharge in a non-erosive manner away from foundations and other improvements. The pipes should be placed no higher than 6 inches above the heel of the wall in the center line of the drainage blanket and should have a minimum diameter of 4 inches. Collector pipes may be either slotted or perforated. Slots should be no wider than 1/8 inch, while perforations should be no more than 1/4 inch in diameter. If retaining walls are less than 6 feet in height, the perforated pipe may be omitted in lieu of weep holes on 4 feet maximum spacing. The weep holes should consist of 4-inch diameter holes (concrete walls) or unmortared head joints (masonry walls) and not be higher than 18 inches above the lowest adjacent grade. Two 8-inch square overlapping patches of geotextile fabric (conforming to the CalTrans Standard Specifications for "edge drains") should be affixed to the rear wall opening of each weep hole to retard soil piping.

During grading and backfilling operations adjacent to any walls, heavy equipment should not be allowed to operate within a lateral distance of 5 feet from the wall or within a lateral distance equal to the wall height, whichever is greater, to avoid developing excessive lateral pressures. Within this zone, only hand operated equipment (“whackers,” vibratory plates, or pneumatic compactors) should be used to compact the backfill soils.

R-Value Test Results and Pavement Design

Three subgrade soil samples were obtained from the project site for R-Value testing at the locations shown on the attached site plan. The samples were tested in accordance with the State of California Materials Manual Test Designation 301. The results of the tests are as follows:

Sample	Depth	Description	R-Value at Equilibrium
1	12-24"	Silty Clay (CL)	Less than 5
2	12-24"	Silty Clay (CL)	Less than 5
3	12-24"	Silty Clay (CL)	Less than 5

The test results are low and indicate poor subgrade support characteristics under dynamic traffic loads. The following table shows the recommended pavement sections for various traffic indices.

Traffic Index	Asphaltic Concrete	Class II Aggregate Base*	Class III Aggregate Subbase	Compacted Subgrade**
4.0	2.0"	8.5"	--	12.0"
4.0	2.0"	4.5"	4.5"	12.0"
4.5	2.5"	9.0"	--	12.0"
4.5	2.5"	4.0"	5.5"	12.0"

5.0	2.5"	11.0"	--	12.0"
5.0	2.5"	5.0"	6.5"	12.0"
5.5	3.0"	11.5"	--	12.0"
5.5	3.0"	5.0"	7.0"	12.0"
6.0	3.0"	13.5"	--	12.0"
6.0	3.0"	6.5"	8.0"	12.0"
6.5	3.5"	14.0"	--	12.0"
6.5	3.5"	6.0"	9.0"	12.0"
7.0	4.0"	15.5"	--	12.0"
7.0	4.0"	6.5"	10.0"	12.0"
7.5	4.0"	17.0"	--	12.0"
7.5	4.0"	7.5"	10.5"	12.0"

* 95% compaction based on ASTM Test Method D1557 or CAL 216
** 90% compaction based on ASTM Test Method D1557 or CAL 216

The following table shows the recommended pavement sections for various traffic indices based on the upper 12 inches of subgrade soil being lime-treated with 5 percent Calcium Quicklime.

Traffic Index	Asphaltic Concrete	Class II Aggregate Base*	Lime-Treated Compacted Subgrade**
4.0	2.0"	4.0"	12.0"
4.5	2.5"	4.0"	12.0"
5.0	2.5"	4.0"	12.0"
5.5	3.0"	4.0"	12.0"
6.0	3.0"	5.0"	12.0"
6.5	3.5"	5.0"	12.0"
7.0	4.0"	6.0"	12.0"
7.5	4.0"	6.0"	12.0"

* 95% compaction based on ASTM Test Method D1557 or CAL 216
** 90% compaction based on ASTM Test Method D1557 or CAL 216

If traffic indices are not available, an estimated (typical value) index of 4.5 may be used for light automobile traffic, and an index of 7.0 may be used for light truck traffic.

The following recommendations are for light-duty and heavy-duty Portland Cement Concrete Pavement Sections based on the design procedures developed by the Portland Cement Association. The PCC Pavement should be reinforced with a minimum of No. 4 bars placed at a minimum of 24 inches on center in each direction.

**PORTLAND CEMENT PAVEMENT
LIGHT DUTY**

Traffic Index	Portland Cement Concrete***	Class II Aggregate Base*	Compacted Subgrade**
4.5	6.0"	5.0"	12.0"
4.5	6.0"	2.0"	12.0"****

HEAVY DUTY

Traffic Index	Portland Cement Concrete***	Class II Aggregate Base*	Compacted Subgrade**
7.0	7.0"	6.0"	12.0"
7.0	6.5"	1.5"	12.0"****

* 95% compaction based on ASTM Test Method D1557 or CAL 216

** 90% compaction based on ASTM Test Method D1557 or CAL 216

***Minimum compressive strength of 4000 psi

****Lime-Treated subgrade compacted to a minimum of 90% of maximum density based on ASTM Test Method D1557

It is recommended that any uncertified fill material encountered within pavement areas be removed and/or recompacted. The fill material should be moisture-conditioned to near optimum moisture and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. As an alternative, the Owner may elect not to recompact the existing fill within paved areas. However, the Owner should be aware that the paved areas may settle which may require annual maintenance. At a minimum, it is recommended that the upper 12 inches of subgrade soil be moisture-conditioned as necessary and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Seismic Parameters – 2019 California Building Code

The Site Class per Section 1613 of the 2019 California Building Code (2019 CBC) and ASCE 7-16, Chapter 20 is based upon the site soil conditions. It is our opinion that a Site Class D is most consistent with the subject site soil conditions. For seismic design of the structures based on the seismic provisions of the 2019 CBC, we recommend the following parameters:

Seismic Item	Value	CBC Reference
Site Class	D	Section 1613.2.2
Site Coefficient F_a	1.000	Table 1613.2.3 (1)
S_s	2.162	Section 1613.2.1
S_{MS}	2.162	Section 1613.2.3
S_{DS}	1.442	Section 1613.2.4
Site Coefficient F_v	1.700	Table 1613.2.3 (2)
S_1	0.782	Section 1613.2.1
S_{M1}	1.329	Section 1613.2.3
S_{D1}	0.886	Section 1613.2.4
T_s	0.615	Section 1613.2

* Based on Equivalent Lateral Force (ELF) Design Procedure being used.

Soil Cement Reactivity

Excessive sulfate in either the soil or native water may result in an adverse reaction between the cement in concrete (or stucco) and the soil. HUD/FHA and CBC have developed criteria for evaluation of sulfate levels and how they relate to cement reactivity with soil and/or water.

Soil samples were obtained from the site and tested in accordance with State of California Materials Manual Test Designation 417. The sulfate concentrations detected from these soil samples were greater than 0.02 percent and are above the maximum allowable values established by HUD/FHA and CBC. Therefore, it is recommended that a Type II cement be used within the concrete to compensate for sulfate reactivity with the cement.

Chemical tests were performed on a near-surface soil sample. The test results indicate that the soils are moderately corrosive to buried metal objects. Therefore, buried metal should be protected using either non-corrosive backfill, protective coatings, wrappings, sacrificial anodes, or a combination of these methods in accordance with the manufacturer's recommendations.

Compacted Material Acceptance

Compaction specifications are not the only criteria for acceptance of the site grading or other such activities. However, the compaction test is the most universally recognized test method for assessing the performance of the Grading Contractor. The numerical test results from the compaction test cannot be used to predict the engineering performance of the compacted material. Therefore, the acceptance of compacted materials will also be dependent on the stability of that material. The Soils Engineer has the option of rejecting any compacted material regardless of the degree of compaction if that material is considered to be unstable or if future instability is suspected. A specific example of rejection of fill material passing the required percent compaction is a fill which has been compacted with an in-situ moisture content significantly less than optimum moisture. This type of dry fill (brittle fill) is susceptible to future settlement if it becomes saturated or flooded.

Testing and Inspection

A representative of Krazan & Associates, Inc. should be present at the site during the earthwork activities to confirm that actual subsurface conditions are consistent with the exploratory fieldwork. This activity is an integral part of our service, as acceptance of earthwork construction is dependent upon compaction testing and stability of the material. This representative can also verify that the intent of these recommendations is incorporated into the project design and construction. Krazan & Associates, Inc. will not be responsible for grades or staking, since this is the responsibility of the Prime Contractor.

LIMITATIONS

Soils Engineering is one of the newest divisions of Civil Engineering. This branch of Civil Engineering is constantly improving as new technologies and understanding of earth sciences advance. Although your site was analyzed using the most appropriate and most current techniques and methods, undoubtedly there will be substantial future improvements in this branch of engineering. In addition to

advancements in the field of Soils Engineering, physical changes in the site, either due to excavation or fill placement, new agency regulations, or possible changes in the proposed structure after the soils report is completed may require the soils report to be professionally reviewed. In light of this, the Owner should be aware that there is a practical limit to the usefulness of this report without critical review. Although the time limit for this review is strictly arbitrary, it is suggested that 2 years be considered a reasonable time for the usefulness of this report.

Foundation and earthwork construction is characterized by the presence of a calculated risk that soil and groundwater conditions have been fully revealed by the original foundation investigation. This risk is derived from the practical necessity of basing interpretations and design conclusions on limited sampling of the earth. The recommendations made in this report are based on the assumption that soil conditions do not vary significantly from those disclosed during our field investigation. If any variations or undesirable conditions are encountered during construction, the Soils Engineer should be notified so that supplemental recommendations may be made.

The conclusions of this report are based on the information provided regarding the proposed construction. If the proposed construction is relocated or redesigned, the conclusions in this report may not be valid. The Soils Engineer should be notified of any changes so the recommendations may be reviewed and re-evaluated.

This report is a Geotechnical Engineering Investigation with the purpose of evaluating the soil conditions in terms of foundation design. The scope of our services did not include any Environmental Site Assessment for the presence or absence of hazardous and/or toxic materials in the soil, groundwater, or atmosphere; or the presence of wetlands. Any statements, or absence of statements, in this report or on any boring log regarding odors, unusual or suspicious items, or conditions observed, are strictly for descriptive purposes and are not intended to convey engineering judgment regarding potential hazardous and/or toxic assessment.

The geotechnical engineering information presented herein is based upon professional interpretation utilizing standard engineering practices and a degree of conservatism deemed proper for this project. It is not warranted that such information and interpretation cannot be superseded by future geotechnical engineering developments. We emphasize that this report is valid for the project outlined above and should not be used for any other sites.

If you have any questions, or if we may be of further assistance, please do not hesitate to contact our office at (916) 564-2200.




Respectfully submitted,
KRAZAN & ASSOCIATES, INC.

Madison K. Weber
Project Engineer
RCE No. 81935




David R. Jarosz, II
Managing Engineer
RGE No. 2698/RCE No. 60185

MKW/DRJ:ht



- APPROXIMATE BORING LOCATION
- ▲ APPROXIMATE R-VALUE LOCATION



SITE MAP Commerce 220 Distribution Center 1055 Commerce Court American Canyon, California	Scale:	NTS	Date:	January 2021
	Drawn by:	HT	Approved by:	DJ
	Project No.	032-20054	Figure No.	1



APPENDIX A

FIELD AND LABORATORY INVESTIGATIONS

Field Investigation

The field investigation consisted of a surface reconnaissance and a subsurface exploratory program. Twenty-four 4½-inch to 6½-inch exploratory borings were advanced. The boring locations are shown on the site plan.

The soils encountered were logged in the field during the exploration and, with supplementary laboratory test data, are described in accordance with the Unified Soil Classification System.

Modified standard penetration tests and standard penetration tests were performed at selected depths. These tests represent the resistance to driving a 2½-inch and 1½-inch diameter split barrel sampler, respectively. The driving energy was provided by a hammer weighing 140 pounds falling 30 inches. Relatively undisturbed soil samples were obtained while performing this test. Bag samples of the disturbed soil were obtained from the auger cuttings. The modified standard penetration tests are identified in the sample type on the boring logs with a full shaded in block. The standard penetration tests are identified in the sample type on the boring logs with half of the block shaded. All samples were returned to our Clovis laboratory for evaluation.

Laboratory Investigation

The laboratory investigation was programmed to determine the physical and mechanical properties of the foundation soil underlying the site. Test results were used as criteria for determining the engineering suitability of the surface and subsurface materials encountered.

In-situ moisture content, dry density, consolidation, direct shear, and sieve analysis tests were completed for the undisturbed samples representative of the subsurface material. Atterberg limits, expansion index and R-value tests were completed for select bag samples obtained from auger cuttings. These tests, supplemented by visual observation, comprised the basis for our evaluation of the site material.


The logs of the exploratory borings and laboratory determinations are presented in this Appendix.

UNIFIED SOIL CLASSIFICATION SYSTEM

UNIFIED SOIL CLASSIFICATION AND SYMBOL CHART		
COARSE-GRAINED SOILS (more than 50% of material is larger than No. 200 sieve size.)		
GRAVELS More than 50% of coarse fraction larger than No. 4 sieve size	Clean Gravels (Less than 5% fines)	
	GW	Well-graded gravels, gravel-sand mixtures, little or no fines
	GP	Poorly-graded gravels, gravel-sand mixtures, little or no fines
	Gravels with fines (More than 12% fines)	
	GM	Silty gravels, gravel-sand-silt mixtures
	GC	Clayey gravels, gravel-sand-clay mixtures
SANDS 50% or more of coarse fraction smaller than No. 4 sieve size	Clean Sands (Less than 5% fines)	
	SW	Well-graded sands, gravelly sands, little or no fines
	SP	Poorly graded sands, gravelly sands, little or no fines
	Sands with fines (More than 12% fines)	
	SM	Silty sands, sand-silt mixtures
SC	Clayey sands, sand-clay mixtures	
FINE-GRAINED SOILS (50% or more of material is smaller than No. 200 sieve size.)		
SILTS AND CLAYS Liquid limit less than 50%	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity
	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
	OL	Organic silts and organic silty clays of low plasticity
SILTS AND CLAYS Liquid limit 50% or greater	MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
	CH	Inorganic clays of high plasticity, fat clays
	OH	Organic clays of medium to high plasticity, organic silts
HIGHLY ORGANIC SOILS	PT	Peat and other highly organic soils

CONSISTENCY CLASSIFICATION	
Description	Blows per Foot
<i>Granular Soils</i>	
Very Loose	< 5
Loose	5 – 15
Medium Dense	16 – 40
Dense	41 – 65
Very Dense	> 65
<i>Cohesive Soils</i>	
Very Soft	< 3
Soft	3 – 5
Firm	6 – 10
Stiff	11 – 20
Very Stiff	21 – 40
Hard	> 40

GRAIN SIZE CLASSIFICATION		
Grain Type	Standard Sieve Size	Grain Size in Millimeters
Boulders	Above 12 inches	Above 305
Cobbles	12 to 13 inches	305 to 76.2
Gravel	3 inches to No. 4	76.2 to 4.76
	Coarse-grained 3 to ¾ inches	76.2 to 19.1
	Fine-grained ¾ inches to No. 4	19.1 to 4.76
Sand	No. 4 to No. 200	4.76 to 0.074
	Coarse-grained No. 4 to No. 10	4.76 to 2.00
	Medium-grained No. 10 to No. 40	2.00 to 0.042
	Fine-grained No. 40 to No. 200	0.042 to 0.074
Silt and Clay	Below No. 200	Below 0.074



Log of Boring B1

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-1

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: 22½ Feet

At Completion: 22½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)					
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30
0		Ground Surface											
0 - 2		SANDY SILT (ML) FILL, fine- to medium-grained; grayish-brown, moist, drills easily											
2 - 5		SILTY CLAY (CL) Very stiff; light brown, moist, drills firmly Hard below 2 feet	119.4	13.9		43							
5 - 10		Very stiff and drills easily below 5 feet											
6			111.6	20.7		24							
10 - 16		SANDY CLAY (CL) Very stiff, fine-grained; light brown, moist, drills firmly											
10			116.0	14.6		37							
16			100.2	24.1		34							
20		With trace GRAVEL below 20 feet											

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 1 of 2

Log of Boring B1

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-1


Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: 22½ Feet

At Completion: 22½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		10	20	30	40
22		 Saturated below 22½ feet	100.5	26.6		28	▲			■	
24											
26		End of Borehole									
28											
30											
32											
34											
36											
38											
40											

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 2 of 2

Log of Boring B2

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-2

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
0		Ground Surface												
0		SANDY CLAY (CL) Soft, fine-grained; brown, moist, drills easily												
2		Very stiff below 12 inches Hard and drills firmly below 2 feet	116.5	14.3		40						■		
4		Light brown below 4 feet												
6			112.8	17.9		42						■		
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B3

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-3

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)							
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30	40	
0		Ground Surface													
0 - 2		SANDY CLAY (CL) Soft, fine-grained; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet	111.0	16.8		26									
2 - 4		SILTY CLAY (CL) Very stiff; light grayish-brown, moist, drills easily	106.8	21.7		30									
4 - 10.5		SANDY CLAY (CL) Very stiff, fine- to medium-grained; light brown, moist, drills easily Drills firmly below 10½ feet	118.5	11.7		34									
10.5 - 16		End of Borehole													
16 - 20															

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B4

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-4

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
0		Ground Surface												
0		SILTY CLAY (CL) Soft; brown, moist, drills easily Firm below 12 inches Stiff below 2 feet												
2			104.8	15.8		18						■		
4		Very stiff and light gray below 3½ feet												
6			100.9	24.1		26						■		
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B5

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-5

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)					
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30
Ground Surface													
0	[Hatched Pattern]	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet											
2		SANDY CLAY (CL) Very stiff, fine-grained; light gray, moist, drills firmly	122.3	13.9		34					■		
4		SILTY CLAY (CL) Very stiff; light brown, moist, drills easily	112.3	16.7		31					■		
6													
10				111.9	20.2		37					■	
12	[Hatched Pattern]	SAND (SP) Medium dense, fine- to medium-grained; tan, moist, drills easily											
14		SILTY CLAY (CL) Very stiff; light brown, moist, drills easily											
16			105.3	23.2		33					■		
18													
20													

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 20 Feet

Sheet: 1 of 1

Log of Boring B6

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-6

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)						
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30	40
0		Ground Surface												
0		SANDY CLAY (CL) Soft, fine-grained; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet												
2			119.2	7.5		32					■			
4		SILTY CLAY (CL) Hard; light brown, moist, drills firmly												
6			118.2	12.9		47					■			
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B7

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-7

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)					
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30
Ground Surface													
0		SANDY CLAY (CL) Soft, fine-grained; brown, moist, drills easily											
2		Stiff below 12 inches											
		SILTY CLAY (CL) Very stiff; light brown, moist, drills firmly	107.2	18.8		32							
4													
6			119.9	14.1		38							
8													
10			110.6	19.3		36							
12		SAND (SP) Medium dense, fine- to medium-grained; light brown, moist, drills firmly											
14		SILTY CLAY (CL) Very stiff; light brown, moist, drills firmly											
16			96.0	28.9		31							
18													
20													

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 1 of 2

Log of Boring B7

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-7

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)						
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30	40
			90.0	30.0		29	▲					■		
22														
24														
26		End of Borehole												
28														
30														
32														
34														
36														
38														
40														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 2 of 2

Log of Boring B8

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-8

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
Ground Surface														
0	█	SANDY CLAY (CL) Soft, fine-grained; brown, moist, drills easily												
2		Stiff below 12 inches Very stiff below 2 feet	121.7	8.7		41								
4	█	SILTY CLAY (CL) Hard; light brown, moist, drills firmly												
6			121.6	14.1		55								
8														
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B9

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-9

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
Ground Surface														
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff and light brown below 2 feet												
2			101.2	19.3		25								
4														
6			110.2	16.5		51								
8														
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B10

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-10

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: 22½ Feet

At Completion: 22½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)							
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content							
							20	40	60	10	20	30	40				
Ground Surface																	
0	SILTY CLAY (CL)	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet Hard and drills firmly below 3½ feet															
2			106.9	21.3		22											
4																	
6			120.0	13.8		42											
10			CLAYEY SAND/SANDY CLAY (SC/CL)	CLAYEY SAND/SANDY CLAY (SC/CL) Medium dense, fine- to medium-grained; brown, moist, drills easily	107.7	15.2		35									
12																	
14																	
16	SANDY CLAY (CL)	SANDY CLAY (CL) Stiff, fine-grained; light brown, moist, drills easily	101.4	23.5		12											
18																	
20	SILTY SAND/SANDY SILT (SM/ML)	SILTY SAND/SANDY SILT (SM/ML) Medium dense, fine- to medium-grained; light brown, moist, drills firmly															

Drill Method: Hollow Stem

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 6½ Inches

Driller: Brent Snyder

Elevation: 50 Feet

Sheet: 1 of 3

Log of Boring B10

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-10

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: 22½ Feet

At Completion: 22½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		
22	▽	SILTY CLAY (CL) Very stiff; light brown, moist, drills easily Saturated below 22½ feet	110.7	17.5	▲	23	20 40 60	10 20 30 40
26			101.9	22.1	▲	16		10 20 30 40
30		SILTY CLAY (CH) Stiff; brown, saturated, drills easily	94.7	26.1	▲	13		10 20 30 40
36		Very stiff below 35 feet	106.1	19.9	▲	17		10 20 30 40
40		Stiff below 40 feet			▲			10 20 30 40

Drill Method: Hollow Stem

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 6½ Inches

Driller: Brent Snyder

Elevation: 50 Feet

Sheet: 2 of 3

Log of Boring B10

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-10

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: 22½ Feet

At Completion: 22½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
42		Very stiff below 45 feet	99.6	22.5	▲	14					■		
44													
46			100.9	22.1	▲	22					■		
48													
50		End of Borehole											
52													
54													
56													
58													
60													

Drill Method: Hollow Stem

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 6½ Inches

Driller: Brent Snyder

Elevation: 50 Feet

Sheet: 3 of 3

Log of Boring B11

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-11

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
Ground Surface														
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet												
2				14.6			29					■		
4		Hard, light brown and drills firmly below 4 feet												
6			122.4	13.5			46					■		
8														
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-8-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B12

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-12

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)					
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30
Ground Surface													
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet											
2			88.8	29.5		28							
4		Hard, light brown and drills firmly below 4 feet											
6			115.0	14.0		45							
8													
10		Very stiff below 10 feet											
12													
14													
16		End of Borehole											
18													
20													

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B13

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-13

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
Ground Surface														
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet												
2			103.4	22.5		26							■	
4	█	Light brown below 4 feet												
6			118.3	15.5		34							■	
8	█													
10														
End of Borehole														
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B14

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-14

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)					
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30
0		Ground Surface											
0		SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet											
2			95.8	18.6		22							
4		Hard and light brown below 3½ feet											
6			116.7	14.3		46							
8													
10		Very stiff below 8½ feet											
10			112.2	18.3		33							
12													
14													
16			108.2	20.3		34							
18													
20													

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 20 Feet

Sheet: 1 of 1

Log of Boring B15

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-15

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
Ground Surface													
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet											
2			97.1	12.8		29				■			
4		Hard and light brown below 3½ feet											
6			121.1	16.4		48				■			
10		End of Borehole											
12													
14													
16													
18													
20													

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B16

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-16

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)						
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.										
							20	40	60	10	20	30	40			
Ground Surface																
0	█	SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet Light brown below 2½ feet														
2			96.7	17.2		24							■			
4																
6			116.7	18.0		39								■		
8																
10			103.1	24.7		38							■			
12																
14																
16		End of Borehole														
18																
20																

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B17

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-17

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
Ground Surface														
0		SILTY SAND (SM) Very loose, fine- to medium-grained; brown, moist, drills easily												
2		SILTY CLAY (CL) Very stiff; brown, moist, drills easily Light brown below 2½ feet	97.7	22.2		24								■
4		Hard below 5 feet												
6			112.4	17.0		48								■
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B18

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-18


Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: 18½ Feet

At Completion: 18½ Feet



Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 1 of 2

Log of Boring B18

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-18

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: 18½ Feet

At Completion: 18½ Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
22			106.5	19.0		19	▲				■		
24													
26		End of Borehole											
28													
30													
32													
34													
36													
38													
40													

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 2 of 2

Log of Boring B19

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-19

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
Ground Surface													
0		SILTY SAND (SM) Very loose, fine- to medium-grained; brown, moist, drills easily											
2		SILTY CLAY (CL) Stiff; brown, moist, drills easily Very stiff, light brown and drills firmly below 2½ feet	106.3	9.0		24				■			
4													
6			119.5	14.8		39				■			
8													
10		End of Borehole											
12													
14													
16													
18													
20													

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B20

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-20

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)						
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		20	40	60	10	20	30	40
0		Ground Surface												
0		SILTY SAND (SM) FILL, fine- to medium-grained; brown, moist, drills easily												
2		SILTY CLAY (CL) Stiff; brown, moist, drills easily Very stiff below 2 feet Light brown below 2½ feet	98.9	14.4		26								
4														
6		Hard below 5 feet	116.4	15.2		40								
8														
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B21

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-21

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: 22 Feet

At Completion: 22 Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
0		Ground Surface												
0		SILTY CLAY (CL) Soft; brown, moist, drills easily Stiff below 12 inches Very stiff below 2 feet												
2			102.7	24.0		30								
4		Light brown below 3½ feet												
6			119.8	13.7		29								
8														
10			114.5	17.1		28								
12														
14		Light grayish-brown below 14 feet												
16			103.8	24.8		25								
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 1 of 2

Log of Boring B21

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-21

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: 22 Feet

At Completion: 22 Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
22		Saturated below 22 feet	103.9	23.7		24	▲				■			
24														
26		End of Borehole												
28														
30														
32														
34														
36														
38														
40														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 25 Feet

Sheet: 2 of 2

Log of Boring B22

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-22

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
Ground Surface														
0		SILTY SAND (SM) FILL, fine- to medium-grained; brown, moist, drills easily												
2		SILTY CLAY (CL) Stiff; brown, moist, drills easily Very stiff below 1½ feet Light brown below 3½ feet	104.4	21.7		28								
4														
6			109.5	15.5		25								
8														
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B23

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-23

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water >

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	Penetration Test			Water Content (%)				
							20	40	60	10	20	30	40	
0		Ground Surface												
0		GRAVELLY CLAYEY SAND (SC) FILL, fine- to medium-grained; brown, moist, drills easily												
2		SILTY CLAY (CL) Very stiff; brown, moist, drills easily	101.2	21.7		34							20	
4		Hard, light brown and drills firmly below 4 feet												
6			107.0	21.4		42							20	
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches

Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B24

Project: Commerce 220 Distribution Center

Project No: 032-20054

Client: Industrial & Commercial Contractors, L.P.

Figure No.: A-24

Location: 1055 Commerce Court, American Canyon, California

Logged By: R. Alexander

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
Ground Surface														
0		GRAVELLY SAND (SP) FILL, fine- to medium-grained; light brown, moist, drills easily												
2		SILTY CLAY (CL) Very stiff; brown, moist, drills easily	108.7	13.3		23								
4		Hard and light brown below 3½ feet												
6			117.9	16.2		63								
10		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 12-9-20

Drill Rig: CME 45B

Krazan and Associates

Hole Size: 4½ Inches


Driller: Brent Snyder

Elevation: 10 Feet

Sheet: 1 of 1


Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
032-20054	B1 @ 5-6'	12/28/2020	CL




Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
032-20054	B4 @ 2-3'	12/28/2020	CL




Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
032-20054	B10 @ 2-3'	12/28/2020	CL




Shear Strength Diagram (Direct Shear)
ASTM D - 3080 / AASHTO T - 236

Project Number	Boring No. & Depth	Soil Type	Date
032-20054	B4 @ 5-6'	CL	12/28/2020




Shear Strength Diagram (Direct Shear)
ASTM D - 3080 / AASHTO T - 236

Project Number	Boring No. & Depth	Soil Type	Date
032-20054	B9 @ 2-3'	CL	12/28/2020



Grain Size Analysis




Gravel		Sand			Silt or Clay
		Fine	Coarse		

(Unified Soils Classification)

Project Name: Commerce 220 Distribution Center
 Project Number: 032-20054
 Soil Classification: CL
 Sample Number: B4 @ 2-3'

Grain Size Analysis



Gravel		Sand		Silt or Clay
Coarse	Fine	Coarse	Medium	Fine

(Unified Soils Classification)

Project Name
 Project Number
 Soil Classification
 Sample Number

Commerce 220 Distribution Center
 032-20054
 CL
 B10 @ 2-3'

Expansion Index Test

ASTM D - 4829

Project Number : 042-20054
 Project Name : Commerce 220 Distribution Center
 Date : 12/28/2020
 Sample location/ Depth : 2-3'
 Sample Number : X1
 Soil Classification : CL

Trial #	1	2	3
Weight of Soil & Mold, gms	751.3		
Weight of Mold, gms	367.8		
Weight of Soil, gms	383.5		
Wet Density, Lbs/cu.ft.	115.7		
Weight of Moisture Sample (Wet), gms	200.0		
Weight of Moisture Sample (Dry), gms	178.5		
Moisture Content, %	12.0		
Dry Density, Lbs/cu.ft.	103.2		
Specific Gravity of Soil	2.7		
Degree of Saturation, %	51.4		

Time	Initial	30 min	1 hr	6hrs	12 hrs	24 hrs
Dial Reading	0	--	--	--	--	0.0891

Expansion Index_{measured} = 89.1

Expansion Index = 89

Exp. Index	Potential Exp.
0 - 20	Very Low
21 - 50	Low
51 - 90	Medium
91 - 130	High
>130	Very High

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 5-6'
 Sample Description: CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	33.04	27.66		27.62	28.90	
Weight of Dry Soil & Tare (g)	30.62	25.99		24.37	26.22	
Weight of Tare (g)	13.74	14.37		13.88	17.45	
Weight of water (g)	2.42	1.66		3.25	2.68	
Weight of Dry Soil (g)	16.88	11.62		10.49	8.77	
Water Content (% of dry wt.)	14.3%	14.3%		31.0%	30.6%	
Number of Blows				25	25	

Plastic Limit : 14



Liquid Limit : 31

Plasticity Index : 17

Unified Soil Classification : CL

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204



Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 10-11'
 Sample Description: SC-CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	31.02	25.22		26.73	26.28	
Weight of Dry Soil & Tare (g)	28.48	23.51		23.31	23.09	
Weight of Tare (g)	13.28	13.12		13.23	13.79	
Weight of water (g)	2.54	1.71		3.42	3.20	
Weight of Dry Soil (g)	15.19	10.39		10.08	9.29	
Water Content (% of dry wt.)	16.7%	16.5%		33.9%	34.4%	
Number of Blows				25	25	

Plastic Limit : 17

Liquid Limit : 34

Plasticity Index : 17
 Unified Soil Classification : CL Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 15-16'
 Sample Description: CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	32.30	25.89		25.61	24.81	
Weight of Dry Soil & Tare (g)	30.23	24.08		21.97	21.57	
Weight of Tare (g)	17.44	13.68		13.88	14.39	
Weight of water (g)	2.07	1.81		3.64	3.24	
Weight of Dry Soil (g)	12.78	10.40		8.09	7.18	
Water Content (% of dry wt.)	16.2%	17.4%		45.0%	45.1%	
Number of Blows				25	25	

Plastic Limit : 17



Liquid Limit : 45

Plasticity Index : 28

Unified Soil Classification : CL

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**

Project Number: **032-20054**

Date Sampled: 12/9/2020

Sampled By: RA

Sample Number:

Sample Location: B10 @ 20-21'

Sample Description: SM-ML

Date Tested: 12/24/2020

Tested By: JM

Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)						
Weight of Dry Soil & Tare (g)						
Weight of Tare (g)						
Weight of water (g)						
Weight of Dry Soil (g)						
Water Content (% of dry wt.)						
Number of Blows						

Plastic Limit : N/D



Liquid Limit : N/D

Plasticity Index : **NON-PLASTIC**

Unified Soil Classification : **NON-PLASTIC**

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204



Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 25-26'
 Sample Description: CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	27.21	26.81		25.96	28.19	
Weight of Dry Soil & Tare (g)	25.53	25.50		22.83	24.72	
Weight of Tare (g)	14.07	16.78		14.25	15.66	
Weight of water (g)	1.67	1.31		3.13	3.47	
Weight of Dry Soil (g)	11.46	8.72		8.59	9.07	
Water Content (% of dry wt.)	14.6%	15.1%		36.5%	38.2%	
Number of Blows				25	25	

Plastic Limit : 15

Liquid Limit : 37

Plasticity Index : 22
 Unified Soil Classification : CL Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**

Project Number: **032-20054**

Date Sampled: 12/9/2020

Sampled By: RA

Sample Number:

Sample Location: B10 @ 30-31'

Sample Description: CH

Date Tested: 12/24/2020

Tested By: JM

Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	28.52	35.11		25.09	24.94	
Weight of Dry Soil & Tare (g)	26.01	32.17		20.82	20.70	
Weight of Tare (g)	13.30	17.17		13.33	13.32	
Weight of water (g)	2.52	2.95		4.26	4.25	
Weight of Dry Soil (g)	12.71	14.99		7.49	7.38	
Water Content (% of dry wt.)	19.8%	19.6%		56.9%	57.5%	
Number of Blows				25	25	

Plastic Limit : 20



Liquid Limit : 57

Plasticity Index : 37

Unified Soil Classification : CH

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 35-36'
 Sample Description: SC-CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	32.30	28.04		25.97	24.69	
Weight of Dry Soil & Tare (g)	30.04	26.01		22.96	22.01	
Weight of Tare (g)	15.65	12.98		13.87	13.79	
Weight of water (g)	2.26	2.03		3.01	2.67	
Weight of Dry Soil (g)	14.39	13.03		9.10	8.23	
Water Content (% of dry wt.)	15.7%	15.6%		33.1%	32.5%	
Number of Blows				25	25	

Plastic Limit : 16



Liquid Limit : 33

Plasticity Index : 17

Unified Soil Classification : CL

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Commerce 220 Distribution Center**

Project Number: **032-20054**

Date Sampled: 12/9/2020

Sampled By: RA

Sample Number:

Sample Location: B10 @ 40-41'

Sample Description: CL

Date Tested: 12/24/2020

Tested By: JM

Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	29.13	31.20		26.02	29.38	
Weight of Dry Soil & Tare (g)	27.34	28.56		22.41	24.90	
Weight of Tare (g)	17.42	13.71		13.87	14.36	
Weight of water (g)	1.79	2.64		3.61	4.48	
Weight of Dry Soil (g)	9.92	14.85		8.54	10.54	
Water Content (% of dry wt.)	18.1%	17.8%		42.2%	42.5%	
Number of Blows				25	25	

Plastic Limit : 18



Liquid Limit : 42

Plasticity Index : 24

Unified Soil Classification : CL

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204



Project: **Commerce 220 Distribution Center**
 Project Number: **032-20054**
 Date Sampled: 12/9/2020 Date Tested: 12/24/2020
 Sampled By: RA Tested By: JM
 Sample Number: Verified By: JG
 Sample Location: B10 @ 45-46'
 Sample Description: CL

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	22.95	35.04		27.11	26.75	
Weight of Dry Soil & Tare (g)	21.45	32.15		23.03	22.82	
Weight of Tare (g)	13.87	16.80		14.03	14.22	
Weight of water (g)	1.50	2.89		4.08	3.94	
Weight of Dry Soil (g)	7.58	15.35		9.01	8.60	
Water Content (% of dry wt.)	19.8%	18.8%		45.3%	45.8%	
Number of Blows				25	25	

Plastic Limit : 19

Liquid Limit : 46

Plasticity Index : 27
 Unified Soil Classification : CL Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:


R - VALUE TEST

ASTM D - 2844 / CAL 301

Project Number : 032-20054
 Project Name : Commerce 220 Distribution Center
 Date : 12/17/2020
 Sample Location/Curve Number : RV#1
 Soil Classification : CL

TEST	A	B	C
Percent Moisture @ Compaction, %			
Dry Density, lbm/cu.ft.	R - Value less than 5 Sample Exuded from bottom of Mold During test		
Exudation Pressure, psi			
Expansion Pressure, (Dial Reading)			
Expansion Pressure, psf			
Resistance Value R			

R - Value at 300 PSI Exudation Pressure	< 5
R - Value by Expansion Pressure	




R - VALUE TEST

ASTM D - 2844 / CAL 301

Project Number : 032-20054
 Project Name : Commerce 220 Distribution Center
 Date : 12/17/2020
 Sample Location/Curve Number : RV#2
 Soil Classification : CL

TEST	A	B	C
Percent Moisture @ Compaction, %			
Dry Density, lbm/cu.ft.	R - Value less than 5 Sample Exuded from bottom of Mold During test		
Exudation Pressure, psi			
Expansion Pressure, (Dial Reading)			
Expansion Pressure, psf			
Resistance Value R			

R - Value at 300 PSI Exudation Pressure	< 5
R - Value by Expansion Pressure	



L


R - VALUE TEST

ASTM D - 2844 / CAL 301

Project Number : 032-20054
 Project Name : Commerce 220 Distribution Center
 Date : 12/17/2020
 Sample Location/Curve Number : RV#3
 Soil Classification : CL

TEST	A	B	C
Percent Moisture @ Compaction, %			
Dry Density, lbm/cu.ft.	R - Value less than 5 Sample Exuded from bottom of Mold During test		
Exudation Pressure, psi			
Expansion Pressure, (Dial Reading)			
Expansion Pressure, psf			
Resistance Value R			

R - Value at 300 PSI Exudation Pressure	< 5
R - Value by Expansion Pressure	



L

APPENDIX B

EARTHWORK SPECIFICATIONS

GENERAL

When the text of the report conflicts with the general specifications in this appendix, the recommendations in the report have precedence.

SCOPE OF WORK: These specifications and applicable plans pertain to and include all earthwork associated with the site rough grading, including but not limited to the furnishing of all labor, tools, and equipment necessary for site clearing and grubbing, stripping, preparation of foundation materials for receiving fill, excavation, processing, placement and compaction of fill and backfill materials to the lines and grades shown on the project grading plans, and disposal of excess materials.

PERFORMANCE: The Contractor shall be responsible for the satisfactory completion of all earthwork in accordance with the project plans and specifications. This work shall be inspected and tested by a representative of Krazan and Associates, Inc., hereinafter known as the Soils Engineer and/or Testing Agency. Attainment of design grades when achieved shall be certified by the project Civil Engineer. Both the Soils Engineer and the Civil Engineer are the Owner's representatives. If the Contractor should fail to meet the technical or design requirements embodied in this document and on the applicable plans, he shall make the necessary readjustments until all work is deemed satisfactory as determined by both the Soils Engineer and the Civil Engineer. No deviation from these specifications shall be made except upon written approval of the Soils Engineer, Civil Engineer or project Architect.

No earthwork shall be performed without the physical presence or approval of the Soils Engineer. The Contractor shall notify the Soils Engineer at least 2 working days prior to the commencement of any aspect of the site earthwork.

The Contractor agrees that he shall assume sole and complete responsibility for job site conditions during the course of construction of this project, including safety of all persons and property; that this requirement shall apply continuously and not be limited to normal working hours; and that the Contractor shall defend, indemnify and hold the Owner and the Engineers harmless from any and all liability, real or alleged, in connection with the performance of work on this project, except for liability arising from the sole negligence of the Owner or the Engineers.

TECHNICAL REQUIREMENTS: All compacted materials shall be densified to a density not less than 90 percent relative compaction based on ASTM Test Method D1557 or CAL-216, as specified in the technical portion of the Soil Engineer's report. The location and frequency of field density tests shall be as determined by the Soils Engineer. The results of these tests and compliance with these specifications shall be the basis upon which satisfactory completion of work will be judged by the Soils Engineer.

SOILS AND FOUNDATION CONDITIONS: The Contractor is presumed to have visited the site and to have familiarized himself with existing site conditions and the contents of the data presented in the soil report.

The Contractor shall make his own interpretation of the data contained in said report, and the Contractor shall not be relieved of liability under the Contract documents for any loss sustained as a result of any variance between conditions indicated by or deduced from said report and the actual conditions encountered during the progress of the work.

DUST CONTROL: The work includes dust control as required for the alleviation or prevention of any dust nuisance on or about the site or the borrow area, or off-site if caused by the Contractor's operation either during the performance of the earthwork or resulting from the conditions in which the Contractor leaves the site. The Contractor shall assume all liability, including court costs of codefendants, for all claims related to dust or windblown materials attributable to his work.

SITE PREPARATION

Site preparation shall consist of site clearing and grubbing and the preparations of foundation materials for receiving fill.

CLEARING AND GRUBBING: The Contractor shall accept the site in this present condition and shall demolish and/or remove from the area of designated project earthwork all structures, both surface and subsurface, trees, brush, roots, debris, organic matter, and all other matter determined by the Soils Engineer to be deleterious or otherwise unsuitable. Such materials shall become the property of the Contractor and shall be removed from the site.

Tree root systems in proposed building areas should be removed to a minimum depth of 3 feet and to such an extent which would permit removal of all roots larger than 1 inch. Tree roots removed in parking areas may be limited to the upper 1½ feet of the ground surface. Backfill of tree root excavations should not be permitted until all exposed surfaces have been inspected and the Soils Engineer is present for the proper control of backfill placement and compaction. Burning in areas which are to receive fill materials shall not be permitted.

SUBGRADE PREPARATION: Surfaces to receive Engineered Fill, building or slab loads shall be prepared as outlined above, excavated/scarified to a depth of 12 inches, moisture-conditioned as necessary, and compacted to 90 percent relative compaction.

Loose soil areas, areas of uncertified fill, and/or areas of disturbed soils shall be moisture-conditioned as necessary and recompact to 90 percent relative compaction. All ruts, hummocks, or other uneven surface features shall be removed by surface grading prior to placement of any fill materials. All areas which are to receive fill materials shall be approved by the Soils Engineer prior to the placement of any of the fill material.

EXCAVATION: All excavation shall be accomplished to the tolerance normally defined by the Civil Engineer as shown on the project grading plans. All over-excavation below the grades specified shall be backfilled at the Contractor's expense and shall be compacted in accordance with the applicable technical requirements.

FILL AND BACKFILL MATERIAL: No material shall be moved or compacted without the presence of the Soils Engineer. Material from the required site excavation may be utilized for construction site fills provided prior approval is given by the Soils Engineer. All materials utilized for constructing site fills shall be free from vegetation or other deleterious matter as determined by the Soils Engineer.

PLACEMENT, SPREADING AND COMPACTION: The placement and spreading of approved fill materials and the processing and compaction of approved fill and native materials shall be the responsibility of the Contractor. However, compaction of fill materials by flooding, ponding, or jetting shall not be permitted unless specifically approved by local code, as well as the Soils Engineer.

Both cut and fill areas shall be surface-compacted to the satisfaction of the Soils Engineer prior to final acceptance.

SEASONAL LIMITS: No fill material shall be placed, spread, or rolled while it is frozen or thawing or during unfavorable wet weather conditions. When the work is interrupted by heavy rains, fill operations shall not be resumed until the Soils Engineer indicates that the moisture content and density of previously placed fill are as specified.

APPENDIX C

PAVEMENT SPECIFICATIONS

1. DEFINITIONS - The term "pavement" shall include asphaltic concrete surfacing, untreated aggregate base, and aggregate subbase. The term "subgrade" is that portion of the area on which surfacing, base, or subbase is to be placed.

The term "Standard Specifications": hereinafter referred to is the 2018 Standard Specifications of the State of California, Department of Transportation, and the "Materials Manual" is the Materials Manual of Testing and Control Procedures, State of California, Department of Public Works, Division of Highways. The term "relative compaction" refers to the field density expressed as a percentage of the maximum laboratory density as defined in the applicable tests outlined in the Materials Manual.

2. SCOPE OF WORK - This portion of the work shall include all labor, materials, tools, and equipment necessary for, and reasonably incidental to the completion of the pavement shown on the plans and as herein specified, except work specifically noted as "Work Not Included."

3. PREPARATION OF THE SUBGRADE - The Contractor shall prepare the surface of the various subgrades receiving subsequent pavement courses to the lines, grades, and dimensions given on the plans. The upper 12 inches of the soil subgrade beneath the pavement section shall be compacted to a minimum relative compaction of 90 percent. The finished subgrades shall be tested and approved by the Soils Engineer prior to the placement of additional pavement courses.

4. UNTREATED AGGREGATE BASE - The aggregate base material shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate base material shall conform to the requirements of Section 26 of the Standard Specifications for Class 2 material, 1½ inches maximum size. The aggregate base material shall be spread and compacted in accordance with Section 26 of the Standard Specifications. The aggregate base material shall be spread in layers not exceeding 6 inches and each layer of aggregate material course shall be tested and approved by the Soils Engineer prior to the placement of successive layers. The aggregate base material shall be compacted to a minimum relative compaction of 95 percent.

5. AGGREGATE SUBBASE - The aggregate subbase shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate subbase material shall conform to the requirements of Section 25 of the Standard Specifications for Class 2 material. The aggregate subbase material shall be compacted to a minimum relative compaction of 95 percent, and it shall be spread and compacted in accordance with Section 25 of the Standard Specifications. Each layer of aggregate subbase shall be tested and approved by the Soils Engineer prior to the placement of successive layers.

6. ASPHALTIC CONCRETE SURFACING - Asphaltic concrete surfacing shall consist of a mixture of mineral aggregate and paving grade asphalt, mixed at a central mixing plant and spread and compacted on a prepared base in conformity with the lines, grades and dimensions shown on the plans. The viscosity grade of the asphalt shall be PG 64-10. The mineral aggregate shall be Type B, ½ inch maximum size, medium grading and shall conform to the requirements set forth in Section 39. The drying, proportioning and mixing of the materials shall conform to Section 39.

The prime coat, spreading and compacting equipment and spreading and compacting mixture shall conform to the applicable chapters of Section 39, with the exception that no surface course shall be placed when the atmospheric temperature is below 50° F. The surfacing shall be rolled with a combination of steel wheel and pneumatic rollers, as described in Section 39-6. The surface course shall be placed with an approved self-propelled mechanical spreading and finishing machine.

7. FOG SEAL COAT - The fog seal (mixing type asphaltic emulsion) shall conform to and be applied in accordance with the requirements of Section 37.