Print From

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: _____

Project Title: SBD 15 Pavement Rehab

Lead Agency: California Department of Transportation (Caltrans) - District 8

Contact Name: Malisa Lieng

Email: SBD15PavementRehab@dot.ca.gov Phone Number: (909) 261-3955

Project Location: Baker / Unincorporated San Bernardino County San Bernardino

City *County*

Project Description (Proposed actions, location, and/or consequences).

Caltrans proposes a multi-asset project with minor pavement rehabilitation improvements on Interstate 15 (I-15) between post mile (PM) R121.0 and PM 144.0 in San Bernardino County. The improvements include 0.15' mill and 0.25' overlay, and 2' shoulder backing on each side of the roadway on the mainline, shoulders, and on/off ramps, from PM R124.4 to PM R137.2. The project would also include upgrading the guardrails, replacing AC dikes, restriping (all lanes), sleeve-lining 6 culverts, rock slope protection (RSP) and guardrail installation at PM R137.67, upgrading 18 sign panels (Type 11), rehabilitating 12 freeway lighting Type 10, 15, 30, and 31, and removing vegetation. All work will be performed within existing Caltrans right of way (ROW).

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

With the following mitigation measures incorporated, the proposed project would have less than significant effects to Biological Resources.

-BIO-Waters 1: Habitat enhancement for temporary impacts.
-BIO-Waters 2: On-site habitat restoration for temporary impacts for native communities.
-BIO-Waters 3: Off-site mitigation banking at a ratio of 3:1 for permanent impacts to native communities.
-BIO-Waters 4: Compensatory Mitigation.
-BIO-General 8: Biological Monitor.
-BIO-Reptile 6: Temporary Demarcation.
-BIO-Reptile 8: Rock Slope Protection.
-BIO-DT 2: Desert Tortoise Translocation.

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

There are no known public controversy areas within the project limits.

Provide a list of the responsible or trustee agencies for the project.

There are no responsible or trustee agencies for the project.