

NOTICE OF INTENT TO ADOPT MITIGATED NEGATIVE DECLARATION /
NOTICE OF AVAILABILITY

The Jamestown Sanitary District is the Lead Agency for and intends to consider adopting a mitigated negative declaration pursuant to Section 21092 and 21092.3 of the Public Resources Code and Section 15072 the California Environmental Quality Act (CEQA) for the following project:

Project Title: Jamestown Sanitary District Wastewater Facilities Upgrades #1 Project

Project Locations:

Wood's Creek Site

17600 SR 49/108, Jamestown, CA

APNS: 059-080-096 (3.73± acres), 059-080-058 (0.07± acre) = 3.8± acres

A portion of Sections 15 & 16, T1N, R14E, MDB&M

Quartz Site

10190 Karlee Lane, Jamestown, CA

APN: 14+- acres of 059-150-027 (31.9± acres)

A portion of Sections 21 and 22, T1N, R14E MDB&M

This project excludes APN: 058-180-055 (31.1± acres)

Project Description:

Quartz WWTF

Install proposed facilities

- Install two tertiary filters capable of treating all influent with one unit out of service.
- Capability to inject chemicals upstream of the filters if filter influent turbidity exceeds 5 NTU for more than 5 minutes, as required by Title 22.
- Piping modifications to integrate proposed facilities into existing WWTF.
- Lined emergency storage pond sized to accommodate at least one day of PWWF, depending on area availability at the Quartz WWTF.
- Pump station to return wastewater from emergency storage pond to treatment facilities.

Improvements to existing facilities

- Addressing accessibility to secondary chlorine contact tank (CCT).
- Adding vertical baffles at the secondary CCT and tertiary CCT to improve modal residence time.
- Upgrading electrical and SCADA programming to integrate proposed facilities into existing WWTF.
- Improving the generator to provide power supply for solids handling and proposed equipment.
- Replacing uninterruptible power supplies (UPSs).
- Improving the electrical conduit connections to reduce potential for water damage of electrical equipment.
- Adding protective measures for outdoor electrical equipment.
- Replacing check valve at on-site pump station.
- Improving the existing sludge dewatering facility
- Providing a contained drainage system to the dewatered cake trailer area.
- Upgrade the sludge dewatering equipment.
- Improving the drying beds by adding a drainage system.
- Adding a flow meter at the discharge of the recycled water pump station.
- Upgrading piping in the chemical storage building.

JSD Wood's Creek WWTF:

Improvements to existing facilities:

- Improving the electrical control panels and main electrical cabinets that are currently exposed to heat, rain, and dust by enclosing the area and adding heating and ventilation controls.
- Improving the grit removal system
 - ✓ increase water pressure capability to system
 - ✓ add canopy for grit dumpster, pump, and control panel with shelter
- Adding protection for the flow meter at the influent pump station.
- Replacing the pumps at existing influent pump station.

Mitigated Negative Declaration - Availability: A copy of the environmental documents (Mitigated Negative Declaration, Initial Study), and supporting documents are available for review at/on the:

Jamestown Sanitary District website: <https://www.jamestownsanitarydistrict.com/>

Comments on the proposed draft Mitigated Negative Declaration should be submitted during the **PUBLIC REVIEW PERIOD STARTING November 15, 2024, AND ENDING December 16, 2024.**

Comments on the Initial Study and proposed Mitigated Negative Declaration should be sent by e-mail to the address below or by mail to

By e-mail: tuolandplanner@gmail.com

PLEASE INCLUDE IN SUBJECT LINE: Jamestown Sanitary District Wastewater Facilities Upgrades

By hand or United States Postal Service:

Augustine Planning Associates, Inc.
270 South Barretta, Suite C
P.O. Box 3117, Sonora, CA 95370
(209) 532-7376

No sites enumerated pursuant to Government Code Section 65962.5 regarding hazardous materials have been identified on site.

/s/Amy Augustine, AICP

Publication Date: November 15, 2024
